

DRAINAGE SCHEDULE

LOCATION	REMOVE EXISTING STRUCTURES	REMOVING CATCH BASINS	PIPE CULVERT REMOVAL	CONCRETE HEADWALL REMOVAL	BOX CULVERT END SECTIONS, NO. 1	BOX CULVERT END SECTIONS, NO 2	PRECAST REINFORCED CONCRETE FLARED END SECTION, 18"	PRECAST REINFORCED CONCRETE FLARED END SECTION, 24"	METAL END SECTIONS, 15"	METAL END SECTIONS, 18"	METAL END SECTIONS, 30"	PIPE CULVERTS, CLASS A, TYPE 1, 18"	PIPE CULVERTS, CLASS A, TYPE 1, 24"	PIPE CULVERTS, CLASS A, TYPE 2, 24"	PIPE CULVERTS, CLASS D, TYPE 1, 15"	PIPE CULVERTS, CLASS D, TYPE 2, 15"	PIPE CULVERTS, CLASS D, TYPE 1, 18"	PIPE CULVERTS, CLASS D, TYPE 2, 30"	PRECAST CONCRETE BOX CULVERTS, 6X2 (SPECIAL)	PRECAST CONCRETE BOX CULVERTS, 10X3 (SPECIAL)	
IL 16																					
STA. 616+50.00, 43.2' RT.											2								45.5		
EX. E. HARRISON AVE.																					
STA. 06+89.55, 28.3' LT.			34.7																		
STA. 07+49.61, 25.1' RT.			27.8																		
STA. 13+86.35, 29.5' RT.				1																	
STA. 13+96.74, AT CL			58.0																		
STA. 14+05.51, 23.6' LT.				1																	
STA. 14+07.63, 34.0' RT.		1																			
STA. 14+07.22, 33.4' RT.			18.0																		
STA. 15+11.31, 35.5' LT.		1																			
STA. 15+11.66, 35.0' LT.			18.0																		
STA. 15+14.64, 23.3' RT.				1																	
STA. 15+23.40, AT CL			58.0																		
STA. 15+34.04, 29.8' LT.				1																	
STA. 21+50.00, 29.8' RT.										2									49.5		
STA. 23+50.00, 32.5' RT.										2									52.3		
STA. 26+47.65 AT CL	1																				
E. HARRISON AVE. (A)																					
STA. 20+89.55 30.7' LT									2							33.0					
STA. 21+49.95 31.7' RT.									2							33.5					
STA. 21+66.65 31.2' LT.									2							40.0					
STA. 26+50.00							2						79.0								
STA. 28+50.00						2													82.0		
E. HARRISON AVE. (B)																					
STA. 50+40.04							2					74.5									
STA. 64+51.44						2														74.0	
STA. 67+89.16 38.8' LT.									2							50.5					
STA. 69+62.15 30.7' RT.									2						26.0						
CONNECTOR RD.																					
STA. 00+40.16								2						75.5							
STA. 02+22.10							2					71.5									
PROJECT TOTALS	1	2	215	4	2	2	4	4	10	4	2	146.0	79.0	75.5	132.5	50.5	102	46	82	74	