

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0040					
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	45	45					
20100500	TREE REMOVAL, ACRES	ACRE	1.4	1.4					
20200100	EARTH EXCAVATION	CU YD	3530	3530					
20400800	FURNISHED EXCAVATION	CU YD	2120	2120					
20800150	TRENCH BACKFILL	CU YD	388	388					
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	914	914					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4532	4532					
25000115	SEEDING, CLASS 1B	ACRE	0.9	0.9					
25000200	SEEDING, CLASS 2	ACRE	1.6	1.6					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	224	224					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	224	224					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	224	224					
25100115	MULCH, METHOD 2	ACRE	2.5	2.5					
25100630	EROSION CONTROL BLANKET	SQ YD	2346	2346					

FILE NAME: I:\G:\M\1015\10823\Work_Drwr_1_M0_Abr_P12\1000_Sheets\10823\10823.dwg

KLINGNER ASSOCIATES, P.C.
Engineers • Architects • Surveyors

USER NAME	- seb	DESIGNED	- seb	REVISED	- 8/27/14 - SEB
PLOT SCALE	= 1/8"=1'-0"	DRAWN	- seb	REVISED	-
PLOT DATE	= 9/29/2014	CHECKED	-	REVISED	-
		DATE	-	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
MISSOURI AVENUE DEEP WELL FACILITY			
SCALE: NONE	SHEET 1	OF 10 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-4T-1	ST. CLAIR	185	4
CONTRACT NO. 76699				
ILLINOIS FED. AID PROJECT				