CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0040					
51100300	SLOPE WALL 6 INCH	SQ YD	4125	4125					
51202100	FURNISHING STEEL PILES HP14X117	FOOT	960	960					
51202305	DRIVING PILES	FOOT	960	960					
51204100	TEST PILE STEEL HP14X117	EACH	1	1					
54248510	CONCRETE COLLAR	CU YD	1	1					
54260311	TRAVERSABLE PIPE GRATE	FOOT	19.3	19.3					
54261327	CONCRETE END SECTION, STANDARD 542001, 27", 1:3	EACH	1	1					
54262315	CONCRETE END SECTION, STANDARD 542006, 15", 1:3	EACH	1	1					
54262318	CONCRETE END SECTION, STANDARD 542006, 18", 1:3	EACH	3	3					
542C0223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	192	192					
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	25	25					
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	36	36					
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	109	109					
56104800	WATER VALVES 4"	EACH	1	1					

FILE NAME = D:\IDOT\Projects\HDR223\Work Order 3 MO Ave PL2\CADD Sheets\0876C99-sht-summary.dgn

KLINGNER & ASSOCIATES, P.C.
Engineers · Architects · Surveyors

USER NAME = sab	DESIGNED - sab	REVISED -
	DRAWN - sab	REVISED -
PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
PLOT DATE = 9/25/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
MISSOURI AVENUE DEEP WELL FACILITY

SCALE: NONE | SHEET 4 OF 10 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-4T-1	ST. CLAIR	185	7

CONTRACT NO. 76099

ILLINOIS FED. AID PROJECT