

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				0040						
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	13	13						
78300100	PAVEMENT MARKING REMOVAL	SQ FT	968	968						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	26	26						
80300100	LOCATING UNDERGROUND CABLE	FOOT	4275	4275						
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	554	554						
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	370	370						
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	564	564						
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	7	7						
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1	1						
87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	614	614						
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	7	7						
87900200	DRILL EXISTING HANDHOLE	EACH	1	1						
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	914	914						
Z0004002	BOLLARDS	EACH	8	8						

FILE NAME: G:\NH\14218203\Met. Order - 3 Mt. Ave. Plot\20140915\Sheet14.dwg



USER NAME - seb	DESIGNED - seb	REVISED -
DRAWN - seb	CHECKED -	REVISED - 9/30/14 - SEB
PLOT SCALE - 40,0000 1/4 in.	DATE -	REVISED -
PLOT DATE - 9/28/2014		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES		
MISSOURI AVENUE DEEP WELL FACILITY		
SCALE: NONE	SHEET 7 OF 10 SHEETS	STA. TO STA.

P.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-4T-1	ST. CLAIR	185	10
CONTRACT NO. 76099			ILLINOIS FED. AID PROJECT	