• (0203.1 & 0312-708W) R-3 CONTRACT NO. 62108

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	•	COOK	870	14
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE	PAY ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE														
			URBAN	ACNHI 90% FED. 10% STATE	ACNHF 80% FED. 20% STATE			ACNHI 90% FED. 10% STATE				ACNHF 80% FED. 20% STATE	ACNHI 90% FED. 10% STATE	ACNHF 80% FED. 20% STATE	ISTHA-ACNHF		ACNHI	
				ROADWAY I-94	ROADWAY IL 394	IL 394 SB OVER I-80 SN-016-2796	IL 394 SB OVER CNRR SN-016-2798	OVER THORN CREEK IL 394 SB SN-016-2800	OVER THORN CREEK I-94 EB SN-016-2807	RETAINING WALL SN-016-W866	CULVERT SN-016-C012	LIGHTING I-94	LIGHTING IL 394	SIGNING I-94	SIGNING IL 394	RAMP F	THORN CREEK OVER IL 394 SB SN-016-2845	VILLAGE OF SOUTH HOLLAND
				J000-2A	J000-2A	X271-2A	X181-2A	X071-2A	X071-2A	Y007	Y007	Y030-1E	Y030-1E	Y002-1C	Y002-1C	J000-2A	X071-2A	Y102
• MX030301	CONDUIT ATTACHED TO STRUCTURE,100MM DIA. GALVANIZED STEEL, PVC COATED	METER	3									3						
△△ MX030355	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ M	2181	2181														
△△ MX030356	NOISE ABATEMENT WALL, STRUCTURE MOUNTED	SQ M	6408	6408														
MX030504	TEMPORARY PAVEMENT (INTERSTATE)	SQ M	1581	608	973													
MX030507	STORM SEWERS AND CULVERTS TO BE GROUTED	CU M	92		92													
MX030523	ERECTING FLOATING BEARINGS, FIXED 1500 KN	EACH	12						12									
• MX032160	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA. PVC, 2 WIDE X 1 HIGH	METER	280									157	123					
• MX032161	CONDUIT ENCASED, REINFORCED CONCRETE, 100MM DIA. PVC, 2 WIDE X 2 HIGH	METER	55										55					
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	135.46	61.61	73.85													
MX032651	MULCH-PLACEMENT 100MM	SQ M	8370		8370													
MX032708	STRIP SEAL EXPANSION JOINT ASSEMBLY	METER	44.7			29.4		15.3										
MX033141	BRIDGE JOINT SYSTEM (EXPANSION), 25MM	METER	15.4				15.4											
MX033183	SOIL STABILIZERS	KG	1501496	305928	1195568	△1												
MX033276	TEMPORARY SOIL RETENTION SYSTEM	SQ M	915.5 △1		775				79 △1		61.5							
MX033290	SEDIMENT CONTROL, SILT FENCE	METER	2877	1814	1063													
MX033291	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	METER	1239	707	532													
MX033292	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ M	900	900														
MX033303	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ M	900	900														
MX033387	CONDUIT ATTACHED TO STRUCTURE, 25MM DIA., RIGID GALVANIZED STEEL, PVC COATED	METER	3									3						
MX355150	BITUMINOUS BASE COURSE SUPERPAVE, 150MM	SQ M	33	33														
MX406012	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	M TON	5	5														
MX406078	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N105	M TON	104	72	32													
MX406210	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-25.0, N105	M TON	42	28	14													
MX407440	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 290MM	SQ M	258	258														
MX482460	BITUMINOUS SHOULDERS SUPERPAVE 330MM	SQ M	492	492														
MX602310	CATCH BASINS, 1.2M BY 0.9M, TYPE 20 FRAME AND GRATE	EACH	7	7														
MX637150	CONCRETE BARRIER, SINGLE FACE, 1065 MM HEIGHT, REINFORCED	METER	1061	550	511													
MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	8937.4	4094.20	4843.20													

• SPECIALTY ITEM
** SFTY-3N
△ Y080
△△ Y220 NOISE ABATEMENT WALL

△1 Rev. 12-5-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND

SUMMARY OF QUANTITIES

HORIZ SCALE: NONE
VERT SCALE: NONE
DATE: JULY 18, 2005
DRAWN BY: JYMC
CHECKED BY: JES

HNTB

J:\34562\cadd\t18\cds\Contract19_SB\sq190104a.dgn
slauer 15-SEP-2005 15:09