• (0203.1 & 0312-708W) R-3 CONTRACT NO. 62108

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	•	COOK	870	16
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE	PAY ITEM	UNIT	TOTAL	ACNHI 90% FED. 10% STATE URBAN	ACNHF 80% FED./20% STATE			ACNHI 90% FED./10% STATE				ACNHF 80% FED. 20% STATE	ACNHI 90% FED. 10% STATE	ACNHF 80% FED. 20% STATE	ISTHA-ACNHF	ACNHI	
				ROADWAY I-94	ROADWAY IL 394	IL 394 SB OVER I-80 SN-016-2796	IL 394 SB OVER CNRR SN-016-2798	OVER THORN CREEK SN-016-2800	IL 394 SB OVER THORN CREEK SN-016-2807	I-94 EB RETAINING WALL SN-016-W866	CULVERT SN-016-C012	LIGHTING I-94	LIGHTING IL 394	SIGNING I-94	SIGNING IL 394	RAMP F	THORN CREEK SN-016-2845 IL 394 SB OVER SOUTH HOLLAND	VILLAGE OF
				CONSTRUCTION TYPE CODE													
				J000-2A	J000-2A	X271-2A	X181-2A	X071-2A	X071-2A	Y007	Y007	Y030-1E	Y030-1E	Y002-1C	Y002-1C	J000-2A	X071-2A	Y082
Z0002600	BAR SPLICERS	EACH	464			98	89	120	98		59							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.44	0.53											0.03		
** Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	5	3	2													
** Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2		2													
** Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	1	1													
** Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1														
** Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2		2													
** Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	27	5	22													
** Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4		4													
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1				1											
△ Z0076600	TRAINEES	HOUR	500	250	250													
TWY00010	ROADWAY EXCAVATION, COMMON	CU M	14005													14005		
TWY00020	ROADWAY EXCAVATION, UNCOMMON	CU M	1685													1685		
TWY00040	STRUCTURE EXCAVATION, COMMON	CU M	154														154	
TWY00050	EMBANKMENT, ZONE A	CU M	8645													8645		
TWY00060	EMBANKMENT, ZONE B	CU M	7960													7960		
TWY00070	POROUS GRANULAR BACKFILL	CU M	124													78	46	
TWY00080	SELECTED SUBGRADE	CU M	739													739		
TWY00140	RIPRAP, HAND-LAID	SQ M	164													16	148	
TWY00160	GRANULAR SUBBASE	CU M	522													522		
TWY00180	PORTLAND CEMENT CONCRETE PAVEMENT (300MM)	SQ M	1747													1747		
TWY00220	BITUMINOUS MATERIALS (TACK)	LITER	85													85		
TWY00250	BITUMINOUS CONCRETE SHOULDERS (150MM)	SQ M	1517													1517		
TWY00370	STUD-TYPE SHEAR CONNECTORS	EACH	6093														6093	
TWY00380	FURNISHING AND ERECTING STRUCTURAL STEEL (MISCELLANEOUS)	KG	111														111	
TWY00400	REINFORCING STEEL, EPOXY COATED	KG	30531													731	29800	
TWY00410	FURNISHING STEEL PILES	METER	425														425	
TWY04113	DRIVING STEEL PILES	EACH	28	△1													28	△1

• SPECIALTY ITEM
•• SFTY-3N
△ Y080
△△ Y220 NOISE ABATEMENT WALL

△1 Rev. 12-5-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND

SUMMARY OF QUANTITIES

HORIZ SCALE: NONE
VERT SCALE: NONE
DATE: JULY 18, 2005

DRAWN BY: JYMC
CHECKED BY: JES

HNTB

jn@345628@cadd@t1@cds@Contract19_SB@sq190124a.dgn
slauer 15-SEP-2005 15:08