• (0203.1 & 0312-708W) R-3 CONTRACT NO. 62108

F.A.I. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	•	COOK	870	7
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE	PAY ITEM	UNIT	TOTAL	ACNHI 90%FED./10%STATE URBAN ROADWAY I-94	ACNHF 80%FED./20%STATE ROADWAY IL 394	ACNHF 80%FED./20%STATE IL 394 SB OVER I-80 SN-016-2796	ACNHF 80%FED./20%STATE IL 394 SB OVER CNRR SN-016-2798	ACNHI 90%FED./10%STATE IL 394 SB OVER THORN CREEK SN-016-2800	ACNHI 90%FED./10%STATE I-94 EB OVER THORN CREEK SN-016-2807	ACNHI 90%FED./10%STATE RETAINING WALL SN-016-W866	ACNHI 90%FED./10%STATE CULVERT SN-016-C012	ACNHF 80%FED./20%STATE LIGHTING I-94	ACNHI 90%FED./10%STATE LIGHTING IL 394	ACNHF 80%FED./20%STATE SIGNING I-94	ACNHF 80%FED./20%STATE SIGNING IL 394	ISTHA-ACNHF RAMP F THORN CREEK SN-016-2845	ACNHI IL 394 SB OVER SOUTH HOLLAND	ACNHI VILLAGE OF SOUTH HOLLAND
				CONSTRUCTION TYPE CODE														
				J000-2A	J000-2A	X271-2A	X181-2A	X071-2A	X071-2A	Y007	Y007	Y030-1E	Y030-1E	Y002-1C	Y002-1C	J000-2A	X071-2A	Y102
M2020010	EARTH EXCAVATION	CU M	75782	22176	53606													
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	7930	3004	3889						1037							
M2040800	FURNISHED EXCAVATION	CU M	43031	10920	32111													
M2070220	POROUS GRANULAR EMBANKMENT	CU M	207				165				42							
M2070400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU M	1381			185		266	791		139							
M2070420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU M	100															
M2080150	TRENCH BACKFILL	CU M	5272	2253	3019													
M2090410	SAND BACKFILL	CU M	25	25														
M2101000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ M	86042	43354	42688													
M2113150	TOPSOIL FURNISH AND PLACE, 150MM	SQ M	48613	16112	32501													
M2113300	TOPSOIL FURNISH AND PLACE, 300MM	SQ M	16528	16528														
M2114100	COMPOST FURNISH AND PLACE, 100MM	SQ M	124980	21233	103747													
M2500210	SEEDING, CLASS 2A	HA	3.8	0.5	3.3													
M2500310	SEEDING, CLASS 4	HA	10.8	1.7	9.1													
M2500314	SEEDING, CLASS 4B	HA	1.4		1.4													
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	1463	100	1363													
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	1463	100	1363													
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	1463	100	1363													
□ M2500750	MOWING	HA	2	2														
M2510115	MULCH, METHOD 2	HA	17.2	3.5	13.7													
M2510630	EROSION CONTROL BLANKET	SQ M	132604	10098	122506													
M2520110	SODDING, SALT TOLERANT	SQ M	16528	16528														
M2520200	SUPPLEMENTAL WATERING	UNIT	4621	229	4392													
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	1770	269	1501													
M2810107	STONE RIPRAP, CLASS A4	SQ M	2404	6	16			802	1580									
M2820200	FILTER FABRIC	SQ M	2920	6	16			1040	1858									
M3111300	SUB-BASE GRANULAR MATERIAL, TYPE B 300MM	SQ M	86042	43354	42688													
M3120100	STABILIZED SUB-BASE 100MM	SQ M	5821	2226	3595													

• SPECIALTY ITEM
•• SFTY-3N
△ Y080
△△ Y220 NOISE ABATEMENT WALL
□ NON-PARTICIPATING

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-94 EAST BOUND / IL 394 SOUTH BOUND

SUMMARY OF QUANTITIES

HORIZ SCALE: NONE
VERT SCALE: NONE
DATE: JULY 18, 2005
DRAWN BY: JYMC
CHECKED BY: JES

HNTB

jobs345628\cadd\118\cdas\Contract19_SBB\sq190034a.dgn
slauer 15-SEP-2005 15:11