

F.A.L. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	870	42
STA.		TO STA.		
FED ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

DRAINAGE SCHEDULE - REMOVAL

LOCATION	CONCRETE HEADWALL REMOVAL	CATCH BASINS TO BE ADJUSTED	MANHOLES TO BE ADJUSTED	MANHOLES TO BE ADJUSTED W/ T8 G	MANHOLES TO BE RECONSTRUCTED	MANHOLES TO BE RECONSTRUCTED W/ NEW T1F, CL	FRAMES AND GRATES TO BE ADJUSTED	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS
	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
I-94	18+363 TO 18+725	0	1	0	0	0	2	0	6	3
	18+725 TO 19+050	1	0	0	0	0	6	1	1	11
	19+050 TO 19+350	0	0	0	0	0	4	0	1	6
	19+350 TO 19+700	0	0	0	0	0	8	0	4	7
	19+700 TO 20+000	0	0	0	0	0	8	3	3	4
I-94 EB	20+625 TO 20+925	0	0	0	0	0	0	3	0	0
I-94 SUBTOTAL		1	1	0	0	0	28	7	15	31
IL 394	38+265 TO 38+615	0	0	1	2	0	0	0	1	0
	38+615 TO 38+865	0	2	1	0	0	0	0	1	0
	38+865 TO 39+240	0	2	0	0	0	0	0	2	0
	39+240 TO 39+600	0	4	2	0	2	0	0	1	0
	39+600 TO 39+850	0	0	2	0	0	0	0	0	2
	39+850 TO 440+200	0	0	0	0	0	0	1	2	13
	400+200 TO 440+525	0	0	0	0	0	0	11	2	8
	440+525 TO 40+835	1	0	0	0	0	0	1	0	3
	440+900 TO 441+167.161	0	0	0	0	0	0	2	3	1
	IL 394 SUBTOTAL		1	8	6	2	5	0	15	12
TOTAL		2	9	6	2	5	28	22	27	58

LOCATION	TRENCH BACKFILL	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL 300MM	STORM SEWER REMOVAL 375MM	STORM SEWER REMOVAL 450MM	STORM SEWER REMOVAL 525MM	STORM SEWER REMOVAL 600MM	STORM SEWER REMOVAL 750MM	STORM SEWERS AND CULVERTS TO BE GROUTED	END SECTIONS TO BE REMOVED
	CU M	EACH	METER	METER	METER	METER	METER	METER	CU M	EACH
I-94	18+363 TO 18+725	226.6	0	281.5	0	0	0	0	0	0
	18+725 TO 19+050	121.4	77.4	150.7	0	0	0	0	0	0
	19+050 TO 19+350	54.8	0	67.9	0	0	0	0	0	0
	19+350 TO 19+700	208.8	0	259.3	0	0	0	0	0	0
	19+700 TO 20+000	342.3	0	229.8	0	21.8	18.0	0	89.4	0
I-94 EB	20+625 TO 20+925	83.4	0	0.0	7.2	0	47.7	0	0	1
I-94 SUBTOTAL		1038	77.5	989.5	7.5	22.0	18.0	48.0	89.5	1
IL 394	38+265 TO 38+615	46.0	0	127.9	0	36.6	0	0	2	0
	38+615 TO 38+865	36.7	0	0.0	0	29.2	0	0	0	0
	38+865 TO 39+240	53.5	0	30.0	0	0	0	0	0	0
	39+240 TO 39+600	122.4	0	79.8	28.6	46.2	0	0	0	2
	39+600 TO 39+850	67.8	0	37.3	0	0	0	0	0	0
	39+850 TO 440+200	480.3	0	192.3	36.6	90.2	0	0	82.9	0
	400+200 TO 440+525	1027.2	0	288.2	206.8	175.5	0	233.3	0	2
	440+525 TO 40+835	248.1	0	0.0	101.9	0	0	24.0	0	1
	440+900 TO 441+167.161	210.5	0	126.2	182.2	0	21.0	0	30.9	0
	IL 394 SUBTOTAL		2293	0	882.0	556.5	378.0	21.0	257.5	31.0
TOTAL		3331	77.5	1871.5	563.5	400.0	39.0	305.5	120.5	6

SC-3

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-94 EAST BOUND / IL 394 SOUTH BOUND

SCHEDULE OF QUANTITIES

HORIZ SCALE:  
VERT SCALE:  
DATE: JULY 18, 2005

DRAWN BY: BJM  
CHECKED BY: JES

**HNTB**

REVISIONS	
NAME	DATE

NOTE:  
THE SCHEDULES ON THIS PAGE MAY NOT REFLECT  
ITEMS QUANTIFIED BETWEEN:  
• I-94 EB STA. 20+657.900 TO STA. 21+222.210,  
• I-94 WB STA. 30+785.473 TO STA. 31+020.000, AND  
• MDTPE94 STA. 25+178.451 TO STA. 25+516.450