

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-2	COOK/LAKE	1207	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62114		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE								VILLAGE OF LANSING *****	LANSING Y007 *****	
				ROADWAY ILLINOIS ..	LIGHTING- ILLINOIS ..	SURVEIL- LANCE ILLINOIS ..	SIGNING ILLINOIS ..	ROADWAY INDIANA	LIGHTING INDIANA	SURVEIL- LANCE INDIANA	SIGNING INDIANA			Y060
M5503200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS II, 1950MM	METER	203.4	203.4	0	0	0	0	0	0	0	0		
M5504800	STORM SEWERS TO BE CLEANED	METER	944	0	0	0	0	944	0	0	0	0		
M5505570	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 600MM	METER	12	0	0	0	0	0	0	0	0	0	12	
M5510015	STORM SEWER REMOVAL 200MM	METER	63.9	63.9	0	0	0	0	0	0	0	0		
M5510025	STORM SEWER REMOVAL 300MM	METER	2387.2	1078.4	0	0	0	1281.8	0	0	0	0	27	
M5510035	STORM SEWER REMOVAL 375MM	METER	462.5	136.5	0	0	0	326	0	0	0	0		
M5510045	STORM SEWER REMOVAL 450MM	METER	222.3	0	0	0	0	222.3	0	0	0	0		
M5510060	STORM SEWER REMOVAL 600MM	METER	159.6	56.7	0	0	0	88.9	0	0	0	0	12	
M5510070	STORM SEWER REMOVAL 750MM	METER	37.4	0	0	0	0	37.4	0	0	0	0		
M5510100	STORM SEWER REMOVAL 1350MM	METER	56	56	0	0	0	0	0	0	0	0		
* M5611210	TAPPING VALVES AND SLEEVES 150MM	EACH	1	0	0	0	0	0	0	0	0	0	1	
M6010110	PIPE DRAINS 150MM	METER	33.1	0	0	0	0	33.1	0	0	0	0		
M6010610	PIPE UNDERDRAINS 150MM	METER	4204.5	4204.5	0	0	0	0	0	0	0	0		
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	0	0	0	0	0	0	0	0		
M6021610	MANHOLES, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	0	0	0	0	0	0	0	0		
M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	0	0	0	0	0	0	0	0		
* M6024410	VALVE VAULTS, TYPE A, 1.5M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	0	0	0	0	0	0	0	0	0	1	
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	60	0	0	0	0	0	0	0	0	0	60	
M6061500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-22.45	METER	13	13	0	0	0	0	0	0	0	0		
M6063610	CONCRETE MEDIAN SURFACE, 100MM (SPECIAL)	SQ M	125	125	0	0	0	0	0	0	0	0		
M6320030	GUARDRAIL REMOVAL	METER	1227.9	340	0	0	0	887.9	0	0	0	0		
M6370175	CONCRETE BARRIER, SINGLE FACE, 1065 MM HEIGHT	METER	125.8	125.8	0	0	0	0	0	0	0	0		
M6370275	CONCRETE BARRIER, DOUBLE FACE, 1065 MM HEIGHT	METER	1053.2	1053.2	0	0	0	0	0	0	0	0		
M6370805	CONCRETE BARRIER TRANSITION	METER	35.2	35.2	0	0	0	0	0	0	0	0		
M6371050	BARRIER BASE	METER	1327	1327	0	0	0	0	0	0	0	0		
* M6380600	MODULAR GLARE SCREEN SYSTEM	METER	4881	1686	0	0	0	3195	0	0	0	0		
M6420015	SHOULDER RUMBLE STRIP	METER	4552	4552	0	0	0	0	0	0	0	0		
* M6690100	BACKFILL PLUGS	CU M	7	7	0	0	0	0	0	0	0	0		
M6690400	SPECIAL WASTE GROUND WATER DISPOSAL	LITER	11088	11088	0	0	0	0	0	0	0	0		
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	2175	2175	0	0	0	0	0	0	0	0		
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	17100.6	5396.6	0	0	0	11704	0	0	0	0		
M7030530	PAVEMENT MARKING TAPE, TYPE III 125MM	METER	3359.1	1347.6	0	0	0	2011.5	0	0	0	0		
M7030550	PAVEMENT MARKING TAPE, TYPE III 200MM	METER	328.3	0	0	0	0	328.3	0	0	0	0		

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA
- • • • 100% VILLAGE OF LANSING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SUMMARY OF QUANTITIES

SCALE _____ DRAWN BY ACE/CAD
DATE 07/05 CHECKED BY TAE



Rev. 12-5-05