

## DISTRICT 2 STANDARDS

4-13-16

### FULL SIZE

- 1.1 Deleted 4-15-15
- 3.1 Mailbox Turnout in Curb and Gutter Section
- 4.1 PC Concrete Islands and Medians Accessible to the Disabled
- 5.1 Standard Outlet for Curb and Gutter
- 10.1 Box Culvert End Sections
- 11.1 Concrete End Sections for Parallel Pipe Culverts 15" thru 84" Dia.
- 12.1 Concrete End Sections for Parallel Pipe Arch Culverts 15" thru 84" Dia.
- 13.1 Traversable Pipe Grate for Box Culvert End Section
- 14.1 Traversable Pipe Grate for Parallel Drainage Structure
- 15.1 Sloped Metal End Sections with Grate
- 20.1 Hot-Mix Asphalt Approaches and Mailbox Returns
- 25.1 Entrance Approaches – Urban Area
- 32.1 Sewer and Water Main Crossings
- 33.1 Concrete Collars for Pipe or Box Culvert Extensions
- 34.1 Work Zone Sign Details
- 35.1 Urban Lane Inside Closure, Multilane, 2W, with Mountable Median
- 36.1 Temporary Road Closure Expressway
- 37.1 Traffic Control for Three Lane Section
- 38.1 Traffic Control for Transition Areas
- 39.1 Traffic Control Typical Weave
- 40.1 Traffic Control for Road Closure
- 41.1 Typical Pavement Markings
- 44.1 Painting Details
- 53.1 Remove and Re-erect Steel Plate Beam Guardrail
- 54.1 Traffic Barrier Terminal, Type 2 (27" height)
- 68.1 Slotted Drain Pipe (Variable Height)
- 71.1 Detail of Flood Gate
- 72.1 40' Single Lane Median Crossover (45 mph Work Zone Speed Limit)
- 73.1 50' Single Lane Median Crossover (45 mph Work Zone Speed Limit)
- 74.1 64' Single Lane Median Crossover (45 mph Work Zone Speed Limit)
- 75.1 40' Single Lane Median Crossover (55 mph Work Zone Speed Limit)
- 76.1 50' Single Lane Median Crossover (55 mph Work Zone Speed Limit)
- 77.1 64' Single Lane Median Crossover (55 mph Work Zone Speed Limit)
- 78.1 88' Single Lane Median Crossover (55 mph Work Zone Speed Limit)
- 79.1 40' Two Lane Median Crossover (45 mph Work Zone Speed Limit)
- 80.1 50' Two Lane Median Crossover (45 mph Work Zone Speed Limit)
- 81.1 64' Two Lane Median Crossover (45 mph Work Zone Speed Limit)
- 82.1 40' Two Lane Median Crossover (55 mph Work Zone Speed Limit)
- 83.1 50' Two Lane Median Crossover (55 mph Work Zone Speed Limit)
- 84.1 64' Two Lane Median Crossover (55 mph Work Zone Speed Limit)
- 85.1 88' Two Lane Median Crossover (55 mph Work Zone Speed Limit)
- 86.1 Beveled Pipe & Guard Detail for Median Crossover
- 90.1 Traffic Barrier Terminal, Type 6B (Special)
- 92.1 Details of Planting and Bracing Trees

## District 2 Standards Designer Notes

4-13-16

### Full Size District 2 Standards

- 1.1 Deleted 4-15-15
- 3.1 Use when a mailbox turnout is needed in a curb & gutter section and there isn't a parking lane or a mail delivery lane.
- 4.1 Use this when there are cross walks that will go through an island or median. Specify which option the contractor is required to use when building the Concrete Median (Special).
- 5.1 Use this when you need an outlet for curb and gutter, other than type B-6.24
- 10.1 This is to be used whenever we have a precast box culvert.
- 11.1 This is to be used for pipe culverts, Class D under all sideroads.
- 12.1 This is to be used for EQRS pipe culverts, Class D under all sideroads.
- 13.1 Use this whenever a cross drainage box culvert end section needs traversable pipe grates. Also include Standard 542311.
- 14.1 Use this whenever you use District Standards 10.1, 11.1 & 12.1 and the culvert is within the main line clear zone.
- 15.1 Use this when a Class D pipe culvert is under an entrance the culvert is within the main line clear zone.
- 20.1 Include for rural entrances and sideroads on 3R projects, reconstruction projects, or for new entrances. Do not include on 3P or Smart resurfacing projects.
- 25.1 Include for urban entrances with curb & gutter on 3R projects, reconstruction projects, or for new entrances. Do not include on 3P or Smart resurfacing projects.
- 32.1 Include in urban projects with proposed storm sewers or water mains.
- 33.1 Use this for pipe or box culvert extensions. Fill in the information in the table for the Bill of Materials.
- 34.1 Work Zone Sign Details. Include this when you have any of the following:
- Include in projects where the clear width through a work zone with temporary concrete barrier wall will be 16.0 feet or less.
  - Include when using Traffic Control and Protection Standard 701316 or 701321.
  - Use this in conjunction with the special provision Traffic Control for Narrow Lanes which is under the Traffic Control Plan. Use this on one-lane stage construction jobs when the lane is less than 13'-6" measured from the toe of the barrier wall to the guardrail or bridge wall.
  - Use this when using District Standard 37.1 and 38.1.
  - Use this on low volume entrances that are between the traffic signals on Highway Standard 701316 or 701321.
  - Include this for any milling of the mainline pavement.

## District 2 Standards Designer Notes


4-13-16

- 35.1 Use this when it is necessary to close the inside lane on an urban project. Also include Highway Standard 701606 and the pay item for 701606.
- 36.1 Use this district standard for any short term closure of an expressway at a diamond interchange.
- 37.1 Use this district standard for work that will require a lane closure in a three lane section such as a truck climbing lane.
- 38.1 Use this district standard when there is a transition from a four lane section that transitions to a two lane section.
- 39.1 Include on 4 lane highways where the contractor may change a portion of the work to the opposite lane.
- 40.1 Include for a mainline road closure.
- 41.1 Include in projects with pavement marking or raised reflective pavement markers.
- 44.1 Include in projects with pavement marking on entrance and exit ramps & cloverleafs.
- 53.1 Use this to remove and re-erect an old type steel plate beam guardrail which has 6" block outs and a 27½" rail height.
- 54.1 Use this when installing a Traffic Barrier Terminal, Type 2 on the old type of steel plate beam guardrail with a 27½" rail height.
- 68.1 This can be used to increase drainage in curb & gutter with very flat grades (less than 0.3%). Also include this when constructing median crossovers.
- 71.1 Use if a property owner has a fenced field with livestock and a stream or river. The flood gate will be placed near the right-of-way to prevent livestock from leaving the field through the waterway. During high water, the flood gate will open to let water and debris through.
- 72.1, 73.1, 74.1, 75.1, 76.1, 77.1, 78.1 Use on single lane median crossovers of the median width specified and for the work zone speed limit. Include District Standard 86.1. If there are overlays on the existing PCC pavement, installing tie bars into the existing PCC pavement will not work. Talk to the Construction Field Engineer or your Project Engineer for more information.
- 79.1, 80.1, 81.1, 82.1, 83.1, 84.1, 85.1 Use on two lane median crossovers of the median width specified and for the work zone speed limit. Include District Standard 86.1. If there are overlays on the existing PCC pavement, installing tie bars into the existing PCC pavement will not work. Talk to the Construction Field Engineer or your Project Engineer for more information.
- 86.1 Include this on median crossovers, District Standards 72.1, 73.1, 74.1, 75.1, 76.1, 77.1, 78.1, 79.1, 80.1, 81.1, 82.1, 83.1, 84.1, & 85.1.


## District 2 Standards Designer Notes

- 90.1 Use this on 4-lane highways that go under dual structures and the piers required shielding. The outside of the piers are shielded with impact attenuators. The gap between the piers is shielded using Traffic Barrier Terminal Type 6B (Special). The Traffic Barrier Terminal Type 6B (Special) is required on both sides of the piers.  
Design Note: The **length** of the double thrie beam between the piers **must be added on the elevation on the District Standard.**
- 92.1 Include when planting new ball & burlapped trees.


# MAILBOX TURNOUT IN CURB AND GUTTER SECTION




COMMERCIAL ENTRANCE WITH MAIL BOX TURNOUT



MAIL BOX TURNOUT



PRIVATE ENTRANCE WITH MAIL BOX TURNOUT



TYPICAL CROSS SECTION


## GENERAL NOTES

- 1.) THE LONGITUDINAL CURB EXPANSION JOINT SHALL CONFORM TO SECTION 1051 OF THE STANDARD SPECIFICATIONS.
- 2.) THE MAILBOX TURNOUT CROSS SLOPE WILL BE AS SHOWN ABOVE, AS SHOWN ON THE STATION CROSS SECTIONS OR AS DIRECTED BY THE ENGINEER.
- 3.) THE MAILBOX TURNOUT SHALL BE CONSTRUCTED WITH SCORED GROOVES, AS SPECIFIED IN ARTICLE 423.06 OF THE STANDARD SPECIFICATIONS, AT APPROXIMATELY 10 FT. CENTERS. IN THE EVENT THERE IS EXISTING OR PROPOSED SIDEWALK PRESENT, THESE SCORED GROOVES SHALL BE PLACED IN LINE WITH EVERY OTHER JOINT IN THE ADJACENT SIDEWALK.
- 4.) THE WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD FOR P.C. CONCRETE DRIVEWAY PAVEMENT OF THE THICKNESS SPECIFIED IN THE PLANS WHICH PRICE SHALL INCLUDE THE LONGITUDINAL CURB EXPANSION JOINT, MONOLITHIC CURB AS SHOWN, SCORED GROOVES, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 5.) SEE THE DISTRICT STANDARD 25.1 FOR ADDITIONAL DETAILS.


ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 10-17-11 REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								


# PC CONCRETE ISLANDS AND MEDIANS ACCESSIBLE TO THE DISABLED




SIDE CURB DETAIL




TYPICAL PLAN OF MEDIAN ISLAND




LARGE ISLAND  
(Free Flow Design)




INTERMEDIATE ISLAND  
(For Right Turn Lane Design)




SMALL ISLAND  
(For Typical Design)



SECTION A-A



SECTION B-B



OPTION 2

General Notes:  
See Standard 606301 and plan sheets for station & offsets, radii, dimensions, and details not shown.

See Standard 424031 for sidewalk details not shown.

The sidewalk should drain to the low side of the island. If necessary the sidewalk shall be sloped to drain at 1%.

See the plan general notes for the type of curb & gutter to be used on islands.

The sidewalk should not be closer than 36 from the corner of the island.

Keyed longitudinal construction joints shall be constructed without tie bars.

Medians and large islands shall consist of PCC Sidewalk 5, Concrete Median Surface 4, and Combination Concrete Curb & Gutter, Type M or B of the size specified. Median island can also be solid concrete medians.

Locations, layouts, and widths of the flush sidewalk area, shall be determined by the designer and shown on the plans.

The intermediate and small islands will be measured for payment from E.O.P. to E.O.P. using either option 1 or option 2, as specified in the plans, and will be paid for at the contract unit price per SQ FT for CONCRETE MEDIAN (SPECIAL) which shall include the combination curb & gutter, sidewalk, aggregate fill, concrete median surface, and solid concrete median.

Omit detectable warnings when distance between back of curbs is less than 6'.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14
	PLOT SCALE = 1:10000 ' / in.	CHECKED -	REVISED - 8-27-13
	PLOT DATE = 1/18/2017	DATE -	REVISED - 10-09-12


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# STANDARD OUTLET FOR CURB & GUTTER



**NOTES**

Class SI Concrete shall be used throughout.

Tie bars shall be No. 6 at 24 centers unless otherwise shown.

Gutter outlet shall be tied to the pavement in accordance with details for longitudinal construction joint shown on Standard 420001.

If the average grade of pavement for the distance from Section A-A to D-D exceeds 2%, this distance shall be increased 6' for each 1% increase in grade.

When curb and gutter is constructed adjacent to flexible pavement, a 1 expansion joint shall be installed at construction joints.

All dimensions are in inches unless otherwise shown.

**QUANTITY**

For Section F-F =  
0.069 cu. yds.  
concrete per ft.

TYPE OF CURB & GUTTER	TABLE OF DIMENSIONS															CONCRETE QUANTITY A-A TO E-E AND CURTAIN WALL FOR 9 PAV'T (CU YDS)	CONCRETE QUANTITY A-A TO E-E AND CURTAIN WALL FOR 10 PAV'T (CU YDS)		
	A	SECTION A-A				SECTION B-B				SECTION C-C				R <sub>1</sub>	R <sub>2</sub>			R <sub>3</sub>	
		B	C	D	E	F	G	H	I	J	K	L	M						N
B-6.12	6	6	1	12	3	7 <sup>7</sup> / <sub>8</sub>	13 <sup>3</sup> / <sub>4</sub>	2 <sup>3</sup> / <sub>4</sub>	4	3	12 <sup>7</sup> / <sub>8</sub>	26 <sup>1</sup> / <sub>2</sub>	5	6	1	2	8	1.87	1.89
B-6.18	6	6	1	18	3 <sup>3</sup> / <sub>4</sub>	9 <sup>1</sup> / <sub>4</sub>	22	3	5	3 <sup>1</sup> / <sub>2</sub>	14 <sup>1</sup> / <sub>4</sub>	28 <sup>3</sup> / <sub>4</sub>	5 <sup>1</sup> / <sub>8</sub>	5 <sup>1</sup> / <sub>2</sub>	1	4	10	2.18	2.20
M-4.06	4	3	4	6	3	9 <sup>1</sup> / <sub>2</sub>	10 <sup>1</sup> / <sub>2</sub>	2	4	3	13	25	3	6	3	5	11	1.78	1.79
M-4.12	4	3	4	12	3 <sup>1</sup> / <sub>8</sub>	9 <sup>3</sup> / <sub>4</sub>	13 <sup>3</sup> / <sub>4</sub>	2 <sup>3</sup> / <sub>4</sub>	6	3	13 <sup>1</sup> / <sub>2</sub>	26 <sup>1</sup> / <sub>2</sub>	5	6	3	5	9	1.89	1.91
M-4.18	4	3	4	18	3 <sup>1</sup> / <sub>2</sub>	9 <sup>1</sup> / <sub>4</sub>	22	3	5	3 <sup>1</sup> / <sub>2</sub>	14 <sup>1</sup> / <sub>4</sub>	28 <sup>3</sup> / <sub>4</sub>	5 <sup>1</sup> / <sub>8</sub>	5 <sup>1</sup> / <sub>2</sub>	3	4	10	2.11	2.13
M-4.24	4	3	4	24	5	11 <sup>1</sup> / <sub>2</sub>	26	3 <sup>3</sup> / <sub>8</sub>	4	3 <sup>3</sup> / <sub>4</sub>	15	38	5 <sup>3</sup> / <sub>8</sub>	5	3	6	12	2.34	2.37
M-6.06	6	2	6	6	2 <sup>1</sup> / <sub>4</sub>	9 <sup>3</sup> / <sub>4</sub>	10 <sup>1</sup> / <sub>2</sub>	2	4	2 <sup>1</sup> / <sub>2</sub>	13	25	3	6	2	5	10	1.84	1.86
M-6.12	6	2	6	12	3 <sup>1</sup> / <sub>2</sub>	8 <sup>1</sup> / <sub>8</sub>	13 <sup>3</sup> / <sub>4</sub>	2 <sup>3</sup> / <sub>4</sub>	6	3	13 <sup>1</sup> / <sub>2</sub>	26 <sup>1</sup> / <sub>2</sub>	5	6	2	2	9	1.96	1.98
M-6.18	6	2	6	18	3 <sup>1</sup> / <sub>2</sub>	9 <sup>7</sup> / <sub>8</sub>	22	3	5	3 <sup>1</sup> / <sub>2</sub>	14 <sup>1</sup> / <sub>4</sub>	28 <sup>3</sup> / <sub>4</sub>	5 <sup>1</sup> / <sub>8</sub>	5 <sup>1</sup> / <sub>2</sub>	2	4	10	2.18	2.20
M-6.24	6	2	6	24	5 <sup>1</sup> / <sub>8</sub>	11	26	3 <sup>3</sup> / <sub>8</sub>	4	3 <sup>3</sup> / <sub>4</sub>	17 <sup>3</sup> / <sub>4</sub>	38	5 <sup>3</sup> / <sub>8</sub>	5	2	3 <sup>1</sup> / <sub>4</sub>	16	2.46	2.49

# BOX CULVERT END SECTIONS

## GENERAL NOTES

Box Culvert End Sections shall be constructed according to the requirements of Section 540 of the Standard Specifications except as modified herein. This work will be measured for payment as each, with each end of each culvert being one each. End sections will be paid for at the contract unit price per each for Box Culvert End Sections of the culvert number specified.

Typical box section dimensions, materials, and reinforcement details for Box Culvert End Sections shall be according to the requirements of ASTM C 1577 as required for the design of the portion of the culvert within the limits of Precast Concrete Box Culverts except as modified herein.

Number of segments shown in Side Elevation is for example only. Length and number of precast box sections required to construct Box Culvert End Sections shall be determined by the Contractor.

\*\*See roadway plans for embankment slope (V:H). The Slope Must Match.

1"  $\emptyset$  anchor rods for the culvert ties shall conform to the requirements of ASTM F1554, Grade 105. Structural steel for tie plate and restraint angle shall conform to the requirements of Article 1006.04 of the Standard Specifications. All components of the culvert tie detail shall be galvanized according to the requirements of AASHTO M 111 or M 232 as applicable.  $2\frac{1}{4}" \times 2\frac{1}{4}" \times \frac{5}{16}"$  plate washers shall be provided under each nut required for the anchor rods. Anchor rods connecting precast sections shall be brought to a snug tight condition followed by an additional  $\frac{1}{2}$  turn on one of the nuts. Match marks shall be provided on the bolt and nut to verify relative rotation between the bolt and the nut. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of using formed holes.

All costs associated with furnishing and installing or constructing the geotextile fabric, toewall, and culvert ties will not be measured for payment but shall be included in the contract unit price for Box Culvert End Sections of the culvert number specified.


Reinforcement bars designated (E) shall be epoxy coated.

Drain holes shall conform to the requirements of Article 503.11 of the Standard Specifications unless noted otherwise.


Nonwoven geotextile fabric shall conform to the requirements of Article 1080.01. The minimum weight of the fabric shall be 6 oz. / sq. yd..

For end sections with traversable pipe grate systems, see Highway Standard 542311 for required modifications.


This standard can be used for either cross drainage structures or parallel drainage structures.




**ELEVATION**



**PLAN**



**END VIEW**



**RESTRAINT ANGLE DETAIL**

12" x 12" block of CA5, CA7, or CA11 coarse aggregate placed over drain opening. Block of aggregate shall be completely wrapped in nonwoven geotextile fabric.


Provide a double layer of 12" x 12" nonwoven geotextile fabric centered over the drain hole. Fabric shall be sealed to the concrete with mastic.

3"  $\emptyset$  PVC drain cast with the concrete (Adjust location to clear reinforcement).


1/2" Square foam blockout around PVC drain (to be removed with formwork)

**SECTION A-A**

(All costs associated with furnishing and constructing the above drain details will not be measured for payment but shall be included in the contract unit price for the end section.)



**TIE PLATE DETAIL**



**SECTION B-B**

FILE NAME = District 2 Standard	USER NAME = ID07/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 5-09-14
	PLOT SCALE = 1:1000 1' = 100'	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# BOX CULVERT END SECTIONS




(Design Earth Cover < 2 ft.) (Design Earth Cover > 2 ft.)


**SECTION C-C**




**SECTION F-F**



**SECTION E-E**




**SECTION D-D**



**ALTERNATE SECTION D-D**

Rise (ft.) T(in.), T <sub>s</sub> (in.)	Reinforcing Steel A <sub>s1m</sub> (in. <sup>2</sup> /ft.)											
	2	3	4	5	6	7	8	9	10	11	12	
4	0.19	0.17										
5	0.26	0.21	0.18									
6		0.26	0.23	0.22								
7		0.33	0.29	0.27	0.28							
8			0.43	0.39	0.36	0.34	0.40					
9				0.43	0.40	0.37	0.36	0.48				
10				0.47	0.44	0.41	0.38	0.42	0.56			
11					0.54	0.46	0.41	0.50	0.65			
12					0.58	0.50	0.45	0.46	0.75			

(A<sub>s1m</sub> reinforcement based upon welded wire reinforcement conforming to AASHTO M 55 or M 221).



**HEADWALL ELEVATION**

(Allow sidewall reinforcement to extend into end of headwall.)

**TOEWALL CONSTRUCTION SEQUENCE**

1. Perform excavation and construct toewall.
2. Backfill according to the applicable paragraphs of Article 502.10 of the Standard Specifications and place bedding for precast box culvert end sections.
3. Set precast box culvert end section.
4. Drill and grout reinforcement in toewall using approved chemical adhesive in accordance with Section 1027 of the Standard Specifications.
5. Pressure grout voids using non-shrink grout conforming to Article 1024.02 of the Standard Specifications.

\* The Contractor may furnish a precast or cast-in-place toewall. The Contractor shall be responsible for the strength and stability of the precast toewall during handling. Additional lifting points may be required depending upon the length of the toewall or the Contractor may need to modify the design of the toewall for the proposed handling the method.

\*\* If soil conditions permit, the sides of the toewall may be poured directly against the soil. The clear cover on the sides of the toewall shall be increased to 3" by increasing the thickness of the toewall.

**l<sub>1</sub> DIMENSION**


- #3 bar = 2'-0"
- #4 bar = 2'-8"
- #5 bar = 3'-4"
- #6 bar = 3'-11"

**Notes:**

Alternate Section D-D is provided to allow the Contractor the option of casting the bottom slab of the end section first followed by construction of the sidewalls using conventional forming methods. Shop drawings that detail slab thickness and reinforcement layout shall be submitted to the Engineer for review and approval when using Alternate Section D-D.

The size and spacing of the v<sub>2</sub>(E) bars shall provide a minimum reinforcement area along each face of the walls (in.<sup>2</sup>/ft.) equal to 1.10\*(A<sub>s1m</sub>). v<sub>2</sub>(E) bars may consist of #3 thru #6 size reinforcement bars and the longitudinal spacing shall not exceed the lesser of the wall thickness or 8 inches.

Bonded construction joints shall be prepared according to Article 503.09 of the Standard Specifications.



**BAR s(E)**

**BAR s<sub>1</sub>**

**BAR v(E)**

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 5-09-14
	PLOT SCALE = 1:10000 / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**


SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# CONCRETE END SECTIONS FOR PARALLEL PIPE CULVERTS 15" THRU 84" DIA.



**ELEVATION**



**END VIEW**

(Showing pipes)

\* This dimension shall be increased by 1/2" for CIP field construction. See General Notes.

**GENERAL NOTES**

The concrete end sections detailed herein for flexible type pipe culverts are restricted to use with parallel type drainage structures only and traversable pipe grating placed perpendicular to the sidewalls. When traversable pipe grating placed parallel to the sidewalls is required, use standard 542001 or 542011.

A segment of pipe culvert shall be cast into the backwall of the concrete end section such that a minimum of 4 ft of pipe culvert extends from the back face of the end section as shown in Elevation.

Segments of pipe culvert shall be joined in accordance with Article 542 of the Standard Specifications except bands for corrugated steel or aluminum culverts shall conform to the length requirements shown in elevation and have the same corrugations as the culvert pipe. These bands will be included in cost of the pipe.


The number of segments shown in elevation is for example only. The length and number of precast sections required to construct the end section shall be determined by the Contractor.

See roadway plans for slope (V:H) and pipe inside diameter.


2 1/4" x 2 1/4" x 5/16" plate washers shall be provided under each nut required for the anchor rods. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of formed holes.

All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).


All dimensions are in inches unless otherwise shown.



**PLAN**




**TIE PLATE DETAIL**



**SECTION A-A**

(Showing end section tie details)



**RESTRAINT ANGLE DETAIL**

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 5-09-14
	PLOT SCALE = 1:10000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				


# CONCRETE END SECTIONS FOR PARALLEL PIPE CULVERTS 15" THRU 84" DIA.



**LONGITUDINAL SECTION**

(Showing bottom slab and backwall reinforcement.)

2-#5 bars at 6" cts. for pipe diameter  $\geq 48"$ , typ. each face




**SECTION B-B**

(Showing backwall reinforcement for pipes.)


**LAP DIMENSION**

- #4 bar = 17"
- #5 bar = 21"
- #6 bar = 25"

\*The Contractor may use lap splices for the sidewall reinforcement at the locations shown.



**SECTION D-D**



**SECTION C-C**

**PARALLEL PIPE CULVERT END SECTION DIMENSIONS**

Pipe I.D.	Tables IB, IC, IIIA, AND IIIB				
	R	S	L		
			Slope of End Section		
			1:4	1:6	1:10
15"	25"	16"	9'-0"	13'-2"	21'-6"
18"	28"	18"	10'-0"	14'-8"	24'-0"
21"	31"	22"	11'-0"	16'-2"	26'-6"
24"	35"	24"	12'-4"	18'-2"	29'-10"
30"	3'-5"	30"	14'-4"	21'-2"	34'-10"
36"	3'-11"	36"	16'-4"	24'-2"	39'-10"
42"	4'-5"	3'-6"	18'-4"	27'-2"	44'-10"
48"	5'-0"	4'-0"	20'-8"	30'-8"	50'-8"
54"	5'-4"	4'-6"	22'-0"	32'-8"	54'-0"
60"	5'-10"	5'-0"	24'-0"	35'-8"	59'-0"
66"	6'-4"	5'-6"	26'-0"	38'-8"	64'-0"
72"	6'-10"	6'-0"	28'-0"	41'-8"	69'-0"
78"	7'-4"	6'-6"	30'-0"	44'-8"	74'-0"
84"	7'-10"	7'-0"	32'-0"	47'-8"	79'-0"

**REINFORCEMENT SCHEDULE**

Pipe I.D.	PIPES	
	As1m	
	Bar Size	Bar Spacing
15"	#4	12"
18"	#4	12"
21"	#4	12"
24"	#4	12"
30"	#4	12"
36"	#4	12"
42"	#4	12"
48"	#4	8"
54"	#4	8"
60"	#5	8"
66"	#5	8"
72"	#5	8"
78"	#5	8"
84"	#6	8"

The above "Tables" are referenced from Article 542.03 of the Standard Specifications.

FILE NAME = District 2 Standard	USER NAME = ID07/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 5-09-14
	PLOT SCALE = 1:10000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# CONCRETE END SECTIONS FOR PARALLEL PIPE CULVERTS 15" THRU 84" DIA.

## QUANTITIES


Pipe I.D.	Tables IB, IC, IIIA, AND IIIB								
	Concrete yd <sup>3</sup>			Reinforcement without Lap lbs.			Reinforcement with Lap lbs.		
	Slope of End Section			Slope of End Section			Slope of End Section		
	1:4	1:6	1:10	1:4	1:6	1:10	1:4	1:6	1:10
15"	1.4	1.9	2.8	250	330	510	270	350	540
18"	1.6	2.2	3.4	290	400	600	310	420	640
21"	2.0	2.7	4.2	330	450	690	360	480	740
24"	2.3	3.2	5.0	370	510	790	400	550	850
30"	3.1	4.3	6.7	490	680	1060	520	720	1130
36"	3.9	5.5	8.7	580	810	1270	620	870	1360
42"	4.9	6.9	10.9	720	1020	1610	770	1080	1710
48"	6.0	8.6	13.7	940	1320	2090	1010	1420	2240
54"	6.9	9.8	15.7	1090	1540	2440	1160	1650	2610
60"	8.1	11.6	18.6	1410	2000	3190	1530	2180	3480
66"	9.5	13.6	21.8	1650	2360	3780	1780	2560	4100
72"	10.9	15.7	25.2	1840	2630	4220	1990	2850	4580
78"	12.4	17.9	28.9	2110	3040	4900	2280	3280	5290
84"	14.1	20.3	32.8	2710	3910	6320	2970	4290	6950

The above quantities are estimates and provided for information only. Actual quantities may vary depending upon the final layout of reinforcement and number of segments determined by the Contractor.


For cast-in-place construction, increase concrete volumes by approximately 12%.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 5-09-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		PLOT SCALE = 1.0000' / in.	CHECKED - DATE -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
		PLOT DATE = 1/18/2017	DATE -							


# CONCRETE END SECTIONS FOR PARALLEL PIPE ARCH CULVERTS 15" THRU 84" DIA.



**ELEVATION**



**PLAN**



**END VIEW**

(Showing pipe arches)

\* This dimension shall be increased by 1/2" for CIP field construction. See General Notes.

**GENERAL NOTES**

The concrete end sections detailed herein for flexible type pipe culverts are restricted to use with parallel type drainage structures only and traversable pipe grating placed perpendicular to the sidewalls. When traversable pipe grating placed parallel to the sidewalls is required, use standard 542001 or 542011.

A segment of pipe culvert shall be cast into the backwall of the concrete end section such that a minimum of 4 ft of pipe culvert extends from the back face of the end section as shown in Elevation.

Segments of pipe culvert shall be joined in accordance with Article 542 of the Standard Specifications except bands for corrugated steel or aluminum culverts shall conform to the length requirements shown in elevation and have the same corrugations as the culvert pipe. These bands will be included in cost of the pipe.


The number of segments shown in elevation is for example only. The length and number of precast sections required to construct the end section shall be determined by the Contractor.

See roadway plans for slope (V:H) and pipe inside diameter.


2 1/4" x 2 1/4" x 5/16" plate washers shall be provided under each nut required for the anchor rods. Holes in the walls for the culvert tie assembly may be drilled using core bits in lieu of formed holes.

All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).

All dimensions are in inches unless otherwise shown.




**TIE PLATE DETAIL**



**SECTION A-A**

(Showing end section tie details)



**RESTRAINT ANGLE DETAIL**

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - REVISED -	5-09-14
	PLOT SCALE = 1:10000' / in.	CHECKED -	REVISED -	
	PLOT DATE = 1/18/2017	DATE -	REVISED -	


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# CONCRETE END SECTIONS FOR PARALLEL PIPE ARCH CULVERTS 15" THRU 84" DIA.



**LONGITUDINAL SECTION**

(Showing bottom slab and backwall reinforcement.)




**SECTION B-B**

(Showing backwall reinforcement for arches.)

**LAP DIMENSION**

- #4 bar = 17"
- #5 bar = 21"
- #6 bar = 25"

\*The Contractor may use lap splices for the sidewall reinforcement at the locations shown.



**SECTION C-C**


**PARALLEL PIPE ARCH CULVERT END SECTION DIMENSIONS**

Equivalent Round Size	Culvert		Table IIA, Corrugation : 2 2/3" x 1/2"						Culvert		Table IIA, Corrugation : 3" x 1"					
	Span	Rise	R	S	L			Span	Rise	R	S	L				
					Slope of End Section							Slope of End Section				
					1:4	1:6	1:10					1:4	1:6	1:10		
15"	17"	13"	23"	18"	8'-4"	12'-2"	19'-10"	-	-	-	-	-	-	-		
18"	21"	15"	25"	22"	9'-0"	13'-2"	21'-6"	-	-	-	-	-	-	-		
21"	24"	18"	28"	24"	10'-0"	14'-8"	24'-0"	-	-	-	-	-	-	-		
24"	28"	20"	30"	28"	10'-8"	15'-8"	25'-8"	-	-	-	-	-	-	-		
30"	35"	24"	34"	36"	12'-0"	17'-8"	29'-0"	-	-	-	-	-	-	-		
36"	42"	29"	39"	3'-6"	13'-8"	20'-2"	33'-2"	40"	31"	3'-6"	40"	14'-8"	21'-8"	35'-8"		
42"	49"	33"	3'-7"	4'-2"	15'-0"	22'-2"	36'-6"	46"	36"	3'-11"	3'-10"	16'-4"	24'-2"	39'-10"		
48"	57"	38"	4'-0"	4'-10"	16'-8"	24'-8"	40'-8"	53"	41"	4'-5"	4'-6"	18'-4"	27'-2"	44'-10"		
54"	64"	43"	4'-5"	5'-4"	18'-4"	27'-2"	44'-10"	60"	46"	4'-10"	5'-0"	20'-0"	29'-8"	49'-0"		
60"	71"	47"	4'-9"	6'-0"	19'-8"	29'-2"	48'-2"	66"	51"	5'-3"	5'-6"	21'-8"	32'-2"	53'-2"		
66"	77"	52"	5'-2"	6'-6"	21'-4"	31'-8"	52'-4"	73"	55"	5'-8"	6'-2"	23'-4"	34'-8"	57'-4"		
72"	83"	57"	5'-7"	7'-0"	23'-0"	34'-2"	56'-6"	81"	59"	6'-0"	6'-10"	24'-8"	36'-8"	60'-8"		
78"	-	-	-	-	-	-	-	87"	63"	6'-5"	7'-4"	26'-4"	39'-2"	64'-10"		
84"	-	-	-	-	-	-	-	95"	67"	6'-9"	8'-0"	27'-8"	41'-2"	68'-2"		

The above "Tables" are referenced from Article 542.03 of the Standard Specifications.

**REINFORCEMENT SCHEDULE**

PIPE ARCHES		
Equivalent Round Size	A <sub>s1m</sub>	
	Bar Size	Bar Spacing
15"	#4	12"
18"	#4	12"
21"	#4	12"
24"	#4	12"
30"	#4	12"
36"	#4	12"
42"	#4	12"
48"	#4	12"
54"	#4	8"
60"	#4	8"
66"	#4	8"
72"	#5	8"
78"	#5	8"
84"	#5	8"



**SECTION D-D**

FILE NAME = District 2 Standard	USER NAME = ID07/District 2	DESIGNED -	REVISED - 5-09-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:10000' / in.	DRAWN -	REVISOR -	SCALE:      SHEET NO.    OF    SHEETS    STA.                    TO STA.		CONTRACT NO.				
	PLOT DATE = 1/18/2017	CHECKED -	REVISOR -	FED. ROAD DIST. NO.    ILLINOIS FED. AID PROJECT						



# TRAVERSABLE PIPE GRATE FOR BOX CULVERT END SECTIONS

PIPE-GRATE SCHEDULE FOR BOX CULVERT END SECTIONS

GENERAL NOTES


For layout of traversable pipe grate system, see Highway Standard 542311.

This table is only to be used for cross drainage structures.


Precast Box Culvert Dimensions			Slope of End Section								
			1:3			1:4			1:6		
S (ft)	R (ft)	T <sub>1</sub> (in)	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe	Main Pipe No. / Length	Int. Support No. / Length	Total Length of Pipe
4	2	7.5	1 @ 8'-10"	N/A	8'-10"	1 @ 11'-7"	N/A	11'-7"	1 @ 17'-2"	N/A	17'-2"
4	2	5	1 @ 8'-2"	N/A	8'-2"	1 @ 10'-8"	N/A	10'-8"	1 @ 15'-11"	N/A	15'-11"
4	3	7.5	1 @ 12'-0"	N/A	12'-0"	1 @ 15'-8"	N/A	15'-8"	1 @ 23'-3"	1 @ 3'-7"	26'-10"
4	3	5	1 @ 11'-4"	N/A	11'-4"	1 @ 14'-10"	N/A	14'-10"	1 @ 22'-0"	1 @ 3'-7"	25'-7"
4	4	7.5	1 @ 15'-2"	N/A	15'-2"	1 @ 19'-10"	1 @ 3'-7"	23'-5"	1 @ 29'-4"	2 @ 3'-7"	36'-6"
4	4	5	1 @ 14'-6"	N/A	14'-6"	1 @ 18'-11"	N/A	18'-11"	1 @ 28'-1"	2 @ 3'-7"	35'-3"
5	2	8	1 @ 8'-11"	N/A	8'-11"	1 @ 11'-9"	N/A	11'-9"	1 @ 17'-5"	N/A	17'-5"
5	2	6	1 @ 8'-5"	N/A	8'-5"	1 @ 11'-1"	N/A	11'-1"	1 @ 16'-5"	N/A	16'-5"
5	3	8	1 @ 12'-1"	N/A	12'-1"	1 @ 15'-10"	N/A	15'-10"	1 @ 23'-6"	1 @ 4'-7"	28'-1"
5	3	6	1 @ 11'-7"	N/A	11'-7"	1 @ 15'-2"	N/A	15'-2"	1 @ 22'-6"	1 @ 4'-7"	27'-1"
5	4	8	1 @ 15'-3"	N/A	15'-3"	1 @ 20'-0"	1 @ 4'-7"	24'-7"	1 @ 29'-7"	2 @ 4'-7"	38'-9"
5	4	6	1 @ 14'-9"	N/A	14'-9"	1 @ 19'-3"	N/A	19'-3"	1 @ 28'-7"	2 @ 4'-7"	37'-9"
5	5	8	1 @ 18'-5"	N/A	18'-5"	1 @ 24'-1"	2 @ 4'-7"	33'-3"	1 @ 35'-8"	3 @ 4'-7"	49'-5"
5	5	6	1 @ 17'-11"	N/A	17'-11"	1 @ 23'-5"	1 @ 4'-7"	28'-0"	1 @ 34'-8"	2 @ 4'-7"	43'-10"
6	2	8	2 @ 8'-11"	N/A	17'-10"	2 @ 11'-9"	N/A	23'-6"	2 @ 17'-5"	N/A	34'-10"
6	2	7	2 @ 8'-8"	N/A	17'-4"	2 @ 11'-5"	N/A	22'-10"	2 @ 16'-11"	N/A	33'-10"
6	3	8	2 @ 12'-1"	N/A	24'-2"	2 @ 15'-10"	N/A	31'-8"	2 @ 23'-6"	1 @ 5'-7"	52'-7"
6	3	7	2 @ 11'-10"	N/A	23'-8"	2 @ 15'-6"	N/A	31'-0"	2 @ 23'-0"	1 @ 5'-7"	51'-7"
6	4	8	2 @ 15'-3"	N/A	30'-6"	2 @ 20'-0"	1 @ 5'-7"	45'-7"	2 @ 29'-7"	2 @ 5'-7"	70'-4"
6	4	7	2 @ 15'-0"	N/A	30'-0"	2 @ 19'-8"	1 @ 5'-7"	44'-11"	2 @ 29'-1"	2 @ 5'-7"	69'-4"
6	5	8	2 @ 18'-5"	N/A	36'-10"	2 @ 24'-1"	2 @ 5'-7"	59'-4"	2 @ 35'-8"	3 @ 5'-7"	88'-1"
6	5	7	2 @ 18'-2"	N/A	36'-4"	2 @ 23'-9"	2 @ 5'-7"	58'-8"	2 @ 35'-2"	2 @ 5'-7"	81'-6"
6	6	8	2 @ 21'-7"	1 @ 5'-7"	48'-9"	2 @ 28'-3"	2 @ 5'-7"	67'-8"	2 @ 41'-9"	3 @ 5'-7"	100'-3"
6	6	7	2 @ 21'-4"	1 @ 5'-7"	48'-3"	2 @ 27'-11"	2 @ 5'-7"	67'-0"	2 @ 41'-3"	3 @ 5'-7"	99'-3"
7	2	8	2 @ 8'-11"	N/A	17'-10"	2 @ 11'-9"	N/A	23'-6"	2 @ 17'-5"	N/A	34'-10"
7	3	8	2 @ 12'-1"	N/A	24'-2"	2 @ 15'-10"	N/A	31'-8"	2 @ 23'-6"	2 @ 6'-7"	60'-2"
7	4	8	2 @ 15'-3"	N/A	30'-6"	2 @ 20'-0"	2 @ 6'-7"	53'-2"	2 @ 29'-7"	3 @ 6'-7"	78'-11"
7	5	8	2 @ 18'-5"	N/A	36'-10"	2 @ 24'-1"	3 @ 6'-7"	67'-11"	2 @ 35'-8"	4 @ 6'-7"	97'-8"
7	6	8	2 @ 21'-7"	2 @ 6'-7"	56'-4"	2 @ 28'-3"	3 @ 6'-7"	76'-3"	2 @ 41'-9"	5 @ 6'-7"	116'-5"
7	7	8	2 @ 24'-9"	3 @ 6'-7"	69'-3"	2 @ 32'-4"	4 @ 6'-7"	91'-0"	2 @ 47'-10"	6 @ 6'-7"	135'-2"
8	2	8	3 @ 8'-11"	N/A	26'-9"	3 @ 11'-9"	N/A	35'-3"	3 @ 17'-5"	N/A	52'-3"
8	3	8	3 @ 12'-1"	N/A	36'-3"	3 @ 15'-10"	N/A	47'-6"	3 @ 23'-6"	2 @ 7'-7"	85'-8"
8	4	8	3 @ 15'-3"	N/A	45'-9"	3 @ 20'-0"	2 @ 7'-7"	75'-2"	3 @ 29'-7"	3 @ 7'-7"	111'-6"
8	5	8	3 @ 18'-5"	N/A	55'-3"	3 @ 24'-1"	3 @ 7'-7"	95'-0"	3 @ 35'-8"	4 @ 7'-7"	137'-4"
8	6	8	3 @ 21'-7"	2 @ 7'-7"	79'-11"	3 @ 28'-3"	3 @ 7'-7"	107'-6"	3 @ 41'-9"	5 @ 7'-7"	163'-2"
8	7	8	3 @ 24'-9"	3 @ 7'-7"	97'-0"	3 @ 32'-4"	4 @ 7'-7"	127'-4"	3 @ 47'-10"	6 @ 7'-7"	189'-0"
8	8	8	3 @ 27'-11"	3 @ 7'-7"	106'-6"	3 @ 36'-6"	4 @ 7'-7"	139'-10"	3 @ 53'-11"	6 @ 7'-7"	207'-3"
9	2	9	3 @ 9'-3"	N/A	27'-9"	3 @ 12'-1"	N/A	36'-3"	3 @ 17'-11"	N/A	53'-9"
9	3	9	3 @ 12'-4"	N/A	37'-0"	3 @ 16'-2"	N/A	48'-6"	3 @ 24'-0"	3 @ 8'-7"	97'-9"
9	4	9	3 @ 15'-6"	N/A	46'-6"	3 @ 20'-4"	2 @ 8'-7"	78'-2"	3 @ 30'-1"	3 @ 8'-7"	116'-0"
9	5	9	3 @ 18'-8"	N/A	56'-0"	3 @ 24'-5"	3 @ 8'-7"	99'-0"	3 @ 36'-2"	4 @ 8'-7"	142'-10"
9	6	9	3 @ 21'-10"	2 @ 8'-7"	82'-8"	3 @ 28'-7"	3 @ 8'-7"	111'-6"	3 @ 42'-3"	5 @ 8'-7"	169'-8"
9	7	9	3 @ 25'-0"	3 @ 8'-7"	100'-9"	3 @ 32'-8"	4 @ 8'-7"	132'-4"	3 @ 48'-4"	6 @ 8'-7"	196'-6"
9	8	9	3 @ 28'-2"	3 @ 8'-7"	110'-3"	3 @ 36'-10"	4 @ 8'-7"	144'-10"	3 @ 54'-5"	6 @ 8'-7"	214'-9"
9	9	9	3 @ 31'-4"	3 @ 8'-7"	119'-9"	3 @ 40'-11"	5 @ 8'-7"	165'-8"	3 @ 60'-6"	7 @ 8'-7"	241'-7"
10	2	10	3 @ 9'-6"	N/A	28'-6"	3 @ 12'-5"	N/A	37'-3"	3 @ 18'-5"	N/A	55'-3"
10	3	10	3 @ 12'-8"	N/A	38'-0"	3 @ 16'-6"	N/A	49'-6"	3 @ 24'-6"	3 @ 9'-7"	102'-3"
10	4	10	3 @ 15'-10"	N/A	47'-6"	3 @ 20'-8"	2 @ 9'-7"	81'-2"	3 @ 30'-7"	3 @ 9'-7"	120'-6"
10	5	10	3 @ 19'-0"	N/A	57'-0"	3 @ 24'-9"	3 @ 9'-7"	103'-0"	3 @ 36'-8"	4 @ 9'-7"	148'-4"
10	6	10	3 @ 22'-1"	2 @ 9'-7"	85'-5"	3 @ 28'-11"	3 @ 9'-7"	115'-6"	3 @ 42'-9"	5 @ 9'-7"	176'-2"
10	7	10	3 @ 25'-3"	3 @ 9'-7"	104'-6"	3 @ 33'-0"	4 @ 9'-7"	137'-4"	3 @ 48'-10"	6 @ 9'-7"	204'-0"
10	8	10	3 @ 28'-5"	3 @ 9'-7"	114'-0"	3 @ 37'-2"	4 @ 9'-7"	149'-10"	3 @ 54'-11"	6 @ 9'-7"	222'-3"
10	9	10	3 @ 31'-7"	4 @ 9'-7"	133'-9"	3 @ 41'-3"	5 @ 9'-7"	171'-8"	3 @ 61'-0"	7 @ 9'-7"	250'-1"
10	10	10	3 @ 34'-9"	4 @ 9'-7"	142'-7"	3 @ 45'-5"	5 @ 9'-7"	184'-2"	3 @ 67'-1"	8 @ 9'-7"	277'-11"
11	2	11	4 @ 9'-9"	N/A	39'-0"	4 @ 12'-9"	N/A	51'-0"	4 @ 18'-11"	N/A	75'-8"
11	3	11	4 @ 12'-11"	N/A	51'-8"	4 @ 16'-11"	N/A	67'-8"	4 @ 25'-0"	3 @ 10'-7"	131'-9"
11	4	11	4 @ 16'-1"	N/A	64'-4"	4 @ 21'-0"	2 @ 10'-7"	105'-2"	4 @ 31'-1"	3 @ 10'-7"	156'-1"
11	6	11	4 @ 22'-5"	2 @ 10'-7"	110'-10"	4 @ 29'-3"	3 @ 10'-7"	148'-9"	4 @ 43'-3"	5 @ 10'-7"	225'-11"
11	8	11	4 @ 28'-9"	3 @ 10'-7"	146'-9"	4 @ 37'-6"	4 @ 10'-7"	192'-4"	4 @ 55'-5"	6 @ 10'-7"	285'-2"
11	10	11	4 @ 35'-0"	4 @ 10'-7"	182'-4"	4 @ 45'-9"	5 @ 10'-7"	235'-11"	4 @ 67'-7"	8 @ 10'-7"	355'-0"
11	11	11	4 @ 38'-2"	4 @ 10'-7"	195'-0"	4 @ 49'-10"	6 @ 10'-7"	262'-10"	4 @ 73'-8"	9 @ 10'-7"	389'-11"
12	2	12	4 @ 10'-0"	N/A	40'-0"	4 @ 13'-1"	N/A	52'-4"	4 @ 19'-5"	N/A	77'-8"
12	3	12	4 @ 13'-2"	N/A	52'-8"	4 @ 17'-3"	N/A	69'-0"	4 @ 25'-6"	3 @ 11'-7"	136'-9"
12	4	12	4 @ 16'-4"	N/A	65'-4"	4 @ 21'-4"	2 @ 11'-7"	108'-6"	4 @ 31'-7"	4 @ 11'-7"	172'-8"
12	6	12	4 @ 22'-8"	2 @ 11'-7"	113'-10"	4 @ 29'-7"	3 @ 11'-7"	153'-1"	4 @ 43'-9"	5 @ 11'-7"	232'-11"
12	8	12	4 @ 29'-0"	3 @ 11'-7"	150'-9"	4 @ 37'-10"	4 @ 11'-7"	197'-8"	4 @ 55'-11"	7 @ 11'-7"	304'-9"
12	10	12	4 @ 35'-4"	4 @ 11'-7"	187'-8"	4 @ 46'-1"	5 @ 11'-7"	242'-3"	4 @ 68'-1"	8 @ 11'-7"	365'-0"
12	12	12	4 @ 41'-8"	5 @ 11'-7"	224'-7"	4 @ 54'-4"	6 @ 11'-7"	286'-10"	4 @ 80'-3"	10 @ 11'-7"	436'-10"

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 5-09-14 REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
									CONTRACT NO.				
PLOT SCALE = 1:8000' / in. PLOT DATE = 1/18/2017					CHECKED - DATE -	REVISED -	SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

# TRAVERSABLE PIPE GRATE FOR PARALLEL DRAINAGE STRUCTURE



**LONGITUDINAL SECTION**




**PLAN VIEW**

## GENERAL NOTES

The minimum edge distance from the center of a hole to the free edge of a structural shape or plate shall be  $1\frac{1}{2}$ " unless noted otherwise.


This standard shall only be used on concrete end sections for parallel drainage structures.

The Contractor may install the thru bolts using drilling and grouting in lieu of providing a formed hole using steel pipe. Installation shall be in accordance with Article 509.06 using a method that results in the annulus surrounding the bolt being completely filled with adhesive. The method of drilling shall not result in spalled concrete at the exit face. Epoxy grouted thru bolts shall be snug tightened followed by an additional  $1\frac{1}{3}$  turn on the interior nut at final installation. Cost included with Traversable Pipe Grate.



**SECTION A-A**

(4"  $\emptyset$  pipe not shown for clarity.)



**VIEW B-B**

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - REVISED -	5-09-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 1:1000 1" = 10'	CHECKED -	REVISED -			SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED -									FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		

# TRAVERSABLE PIPE GRATE FOR PARALLEL DRAINAGE STRUCTURE

**PIPE GRATE SCHEDULE FOR PARALLEL BOX CULVERTS**

(<2 FT COVER)							
BOX SIZE		SLOPE OF END SECTION					
		1:4		1:6		1:10	
SPAN (FT.)	RISE (FT.)	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe
3	2	5 @ 2'-7"	12'-11"	8 @ 2'-7"	20'-8"	12 @ 2'-7"	31'-0"
3	3	7 @ 2'-7"	18'-1"	11 @ 2'-7"	28'-5"	17 @ 2'-7"	43'-11"
4	2	5 @ 3'-7"	17'-11"	8 @ 3'-7"	28'-8"	13 @ 3'-7"	46'-7"
4	3	8 @ 3'-7"	28'-8"	11 @ 3'-7"	39'-5"	18 @ 3'-7"	64'-6"
4	4	10 @ 3'-7"	35'-10"	14 @ 3'-7"	50'-2"	23 @ 3'-7"	82'-5"
5	2	6 @ 4'-7"	27'-6"	8 @ 4'-7"	36'-8"	13 @ 4'-7"	59'-7"
5	3	8 @ 4'-7"	36'-8"	11 @ 4'-7"	50'-5"	18 @ 4'-7"	82'-6"
5	4	10 @ 4'-7"	45'-10"	14 @ 4'-7"	64'-2"	23 @ 4'-7"	105'-5"
5	5	12 @ 4'-7"	55'-0"	17 @ 4'-7"	77'-11"	28 @ 4'-7"	128'-4"
6	2	6 @ 5'-7"	33'-6"	8 @ 5'-7"	44'-8"	13 @ 5'-7"	72'-7"
6	3	8 @ 5'-7"	44'-8"	11 @ 5'-7"	61'-5"	18 @ 5'-7"	100'-6"
6	4	10 @ 5'-7"	55'-10"	14 @ 5'-7"	78'-2"	23 @ 5'-7"	128'-5"
6	5	12 @ 5'-7"	67'-0"	17 @ 5'-7"	94'-11"	28 @ 5'-7"	156'-4"
6	6	14 @ 5'-7"	78'-2"	20 @ 5'-7"	111'-8"	33 @ 5'-7"	184'-3"
7	2	6 @ 6'-7"	39'-6"	8 @ 6'-7"	52'-8"	13 @ 6'-7"	85'-7"
7	3	8 @ 6'-7"	52'-8"	11 @ 6'-7"	72'-5"	18 @ 6'-7"	118'-6"
7	4	10 @ 6'-7"	65'-10"	14 @ 6'-7"	92'-2"	23 @ 6'-7"	151'-5"
7	5	12 @ 6'-7"	79'-0"	17 @ 6'-7"	111'-11"	28 @ 6'-7"	184'-4"
7	6	14 @ 6'-7"	92'-2"	20 @ 6'-7"	131'-8"	33 @ 6'-7"	217'-3"
7	7	16 @ 6'-7"	105'-4"	23 @ 6'-7"	151'-5"	38 @ 6'-7"	250'-2"
8	2	6 @ 7'-7"	45'-6"	8 @ 7'-7"	60'-8"	13 @ 7'-7"	98'-7"
8	3	8 @ 7'-7"	60'-8"	11 @ 7'-7"	83'-5"	18 @ 7'-7"	136'-6"
8	4	10 @ 7'-7"	75'-10"	14 @ 7'-7"	106'-2"	23 @ 7'-7"	174'-5"
8	5	12 @ 7'-7"	91'-0"	17 @ 7'-7"	128'-11"	28 @ 7'-7"	212'-4"
8	6	14 @ 7'-7"	106'-2"	20 @ 7'-7"	151'-8"	33 @ 7'-7"	250'-3"
8	7	16 @ 7'-7"	121'-4"	23 @ 7'-7"	174'-5"	38 @ 7'-7"	288'-2"
8	8	18 @ 7'-7"	136'-6"	26 @ 7'-7"	197'-2"	43 @ 7'-7"	326'-1"
9	2	6 @ 8'-7"	51'-6"	8 @ 8'-7"	68'-8"	13 @ 8'-7"	111'-7"
9	3	8 @ 8'-7"	68'-8"	11 @ 8'-7"	94'-5"	18 @ 8'-7"	154'-6"
9	4	10 @ 8'-7"	85'-10"	14 @ 8'-7"	120'-2"	23 @ 8'-7"	197'-5"
9	5	12 @ 8'-7"	103'-0"	17 @ 8'-7"	145'-11"	28 @ 8'-7"	240'-4"
9	6	14 @ 8'-7"	120'-2"	20 @ 8'-7"	171'-8"	33 @ 8'-7"	283'-3"
9	7	16 @ 8'-7"	137'-4"	23 @ 8'-7"	197'-5"	38 @ 8'-7"	326'-2"
9	8	18 @ 8'-7"	154'-6"	26 @ 8'-7"	223'-2"	43 @ 8'-7"	369'-1"
9	9	20 @ 8'-7"	171'-8"	30 @ 8'-7"	257'-6"	48 @ 8'-7"	412'-0"
10	2	6 @ 9'-7"	57'-6"	9 @ 9'-7"	86'-3"	14 @ 9'-7"	134'-2"
10	3	8 @ 9'-7"	76'-8"	12 @ 9'-7"	115'-0"	19 @ 9'-7"	182'-1"
10	4	10 @ 9'-7"	95'-10"	15 @ 9'-7"	143'-9"	24 @ 9'-7"	230'-0"
10	5	12 @ 9'-7"	115'-0"	18 @ 9'-7"	172'-6"	29 @ 9'-7"	277'-11"
10	6	14 @ 9'-7"	134'-2"	21 @ 9'-7"	201'-3"	34 @ 9'-7"	325'-10"
10	7	16 @ 9'-7"	153'-4"	24 @ 9'-7"	230'-0"	39 @ 9'-7"	373'-9"
10	8	18 @ 9'-7"	172'-6"	27 @ 9'-7"	258'-9"	44 @ 9'-7"	421'-8"
10	9	20 @ 9'-7"	191'-8"	30 @ 9'-7"	287'-5"	49 @ 9'-7"	469'-7"
10	10	22 @ 9'-7"	210'-10"	33 @ 9'-7"	316'-3"	54 @ 9'-7"	517'-6"

**PIPE GRATE SCHEDULE FOR PARALLEL BOX CULVERTS**

(<2 FT COVER)							
BOX SIZE		SLOPE OF END SECTION					
		1:4		1:6		1:10	
SPAN (FT.)	RISE (FT.)	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe
11	2	6 @ 10'-7"	63'-6"	9 @ 10'-7"	95'-3"	14 @ 10'-7"	148'-2"
11	3	8 @ 10'-7"	84'-8"	12 @ 10'-7"	127'-0"	19 @ 10'-7"	201'-1"
11	4	10 @ 10'-7"	105'-10"	15 @ 10'-7"	158'-9"	24 @ 10'-7"	254'-0"
11	6	14 @ 10'-7"	148'-2"	21 @ 10'-7"	222'-3"	34 @ 10'-7"	359'-10"
11	8	18 @ 10'-7"	190'-6"	27 @ 10'-7"	285'-9"	44 @ 10'-7"	465'-8"
11	10	23 @ 10'-7"	243'-5"	33 @ 10'-7"	349'-3"	54 @ 10'-7"	571'-6"
11	11	25 @ 10'-7"	264'-7"	36 @ 10'-7"	381'-0"	59 @ 10'-7"	624'-5"
12	2	6 @ 11'-7"	69'-6"	9 @ 11'-7"	104'-3"	15 @ 11'-7"	173'-9"
12	3	8 @ 11'-7"	92'-8"	12 @ 11'-7"	139'-0"	20 @ 11'-7"	231'-8"
12	4	10 @ 11'-7"	115'-10"	15 @ 11'-7"	173'-9"	25 @ 11'-7"	289'-7"
12	6	15 @ 11'-7"	173'-9"	21 @ 11'-7"	243'-3"	35 @ 11'-7"	405'-5"
12	8	19 @ 11'-7"	220'-1"	27 @ 11'-7"	312'-9"	45 @ 11'-7"	521'-3"
12	10	23 @ 11'-7"	266'-5"	33 @ 11'-7"	382'-3"	55 @ 11'-7"	637'-1"
12	12	27 @ 11'-7"	312'-9"	39 @ 11'-7"	451'-9"	65 @ 11'-7"	752'-11"

**PIPE GRATE SCHEDULE FOR PARALLEL BOX CULVERTS**

(>2 FT COVER)							
BOX SIZE		SLOPE OF END SECTION					
		1:4		1:6		1:10	
SPAN (FT.)	RISE (FT.)	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe
3	2	5 @ 2'-7"	12'-11"	7 @ 2'-7"	18'-1"	11 @ 2'-7"	28'-5"
3	3	7 @ 2'-7"	18'-1"	10 @ 2'-7"	25'-10"	16 @ 2'-7"	41'-4"
4	2	5 @ 3'-7"	17'-11"	7 @ 3'-7"	25'-1"	12 @ 3'-7"	43'-0"
4	3	7 @ 3'-7"	25'-1"	10 @ 3'-7"	35'-10"	17 @ 3'-7"	60'-11"
4	4	9 @ 3'-7"	32'-3"	13 @ 3'-7"	46'-7"	22 @ 3'-7"	78'-10"
5	2	5 @ 4'-7"	22'-11"	7 @ 4'-7"	32'-1"	12 @ 4'-7"	55'-0"
5	3	7 @ 4'-7"	32'-1"	11 @ 4'-7"	50'-5"	17 @ 4'-7"	77'-11"
5	4	9 @ 4'-7"	41'-3"	14 @ 4'-7"	64'-2"	22 @ 4'-7"	100'-10"
5	5	11 @ 4'-7"	50'-5"	17 @ 4'-7"	77'-11"	27 @ 4'-7"	123'-9"
6	2	5 @ 5'-7"	27'-11"	8 @ 5'-7"	44'-8"	12 @ 5'-7"	67'-0"
6	3	7 @ 5'-7"	39'-1"	11 @ 5'-7"	61'-5"	17 @ 5'-7"	94'-11"
6	4	10 @ 5'-7"	55'-10"	14 @ 5'-7"	78'-2"	23 @ 5'-7"	128'-5"
6	5	12 @ 5'-7"	67'-0"	17 @ 5'-7"	94'-11"	28 @ 5'-7"	156'-4"
6	6	14 @ 5'-7"	78'-2"	20 @ 5'-7"	111'-8"	33 @ 5'-7"	184'-3"

Follow (<2 FT Cover) table for all other sizes

FILE NAME = District 2 Standard	USER NAME = ID07/District 2	DESIGNED - DRAWN -	REVISED - 5-09-14 REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED -			CONTRACT NO.					
	PLOT DATE = 1/18/2017	DATE -	REVISED -			SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.

# TRAVERSABLE PIPE GRATE FOR PARALLEL DRAINAGE STRUCTURE

**PIPE GRATE SCHEDULE FOR PARALLEL PIPE CULVERTS 15" THRU 84" DIA.**

Pipe I.D.	SLOPE OF END SECTION					
	1:4		1:6		1:10	
	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe
15"	3 @ 0'-11"	2'-9"	4 @ 0'-11"	3'-8"	6 @ 0'-11"	5'-6"
18"	3 @ 1'-1"	3'-3"	5 @ 1'-1"	5'-5"	7 @ 1'-1"	7'-7"
21"	4 @ 1'-5"	5'-8"	5 @ 1'-5"	7'-1"	9 @ 1'-5"	12'-9"
24"	5 @ 1'-7"	7'-11"	6 @ 1'-7"	9'-6"	10 @ 1'-7"	15'-10"
30"	6 @ 2'-1"	12'-6"	8 @ 2'-1"	16'-8"	13 @ 2'-1"	27'-1"
36"	7 @ 2'-7"	18'-1"	10 @ 2'-7"	25'-10"	15 @ 2'-7"	38'-9"
42"	8 @ 3'-1"	24'-8"	11 @ 3'-1"	33'-11"	18 @ 3'-1"	55'-6"
48"	9 @ 3'-7"	32'-3"	13 @ 3'-7"	46'-7"	21 @ 3'-7"	75'-3"
54"	10 @ 4'-1"	40'-10"	14 @ 4'-1"	57'-2"	23 @ 4'-1"	93'-11"
60"	11 @ 4'-7"	50'-5"	15 @ 4'-7"	68'-9"	25 @ 4'-7"	114'-7"
66"	12 @ 5'-1"	61'-0"	17 @ 5'-1"	86'-5"	28 @ 5'-1"	142'-4"
72"	13 @ 5'-7"	72'-7"	18 @ 5'-7"	100'-6"	30 @ 5'-7"	167'-6"
78"	14 @ 6'-1"	85'-2"	20 @ 6'-1"	121'-8"	33 @ 6'-1"	200'-9"
84"	15 @ 6'-7"	98'-9"	21 @ 6'-7"	138'-3"	35 @ 6'-7"	230'-5"

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 5-09-14 REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 1.0000' / in.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO.			
PLOT DATE = 1/18/2017	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								

# TRAVERSABLE PIPE GRATE FOR PARALLEL DRAINAGE STRUCTURE

**PIPE GRATE SCHEDULE FOR PARALLEL PIPE ARCH CULVERTS 15" THRU 84" DIA.**

SLOPE OF END SECTION						
Pipe I.D.	Table IIA, Corrugation : 2 2/3" x 1/2"					
	1:4		1:6		1:10	
	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe
15"	2 @ 1'-1"	2'-2"	3 @ 1'-1"	3'-3"	5 @ 1'-1"	5'-5"
18"	3 @ 1'-5"	4'-3"	4 @ 1'-5"	5'-8"	6 @ 1'-5"	8'-6"
21"	3 @ 1'-7"	4'-9"	5 @ 1'-7"	7'-11"	7 @ 1'-7"	11'-1"
24"	4 @ 1'-11"	7'-8"	5 @ 1'-11"	9'-7"	8 @ 1'-11"	15'-4"
30"	4 @ 2'-7"	10'-4"	6 @ 2'-7"	15'-6"	10 @ 2'-7"	25'-10"
36"	5 @ 3'-1"	15'-5"	7 @ 3'-1"	21'-7"	12 @ 3'-1"	37'-0"
42"	6 @ 3'-9"	22'-6"	9 @ 3'-9"	33'-9"	14 @ 3'-9"	52'-6"
48"	7 @ 4'-5"	30'-11"	10 @ 4'-5"	44'-2"	16 @ 4'-5"	70'-8"
54"	8 @ 4'-11"	39'-4"	11 @ 4'-11"	54'-1"	18 @ 4'-11"	88'-6"
60"	8 @ 5'-7"	44'-8"	12 @ 5'-7"	67'-0"	20 @ 5'-7"	111'-8"
66"	9 @ 6'-1"	54'-9"	13 @ 6'-1"	79'-1"	22 @ 6'-1"	133'-10"
72"	10 @ 6'-7"	65'-10"	15 @ 6'-7"	98'-9"	24 @ 6'-7"	158'-0"
78"	-	-	-	-	-	-
84"	-	-	-	-	-	-

**PIPE GRATE SCHEDULE FOR PARALLEL PIPE ARCH CULVERTS 15" THRU 84" DIA.**

SLOPE OF END SECTION						
Pipe I.D.	Table IIA, Corrugation : 3" x 1"					
	1:4		1:6		1:10	
	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe
15"	-	-	-	-	-	-
18"	-	-	-	-	-	-
21"	-	-	-	-	-	-
24"	-	-	-	-	-	-
30"	-	-	-	-	-	-
36"	6 @ 2'-11"	17'-6"	8 @ 2'-11"	23'-4"	13 @ 2'-11"	37'-11"
42"	7 @ 3'-5"	23'-11"	10 @ 3'-5"	34'-2"	15 @ 3'-5"	51'-3"
48"	8 @ 4'-1"	32'-8"	11 @ 4'-1"	44'-11"	18 @ 4'-1"	73'-6"
54"	9 @ 4'-7"	41'-3"	12 @ 4'-7"	55'-0"	20 @ 4'-7"	91'-10"
60"	9 @ 5'-1"	45'-9"	14 @ 5'-1"	71'-2"	22 @ 5'-1"	111'-10"
66"	10 @ 5'-9"	57'-6"	15 @ 5'-9"	86'-3"	24 @ 5'-9"	138'-0"
72"	11 @ 6'-5"	70'-7"	16 @ 6'-5"	102'-8"	26 @ 6'-5"	166'-10"
78"	12 @ 6'-11"	83'-0"	17 @ 6'-11"	117'-7"	28 @ 6'-11"	193'-8"
84"	12 @ 7'-7"	91'-0"	18 @ 7'-7"	136'-6"	30 @ 7'-7"	227'-6"

# TRAVERSABLE PIPE GRATE FOR PARALLEL DRAINAGE STRUCTURE

**PIPE GRATE SCHEDULE FOR PARALLEL ELLIPTICAL PIPE CULVERTS 15" THRU 72" DIA.**


Pipe I.D.	SLOPE OF END SECTION					
	1:4		1:6		1:10	
	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe	Pipes No. / Length	Total Length of Pipe
15"	3 @ 2'-7"	7'-9"	5 @ 2'-7"	12'-11"	7 @ 2'-7"	18'-1"
18"	3 @ 2'-7"	7'-9"	5 @ 2'-7"	12'-11"	7 @ 2'-7"	18'-1"
21"	5 @ 3'-3"	16'-3"	7 @ 3'-3"	22'-9"	12 @ 3'-3"	39'-0"
24"	5 @ 3'-3"	16'-3"	7 @ 3'-3"	22'-9"	12 @ 3'-3"	39'-0"
27"	6 @ 3'-7"	21'-6"	8 @ 3'-7"	28'-8"	13 @ 3'-7"	46'-7"
30"	6 @ 3'-11"	23'-6"	9 @ 3'-11"	35'-3"	14 @ 3'-11"	54'-10"
36"	7 @ 4'-7"	32'-1"	10 @ 4'-7"	45'-10"	16 @ 4'-7"	73'-4"
42"	8 @ 5'-5"	43'-4"	11 @ 5'-5"	59'-7"	18 @ 5'-5"	97'-6"
48"	9 @ 6'-1"	54'-9"	13 @ 6'-1"	79'-1"	20 @ 6'-1"	121'-8"
54"	10 @ 6'-9"	67'-6"	14 @ 6'-9"	94'-6"	23 @ 6'-9"	155'-3"
60"	11 @ 7'-7"	83'-5"	15 @ 7'-7"	113'-9"	25 @ 7'-7"	189'-7"
66"	11 @ 8'-3"	90'-9"	17 @ 8'-3"	140'-3"	27 @ 8'-3"	222'-9"
72"	12 @ 8'-11"	107'-0"	18 @ 8'-11"	160'-6"	30 @ 8'-11"	267'-6"

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 5-09-14 REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 1,0000' / in.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO.			
PLOT DATE = 1/18/2017	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								


# SLOPED METAL END SECTIONS WITH GRATE

## GENERAL NOTES


- USE END SECTIONS ON 1V:4H TO 1V:6H SLOPES ONLY. USE TOE PLATE EXTENSION.
- A 1:6 SLOPED END SECTION WILL BE USED FOR ALL PARALLEL DRAINAGE STRUCTURE END SECTIONS.
- FABRICATE SAFETY AND LONGITUDINAL BARS FROM STEEL PIPE CONFORMING TO ASTM A53 SCHEDULE 40 SPECIFICATIONS. GALVANIZE BARS HOT DIPPED AFTER FABRICATION.
- A LONGITUDINAL BAR IS REQUIRED FOR CROSS DRAINAGE END SECTIONS WHEN THE SPAN IS GREATER THAN 30". USE ADDITIONAL LONGITUDINAL BARS IF SPACING EXCEEDS 30" ON LARGER END SECTIONS.
- SAFETY AND LONGITUDINAL BARS ARE NOT REQUIRED ON 30" AND SMALLER CROSS DRAINAGE END SECTIONS.
- THESE END SECTIONS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR SLOPED METAL END SECTIONS WITH GRATE OF THE DIAMETER SPECIFIED, WHICH SHALL INCLUDE FURNISHING AND INSTALLING THE END SECTION COMPLETE IN PLACE, INCLUDING THE TOE PLATE, EXCAVATING, BACKFILLING, CONNECTING TO THE PIPE, AND CROSS DRAINAGE BARS.




FRONT VIEW  
ROUND PIPE CULVERT




ELEVATION  
CROSS DRAINAGE END SECTION




ELEVATION  
PARALLEL DRAINAGE END SECTION




FRONT VIEW  
PIPE ARCH CULVERT




FOR METAL ROUND PIPES  
15" THRU 24"  
TYPE #1



FOR METAL ROUND PIPES 30" AND LARGER, FOR PIPE ARCHES 21" X 15" AND LARGER  
TYPE #2




LONGITUDINAL DRAINAGE BAR



PARALLEL BARS


## CONNECTOR DETAILS

## SAFETY BAR DETAILS




PARALLEL DRAINAGE  
END SECTION

CROSS DRAINAGE END SECTION



SECTION A-A



SECTION B-B

NO SCALE

## METAL END SECTIONS FOR ROUND PIPE CULVERT

PIPE SIZE * INCHES	METAL THICK (MIN.) INCH/GAGE	DIMENSIONS IN INCHES						
		A	H	W	OVERALL WIDTH	L		
						Slope=4	Slope=6	
24	0.064/16	8	6	30	46	55	83	
30	0.109/12	12	9	36	60	79	118	
36	0.109/12	12	9	42	66	102	154	
42	0.109/12	16	12	48	80	126	189	
48	0.109/12	16	12	54	86	150	224	
54	0.109/12	16	12	60	92	173	260	
60	0.109/12	16	12	66	98	197	295	

## METAL END SECTIONS FOR PIPE ARCH CULVERT

PIPE SIZE (INCHES)			METAL THICK (MIN.) INCH/GAGE	DIMENSIONS (INCHES)						
EQUIV. *	SPAN	RISE		A	H	W	OVERALL WIDTH	L		
								Slope=4	Slope=6	
24	28	20	0.064/16	8	6	33	49	40	60	
30	35	24	0.109/12	12	9	40	64	55	83	
36	41	29	0.109/12	12	9	47	71	75	112	
42	48	32	0.109/12	16	12	54	86	90	136	
48	56	37	0.109/12	16	12	62	94	110	165	
54	63	42	0.109/12	16	12	69	101	130	195	
60	70	46	0.109/12	16	12	76	107	146	218	
72	82	56	0.109/12	16	12	88	120	185	278	

FILE NAME = District 2 Standard	USER NAME = ID07/District 2	DESIGNED - DRAWN -	REVISED - REVISED -
	PLOT SCALE = 1:10000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD


SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# HOT-MIX ASPHALT APPROACHES AND MAILBOX RETURNS




**FIELD ENTRANCE**




**MAILBOX TURNOUT**

**NOTE**


- ① TURNOUTS ARE TO BE CONSTRUCTED ON THE APPROACH SIDE OF ALL PE & CE REGARDLESS IF A MAILBOX IS PRESENT.
- ② ALL PE & CE ARE TO BE SURFACED TO RIGHT OF WAY LINE. AREA BEHIND RIGHT OF WAY SHALL MATCH EXISTING SURFACE.
- ③ ALL PE & CE TO BE CONSTRUCTED WITH AN 8" AGGREGATE BASE COURSE, TYPE B AND WITH A 2 1/4" INCIDENTAL HOT-MIX ASPHALT SURFACING, UNLESS OTHERWISE NOTED.
- ④ FE ARE TO BE AGGREGATE TO RIGHT OF WAY OR TOUCH DOWN, WHICH EVER IS GREATEST.
- ⑤ EXCAVATION REQUIRED FOR PLACEMENT OF AGGREGATE BASE COURSE SHALL BE INCLUDED IN THE COST OF THE AGGREGATE BASE COURSE.
- ⑥ ON ENTRANCES THE CONTRACTOR HAS THE OPTION OF USING RADIUS RETURNS. USE RADII OF 20' TO 60'.
- ⑦ SIDE ROADS SHALL HAVE 3" INCIDENTAL PLACED IN TWO 1 1/2" LIFTS.




**SIDE ROAD RETURN/EARTH SHOULDER**




**PRIVATE ENTRANCE**




**RURAL ENTRANCE PROFILE APPROACH**



**SIDE ROAD RETURN/HMA SHOULDER**



**COMMERCIAL ENTRANCE**



**SIDE ROAD RETURN WITH RIGHT TURN LANE**

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-13-17
		DRAWN -	REVISED - 6-27-14
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 8-27-13
	PLOT DATE = 1/18/2017	DATE -	REVISED - 12-07-10




**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				










# ENTRANCE APPROACHES – URBAN AREA



A MINIMUM OF 440 FEET SHALL BE MAINTAINED BETWEEN CENTER LINES OF ADJACENT DRIVEWAYS.  $\Delta$  90° DESIRABLE, 45° MIN. ANGLE PERMITTED ONLY FOR ONE-WAY DRIVEWAYS. 60° MIN. ANGLE FOR TWO-WAY DRIVEWAYS.

NOTE: #1 ENCROACHMENT ON THE ADJACENT PROPERTY OWNER LAND REQUIRES HIS OR HER WRITTEN APPROVAL.

\*\* 4'-10' IF HIGHWAY CURBED. AT EDGE OF SHOULDER IF HIGHWAY UNCURBED.



NOTE: CURVED ENTRANCE RETURNS MAY BE USED FOR LOW TO MODERATE VOLUME LOCATIONS WITH REVIEW ON A CASE-BY-CASE BASIS.

FILE NAME = District 2 Standard	USER NAME = ID07/District 2	DESIGNED -	REVISED - 6-27-14
		DRAWN -	REVISED - 12-07-10
	PLOT SCALE = 1:10000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				



# SEWER AND WATER MAIN CROSSINGS



THIS DETAIL IS FOR UNKNOWN UTILITIES UNLESS QUANTITIES ARE INCLUDED IN THE PLANS THE EXTRA WORK WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.04.

WHEN PROPOSED SEWER (OR WATER) IS LOCATED 10'-0" OR MORE FROM EXISTING WATER (OR SEWER) NO SPECIAL CONSTRUCTION REQUIRED.

WHEN PROPOSED SEWER (OR WATER) IS LOCATED LESS THAN 10'-0" FROM EXISTING WATER (OR SEWER) DETAILS BELOW SHALL APPLY.




CASING SHALL BE CAST IRON WITH AN INSIDE DIAMETER 2" LARGER IN DIAMETER THAN ENCASED PIPE OUTSIDE DIAMETER WITH BOTH ENDS OF CASING SEALED


AT GRADE CROSSING OF SANITARY AND STORM SEWER

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED

POINT LOADS SHALL NOT BE ALLOWED BETWEEN SEWER OR SEWER CASING AND WATER MAIN  
 PROVIDE ADEQUATE SUPPORT FOR EXISTING WATER MAIN TO PREVENT DAMAGE DUE TO SETTLEMENT OF SEWER TRENCH




PROVIDE ADEQUATE SUPPORT FOR EXISTING WATER MAIN TO PREVENT DAMAGE DUE TO SETTLEMENT OF SEWER TRENCH  
 MAINTAIN 18 MINIMUM VERTICAL SEPARATION FOR 10 FT. HORIZONTALLY



ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED


PROPOSED SEWER LINE BELOW EXISTING WATER MAIN

PROVIDE ADEQUATE SUPPORT FOR EXISTING SEWER LINE TO PREVENT DAMAGE DUE TO SETTLEMENT  
 PLACE TRENCH BACKFILL FOR 10 FT. ON EITHER SIDE OF SEWER LINE



CASING SHALL BE CAST IRON WITH AN INSIDE DIAMETER 2" LARGER IN DIAMETER THAN ENCASED PIPE OUTSIDE DIAMETER WITH BOTH ENDS OF CASING SEALED


PROVIDE ADEQUATE SUPPORT FOR EXISTING WATER MAIN TO PREVENT DAMAGE DUE TO SETTLEMENT OF SEWER TRENCH  
 MAINTAIN 18 MINIMUM VERTICAL SEPARATION FOR 10 FT. HORIZONTALLY



ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED

PROPOSED WATER MAIN ABOVE EXISTING SEWER LINE

POINT LOADS SHALL NOT BE ALLOWED BETWEEN WATER MAIN OR WATER MAIN CASING AND SEWER




CASING SHALL BE CAST IRON WITH AN INSIDE DIAMETER 2" LARGER IN DIAMETER THAN ENCASED PIPE OUTSIDE DIAMETER WITH BOTH ENDS OF CASING SEALED

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED

PROPOSED WATER MAIN ABOVE EXISTING SEWER LINE

PROVIDE ADEQUATE SUPPORT FOR SEWER TO PREVENT SETTLING AND BREAKING THE WATER MAIN.



ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED

EXISTING WATER MAIN BELOW PROPOSED SEWER LINE WITH MINIMUM 18 VERTICAL SEPARATION

FILE NAME = District 2 Standard	USER NAME = 1007/District 2	DESIGNED - DRAWN -	REVISED - 10-17-11 REVISED -
	PLOT SCALE = 1/8" = 1' / in.	CHECKED - DATE -	REVISED - REVISED -
	PLOT DATE = 1/18/2017		

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD


SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				



# WORK ZONE SIGN DETAILS

**ILLINOIS STANDARD G20-I100**




COLOR LEGEND AND BORDER BACKGROUND BLACK ORANGE NON-REFLECTORIZED REFLECTORIZED

SIGN SIZE	DIMENSIONS											
	A	B	C	D	E	F	G	H	J	K	L	M
60 x 36	60.00	36.00	2.25	6.4	21.80	16.40	10.00	22.40	13.20	15.50	10.50	10.00

SIGN SIZE	SERIES BY LINE			MARGIN	BORDER
	1	2	3		
60 x 36	5C	5C	5C	0.625	0.875

Sign not to scale

**ILLINOIS STANDARD W8-I107**



COLOR LEGEND AND BORDER BACKGROUND BLACK ORANGE NON-REFLECTORIZED REFLECTORIZED

SIGN SIZE	DIMENSIONS								
	A	B	C	D	E	F	G	H	J
48 x 48	48.00	3.00	25.00	34.80	34.20	24.94	9.00	1.00	10.00

SIGN SIZE	SERIES BY LINE			MARGIN	BORDER
	1	2	3		
48 x 48	7C	7C	7C	1.250	0.750

Sign not to scale

**GENERAL NOTES**

All work to furnish and install these signs shall be included in the cost of the specified traffic control standards and shall not be paid separately.

All Illinois Standard signs shall conform to the latest edition of the "Illinois Standard Highway Signs Book" in effect on the date of invitation for bids.

Signs shall meet the applicable portions of Sections 701 and 720 of the Standard Specifications.

All dimensions are in inches unless otherwise noted.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 3-02-16
		DRAWN -	REVISED -
	PLOT SCALE = 1,0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**


**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# WORK ZONE SIGN DETAILS

## ILLINOIS STANDARD W12-I102



### GENERAL NOTES

All work to furnish and install these signs shall be included in the cost of the specified traffic control standards and shall not be paid separately.

All Illinois Standard signs shall conform to the latest edition of the "Illinois Standard Highway Signs Book" in effect on the date of invitation for bids.

Signs shall meet the applicable portions of Sections 701 and 720 of the Standard Specifications.

All dimensions are in inches unless otherwise noted.

COLOR      LEGEND AND BORDER BACKGROUND      BLACK FL ORANGE      NON-REFLECTORIZED REFLECTORIZED


SIGN SIZE	DIMENSIONS	
	A	B
48 x 48	48.00	3.00

① Illinois Standard signs W12-I102 and W12-I103 shall be used as described in the special provisions.

SIGN SIZE	SERIES BY LINE	MARGIN	BORDER
	1		
48 x 48	12C	0.750	1.250

Sign not to scale

## ILLINOIS STANDARD W12-I103



COLOR      LEGEND AND BORDER BACKGROUND (WIDTH)      BLACK WHITE FL ORANGE      NON-REFLECTORIZED REFLECTORIZED REFLECTORIZED

SIGN SIZE	DIMENSIONS											
	A	B	C	D	E	F	G	H	J	K	L	M
48 x 48	48.00	3.00	38.40	13.20	19.20	32.00	22.00	26.20	12.00	24.00	10.00	11.00

SIGN SIZE	SERIES BY LINE				MARGIN	BORDER
	1	2	3	4		
48 x 48	6C	8D	6D	6D	0.750	1.250

Sign not to scale

XX'-XX" WIDTH AND X MILES ARE VARIABLE TOP AND BOTTOM OF BACKGROUND WHITE

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 3-02-16
		DRAWN -	REVISED -
	PLOT SCALE = 1.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# WORK ZONE SIGN DETAILS

## ROAD CLOSED TO OVERSIZED LOADS

## STOP LINE SIGN FOR TEMPORARY SIGNALS



COLOR	LEGEND AND BORDER BACKGROUND	BLACK ORANGE	NON-REFLECTORIZED REFLECTORIZED
-------	------------------------------	--------------	---------------------------------

COLOR	LEGEND AND BORDER BACKGROUND	BLACK WHITE	NON-REFLECTORIZED REFLECTORIZED
-------	------------------------------	-------------	---------------------------------

Permit Loads - Loads Over 13 Feet; 3.0" Radius, 1.3" Border;  
 [NO OVERSIZE -] D; [OVERWEIGHT LOADS] D 85% spacing; [XX MILES AHEAD] D;  
 Table of letter and object lefts.

SIGN SIZE	SERIES BY LINE		
	1	2	3
24 x 24	4C	4C	4C

N	O	O	V	E	R	S	I	Z	E	-
11.7	18.1	30.0	36.2	42.8	48.4	54.4	60.7	63.5	69.5	80.8

O	V	E	R	W	E	I	G	H	T	L	O	A	D	S
2.6	8.6	15.0	20.4	26.2	33.4	38.8	41.3	47.4	53.2	64.5	69.9	75.9	82.9	88.7

X	X	M	I	L	E	S	A	H	E	A	D
7.6	13.6	25.3	32.3	35.1	40.6	46.2	57.9	65.1	71.4	76.6	83.7

Sign not to scale

Sign not to scale

### GENERAL NOTES

All work to furnish and install these signs shall be included in the cost of the specified traffic control standards and shall not be paid separately.

All Illinois Standard signs shall conform to the latest edition of the "Illinois Standard Highway Signs Book" in effect on the date of invitation for bids.

Signs shall meet the applicable portions of Sections 701 and 720 of the Standard Specifications.


All dimensions are in inches unless otherwise noted.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - REVISED -	3-02-16	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED -			SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								

**ENTRANCE SIGN FOR USE  
WITH TEMPORARY SIGNALS**

**WORK ZONE SIGN DETAILS**

2



COLOR LEGEND AND BORDER BACKGROUND BLACK ORANGE NON-REFLECTORIZED REFLECTORIZED

2.25" Radius, 0.88" Border, 0.50" Indent;  
[CAUTION] D; [ONE LANE ROAD] D;  
[FOLLOW TRAFFIC] D; [FLOW] D

2 This sign shall be installed at entrances located between the temporary signals as shown in the staging plans.

**Table Of Widths And Spaces**

22.31	C	0.62	A	0.94	U	0.94	T	0.94	I	1.17	O	1.17	N	3.36	22.31
	3.36		4.18		3.36		3.04		0.78		3.52		3.36		

8.23	O	1.17	N	1.18	E
	3.51		3.36		3.04

5.00	L	0.31	A	0.94	N	1.17	E
	3.05		4.18		3.36		3.05

5.00	R	0.93	O	0.94	A	0.93	D	8.23
	3.36		3.52		4.18		3.36	


7.43	F	0.94	O	1.17	L	0.94	L	0.94	O	0.94	W
	3.04		3.52		3.04		3.05		3.51		4.37

5.00	T	0.94	R	0.94	A	0.93	F	0.94	F	0.94	I	1.18	C	7.43
	3.05		3.36		4.18		3.05		3.04		0.78		3.35	

27.60	F	0.94	L	0.94	O	0.93	W	27.60
	3.05		3.04		3.52		4.38	

Sign not to scale

**STAY IN YOUR LANE**



COLOR LEGEND AND BORDER BACKGROUND BLACK ORANGE NON-REFLECTORIZED REFLECTORIZED

48.0" across sides 3.8" Radius, 1.0" Border, 0.6" Indent;  
"STAY" E Mod; "IN YOUR" E Mod; "LANE" E Mod;

**Table of Letter and Object Lefts**

S	T	A	Y
20.7	26.8	31.6	38.0

I	N	Y	O	U	R
13.2	15.9	26.7	33.9	40.5	46.8

L	A	N	E
20.9	25.8	33.1	39.4

Sign not to scale

**GENERAL NOTES**

All work to furnish and install these signs shall be included in the cost of the specified traffic control standards and shall not be paid separately.

All Illinois Standard signs shall conform to the latest edition of the "Illinois Standard Highway Signs Book" in effect on the date of invitation for bids.

Signs shall meet the applicable portions of Sections 701 and 720 of the Standard Specifications.

All dimensions are in inches unless otherwise noted.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - REVISED -	3-02-16
	PLOT SCALE = 1.0000' / in.	CHECKED -	REVISED -	
	PLOT DATE = 1/18/2017	DATE -	REVISED -	


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# URBAN LANE INSIDE CLOSURE, MULTILANE, 2-WAY, WITH MOUNTABLE MEDIAN



W20-1(0)-48  
For maintenance



W20-1103(0)-48  
For construction




W20-5L(0)-48



W4-2L(0)-48



W20-7(0)-48



W20-1(0)-48  
For maintenance



W20-1103(0)-48  
For construction

## SYMBOLS

- WORK AREA
- CLOSED LANE
- ARROW BOARD
- SIGN ON PORTABLE OR PERMANENT SUPPORT
- CONE, DRUM OR BARRICADE
- FLAGGER WITH TRAFFIC CONTROL SIGN.
- WORKER ON FOOT

SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

- ① Refer to SIGN SPACING TABLE for distances.
- ② Use flagger and flagger sign only when flagger is required per Article 701.13(b).
- ③ Devices at 10' centers from edge of radius return to edge of radius return when left turns are prohibited due to actively working in the intersection.
- ④ Cones at 20' (6 m) centers for 250' (75 m). Additional cones may be placed at 40' (12 m) centers. When drums or Type I or Type II barricades are used, the interval between devices may be doubled (excluding devices in intersections).
- ⑤ Cones, drums or barricades at 20' (6 m) centers in taper.
- ⑥ No equipment, materials, vehicles, or other hazards are allowed in the closed lane in the opposite direction within 100' of a worker on foot.

## GENERAL NOTES

This Standard is used where at any time, day or night, any vehicle, equipment, workers or their activities encroach on the pavement requiring the closure of one or more traffic lanes in an Urban area.

Calculate L as follows:

SPEED LIMIT

FORMULAS

English (Metric)

$$L = \frac{WS^2}{60} \quad L = \frac{WS^2}{150}$$

40 mph (70 km/h) or less:

$$L = (W)(S) \quad L = 0.65(W)(S)$$

45 mph (80 km/h) or greater:

W = Width of offset in feet (meters).

S = Normal posted speed mph (km/h).

All dimensions are in inches (millimeters) unless otherwise shown.

Lane closures in the opposite direction shall be removed when no workers are present.

Cones or reflectorized cones shall not be used during hours of darkness.

This Traffic Control detail shall be included in the cost of Traffic Control and Protection Standard 701606.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 7-22-14
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# TEMPORARY ROAD CLOSURE EXPRESSWAY



## GENERAL NOTES

1. MAINTENANCE OF TRAFFIC IS ACCORDING TO STANDARDS 701400, AND 701401 (NIGHT) OR 701406 (DAY ONLY).
2. TYPE II BARRICADES OR DRUMS AT EXIT RAMP WITH LIGHTS AT 20' CENTERS (NO LESS THAN FOUR DRUMS).

## SYMBOLS

- SIGN
- DIRECTION INDICATOR BARRICADE WITH LIGHT
- TYPE II BARRICADE OR DRUM WITH LIGHT
- FLAGGER WITH TRAFFIC CONTROL SIGN
- ⌈ TYPE III BARRICADE WITH FLASHERS
- ☐ PORTABLE CHANGEABLE MESSAGE SIGN
- ↓ ARROW BOARD

SIGNING ACCORDING TO SPECIFIED STANDARDS

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16
		DRAWN -	REVISED - 8-27-13
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 4-04-11
	PLOT DATE = 1/18/2017	DATE -	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# TRAFFIC CONTROL FOR THREE LANE SECTION CASE 1



- ① Use flagger and flagger signs only when flagger is required per Article 701.13(b).
- ② Cones at 20' centers for 250'. Additional cones may be placed at 40' centers. When drums or type I or II barricades are used, the interval between devices may be doubled.

SYMBOLS


- WORK AREA
- SIGN
- FLAGGER WITH TRAFFIC CONTROL SIGN
- CONE, DRUM OR BARRICADE
- TYPE III BARRICADE

THIS TRAFFIC CONTROL DETAIL SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - 8-27-13										
		CHECKED -	REVISED - 7-30-13										
		DATE -	REVISED -										
					SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
										FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			

# TRAFFIC CONTROL FOR THREE LANE SECTION CASE 2

W20-I103(O)-48



### SYMBOLS

- WORK AREA
- SIGN
- FLAGGER WITH TRAFFIC CONTROL SIGN
- CONE, DRUM OR BARRICADE

- ① Use flagger and flagger signs only when flagger is required per Article 701.13(b).
- ② Cones at 20' centers for 250'. Additional cones may be placed at 40' centers. When drums or type I or II barricades are used, the interval between devices may be doubled.

THIS TRAFFIC CONTROL DETAIL SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

\*IF THE WORK ENDS WITHIN 2500 FEET OF THE TRANSITION WHEN THE SPEED IS > 40 MPH OR 1500 FEET FOR ALL OTHER SPEEDS, THE CLIMBING LANE SHALL REMAIN CLOSED AS SHOWN.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 8-27-13
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 7-30-13
	PLOT DATE = 1/18/2017	DATE -	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# TRAFFIC CONTROL FOR THREE LANE SECTION CASE 3



NOTE: DO NOT OPEN THE CLIMBING LANE UNLESS THERE IS AT LEAST 1/2 MILE BEFORE THE LANE ENDS.

### SYMBOLS

- WORK AREA
- SIGN
- FLAGGER WITH TRAFFIC CONTROL SIGN
- CONE, DRUM OR BARRICADE

② Cones at 20' centers for 250'. Additional cones may be placed at 40' centers. When drums or type I or II barricades are used, the interval between devices may be doubled.

THIS TRAFFIC CONTROL DETAIL SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16
		DRAWN -	REVISED - 8-27-13
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 7-30-13
	PLOT DATE = 1/18/2017	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**


SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# TRAFFIC CONTROL FOR THREE LANE SECTION

## CASE 4

W20-I103(O)-48



NOTE: DO NOT OPEN THE CLIMBING LANE UNLESS THERE IS AT LEAST 1/2 MILE BEFORE THE LANE ENDS.

### SYMBOLS

-  WORK AREA
-  SIGN
-  FLAGGER WITH TRAFFIC CONTROL SIGN
-  CONE, DRUM OR BARRICADE
-  TYPE III BARRICADE

② Cones at 20' centers for 250'. Additional cones may be placed at 40' centers. When drums or type I or II barricades are used, the interval between devices may be doubled.


THIS TRAFFIC CONTROL DETAIL SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

CASE 4 APPLIES WHEN NO WORKERS ARE PRESENT. WHEN WORKERS ARE PRESENT, TWO LANES SHALL BE CLOSED AND TRAFFIC CONTROL SHALL BE ACCORDING TO CASE 3.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 8-27-13	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -	REVISED - 7-30-13			SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.		
		DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							

# TRAFFIC CONTROL FOR TRANSITION AREAS

## CASE 1



FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16
		DRAWN -	REVISED - 8-27-13
	PLOT SCALE = 1:10000' / in.	CHECKED -	REVISED - 1-16-13
	PLOT DATE = 1/18/2017	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# TRAFFIC CONTROL FOR TRANSITION AREAS

## CASE 2



**GENERAL NOTES**  
 THIS DETAIL IS TO BE USED IN CONJUNCTION WITH THE APPLICABLE MULTILANE TRAFFIC CONTROL AND PROTECTION STANDARD.

1. If applicable, Use if shown on applicable multilane Traffic Control and Protection Standard being used.
2. If the work is within 2500 feet of the transition when the speed is > 40 mph, or 1500 feet for all other speeds, the detail shall be used.
3. WORK ZONE SPEED LIMIT 55 SIGN ASSEMBLY shall be replaced with WORK ZONE SPEED LIMIT 45 SIGN ASSEMBLY where the workers are within 500 feet of the transition.


THIS TRAFFIC CONTROL DETAIL SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

NOTE: STANDARDS 701301 AND 701306 SHALL NOT BE USED WITHIN 500 FEET OF THE TRANSITION.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 8-27-13	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:10000' / in.	CHECKED -	REVISED - 1-16-13		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.		
	PLOT DATE = 1/18/2017	DATE -	REVISED -		FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT				

# TRAFFIC CONTROL FOR TRANSITION AREAS

## CASE 3



**GENERAL NOTES**  
 THIS DETAIL IS TO BE USED IN CONJUNCTION WITH THE APPLICABLE MULTILANE TRAFFIC CONTROL AND PROTECTION STANDARD.

1. If applicable, Use if shown on applicable multilane Traffic Control and Protection Standard being used.
2. If the work is within 2500 feet of the transition when the speed is > 40 mph, or 1500 feet for all other speeds, the detail shall be used.
3. WORK ZONE SPEED LIMIT 55 SIGN ASSEMBLY shall be replaced with WORK ZONE SPEED LIMIT 45 SIGN ASSEMBLY where the workers are within 500 feet of the transition.

THIS TRAFFIC CONTROL DETAIL SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.


- FLAGGER WITH TRAFFIC CONTROL SIGN
- DRUMS OR BARRICADES WITH LIGHTS
- WORK AREA

NOTE: STANDARDS 701301 AND 701306 SHALL NOT BE USED WITHIN 500 FEET OF THE TRANSITION.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - 8-27-13									
		CHECKED -	REVISED - 3-05-12					CONTRACT NO.				
		DATE -	REVISED -					ILLINOIS FED. AID PROJECT				
		PLOT SCALE = 1/8" = 10'			SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.			

# TRAFFIC CONTROL FOR TRANSITION AREAS

## CASE 4




**GENERAL NOTES**  
 THIS DETAIL IS TO BE USED IN CONJUNCTION WITH THE APPLICABLE MULTILANE TRAFFIC CONTROL AND PROTECTION STANDARD.

1. If applicable, Use if shown on applicable multilane Traffic Control and Protection Standard being used.
2. If the work is within 2500 feet of the transition when the speed is > 40 mph, or 1500 feet for all other speeds, the detail shall be used.
3. WORK ZONE SPEED LIMIT 55 SIGN ASSEMBLY shall be replaced with WORK ZONE SPEED LIMIT 45 SIGN ASSEMBLY where the workers are within 500 feet of the transition.



THIS TRAFFIC CONTROL DETAIL SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

NOTE: STANDARDS 701301 AND 701306 SHALL NOT BE USED WITHIN 500 FEET OF THE TRANSITION.

-  FLAGGER WITH TRAFFIC CONTROL SIGN
-  DRUMS OR BARRICADES WITH LIGHTS
-  WORK AREA

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - 8-27-13									
		CHECKED -	REVISED - 3-05-12					CONTRACT NO.				
		DATE -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
				SCALE:      SHEET NO.    OF    SHEETS    STA.                    TO STA.								

# TRAFFIC CONTROL TYPICAL WEAVE




W1-4R(O)-48

Temporary Pavement Marking required if Typical Weave is used for 14 days or more.

### SYMBOLS

- DRUM WITH STEADY BURN MONO-DIRECTIONAL LIGHT
- SIGN



W1-4L(O)-48

### GENERAL NOTES:

USE ON LONG 4-LANE PROJECTS WHERE THE CONTRACTOR MAY CHANGE A PORTION OF THE WORK TO THE OPPOSITE LANE.

USE WHERE THE PROJECT IS ADJACENT TO ANOTHER AND THE CONTRACTOR COULD BE WORKING ON DIFFERENT LANES.

TEMPORARY PAVEMENT MARKING SHALL BE USED WHEN TYPICAL WEAVE IS USED FOR 14 DAYS OR MORE.

TRAFFIC CONTROL TYPICAL WEAVE SHALL BE INCLUDED IN THE COST OF THE SPECIFIC TRAFFIC CONTROL STANDARDS OF ITEMS.

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

### STANDARD WEAVE CONDITIONS FOR DIFFERENT SPEED LIMITS

POSTED SPEED LIMIT	WEAVE LENGTH
65 MPH OR HIGHER	780 FT.
55 MPH	660 FT.
45 MPH	540 FT.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14
	PLOT SCALE = 1,0000' / in.	CHECKED -	REVISED - 8-27-13
	PLOT DATE = 1/18/2017	DATE -	REVISED - 10-17-11


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# TRAFFIC CONTROL FOR ROAD CLOSURE



## SYMBOLS

-  Work area
-  Type III Barricade with Flashers
-  Sign with flashing light

## GENERAL NOTES

Longitudinal dimensions may be adjusted to fit field conditions.

Side roads requiring all three signs as shown in CONDITION I (Major Sideroad Closure), shall be listed in the special provision.

\*\* Where local access is to be maintained, barricades are to be set up as shown in Road Closed to thru traffic. Type III Barricades and R11-2-4830 signs shall be as shown in "Road Closed To All Traffic" detail on Highway Standard 701901.

All dimensions are in inches unless otherwise shown.


①

SIGN SPACING TABLE	
Posted Speed	Sign Spacing
45 MPH and above	500'
Below 45 MPH	250'

②

SIGN LEGEND	
Posted Speed Limit	Distance
45 MPH and above	1000'
Below 45 MPH	500'

ROAD CLOSED TO THRU TRAFFIC BARRICADE SET UP



Type III Barricades and R11-4-4830 signs shall be as shown in "Road Closed To Thru Traffic" detail on Highway Standard 701901. If the distance "D" exceeds 2000' an additional set of barricades and R11-4-4830 shall be placed at each end of the work area.

## CONDITION II

Minor Sideroad Closure

## CONDITION I


Major Sideroad Closure

TYPICAL APPLICATION FOR ROAD CLOSURE


FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 8-27-13	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1/8" = 100'	CHECKED -	REVISED - 10-17-11		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								

# TYPICAL PAVEMENT MARKINGS

## TYPICAL PAVEMENT MARKING FOR FLUSH MEDIAN AT LEFT TURN LANE




## MEDIAN PAVEMENT MARKING




\*\* ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

## TYPICAL ISLAND OFFSET SHOULDER WIDTH




## TYPICAL MARKING FOR PAINTED ISLANDS

NOTE:  
\* 45° TO LOCAL TAN.



## STANDARD CROSSWALK MARKING

See Schedules for Locations




\* Distance to the nearest edge of the intersecting roadway in the absence of a marked crosswalk.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 6-27-14 REVISED - 3-05-12	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1,0000' / in.	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								

# TYPICAL PAVEMENT MARKINGS


## ARROW LAYOUT



- ◀ ONE-WAY AMBER MARKER
- ◁ ONE-WAY CRYSTAL MARKER
- ◆ TWO-WAY AMBER MARKER

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.


## TYPICAL PAVEMENT MARKING FOR FLUSH MEDIAN



### RECOMMENDED SPACING BETWEEN DIAGONALS (IN FEET)

Speed Limit Range	Continuous Median Area	Intersection Channelization	Objects (Islands)
less than 30MPH	50'	15'	10'
30-40MPH	75'	20'	15'
45MPH & over	75'	30'	20'

NOTE: if the spacing recommended in the Table does not permit at least five diagonal lines in the area being marked, the spacing from the next lowest speed range should be used. The recommended spacing is measured parallel to the pavement center line.



FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 6-27-14 REVISED - 3-05-12
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# TYPICAL PAVEMENT MARKINGS



\* SEE HIGHWAY STANDARD 781001 FOR SPACING DETAILS.  
USE DOUBLE MARKERS WHEN ADT > 20,000.

## MULTI-LANE / DIVIDED



\* REDUCE TO 40' O.C. ON CURVES WHERE ADVISORY SPEEDS ARE 10 MPH LOWER THAN POSTED SPEEDS.


\*\* USE DOUBLE MARKERS WHEN ADT ≥ 20,000

\*\*\* CENTERLINE SKIP DASH PAVEMENT MARKING SPEED LIMIT LESS THAN 40 MPH USE 4" LINE. SPEED LIMIT 40 MPH AND OVER USE 6" LINE.


## MULTI-LANE / UNDIVIDED & ONE WAY

(FOR MULTI-LANE UNDIVIDED HIGHWAYS USE THIS  
DETAIL NOT HIGHWAY STANDARD 781001)

## TYPICAL PARKING SPACING



## TYPICAL PAVEMENT MARKING FOR TWO LANE SECTION – NO PASSING ZONES




FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 6-27-14 REVISED - 8-27-13	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 11-28-12					CONTRACT NO.				
	PLOT DATE = 1/18/2017	DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	

# PAINING DETAILS


CENTERLINE SKIP DASH PAVEMENT MARKING WIDTH SHALL BE 4" WHEN THE POSTED SPEED LIMIT IS UNDER 40 MPH AND 6" WHEN THE POSTED SPEED LIMIT IS 40 MPH AND OVER.

## EXIT RAMP

NOTE: GORE HATCHING PLACED ONLY WHEN SCHEDULED IN THE PLANS




## ENTRANCE RAMP



ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

## CLOVERLEAF



FILE NAME =  
District 2 Standard

USER NAME = IDOT/District 2  
PLOT SCALE = 1,0000' / in.  
PLOT DATE = 1/18/2017

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED - 8-27-13  
REVISED - 10-18-11  
REVISED -  
REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD


SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				


# REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL




**TYPE A**  
6'-3" Typical post spacing




SECTION A-A




**TYPE B**  
37 1/2 Closed post spacing




SECTION C-C



**TYPE D**  
Double steel plate beam guardrail  
6'-3" typical post spacing



**TYPE C**  
37 1/2 Block-out spacing



SECTION B-B

## GENERAL NOTES

All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).

All dimensions are in inches unless otherwise shown.

The existing steel posts may be drilled to match the bolt pattern shown herein for the wood block-out, or a new steel post shall be provided.

This detail is applicable to the guardrail system used prior to January 1, 2007. For details on the Midwest Guardrail System, see Standard 630001.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 10-18-11
	PLOT SCALE = 1:0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**


SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				


# REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL




STEEL POST CONSTRUCTION



STEEL BLOCK-OUT DETAIL




WOOD POST CONSTRUCTION



NOTE

Plate A shall be placed between rail element and block-out at non-splice mounting points only when steel block-outs are used.

PLATE A



POST OR SPLICE BOLT & NUT

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16
		DRAWN -	REVISED - 10-18-11
	PLOT SCALE = 1:0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION


REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL


Place standard end shoe between splice plate and rail element



**SPLICE PLATE**




**RAIL ELEMENT SPLICE**




NOTE

Anchor plate T shall be used to attach cable assembly to guardrail when required on traffic barrier terminals.


**ANCHOR PLATE T DETAILS**



Class A rail element



**END SECTION**




NOTE

When end shoe is attached to a bridge parapet which has an expansion joint, the bolts shall be provided with a locknut or double nut and shall be tightened only to a point that will allow guardrail movement.

The standard end shoe shall be attached to the concrete with pre-drilled or self-drilling anchor bolts. The anchor cone shall be set flush with the surface of the concrete.

Externally threaded studs protruding from the surface of the concrete will not be permitted.



**END SHOE**



**ALTERNATE END SHOE**

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 10-18-11	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:0000' / in.	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.		
	PLOT DATE = 1/18/2017	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							


# REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL




Note:  
If it is necessary for D to be more than 12 and less than 10'-0" type M-2 curb and gutter (Std. 606001) shall be used in front of and in advance of the guardrail.

GUARDRAIL PLACED BEHIND CURB

(D = 0 desirable to 12 maximum)



WOOD BLOCK-OUT AND STEEL POST DETAILS




Note:  
Ledge line is top of rock ledge or hard slag fill.

ELEVATION

FOOTING FOR POST WHEN IMPERVIOUS MATERIAL IS ENCOUNTERED

V	W	L	
		Steel Post	Wood Post
0 - 18	24	21	23
>18 - 41.5	12	8	10
>41.5 - 53.5	12 - 0	8	10



CABLE ASSEMBLY  
(40,000 lbs. min. breaking strength)  
Tighten to fault tension.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 10-18-11
	PLOT SCALE = 1,0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD


SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				


# TRAFFIC BARRIER TERMINAL, TYPE 2 (27" HEIGHT)




BEARING PLATE K




PLAN




WOOD POST




ELEVATION



YOKE  
3/16 thick steel



CABLE STRUT



STEEL TUBE




PLATE WASHER F

### GENERAL NOTES

See Standard 630001 for details of guardrail not shown.


The bearing plate K shall be held in position by (2) two eight penny nails driven into the post and bent over the top of the plate.

All dimensions are in inches unless otherwise shown.


FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 10-18-11 REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
	PLOT SCALE = 1:0000' / in.	CHECKED -	REVISED -					SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.		
	PLOT DATE = 1/18/2017	DATE -	REVISED -								FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

# SLOTTED DRAIN PIPE

LOADING CONDITION	MAX. EXTENDER HEIGHT - "H"
H20/H25 • 750 PSI CONCRETE • 125 PSI TIRE PRESSURE	19"



DETAIL WITH VARIABLE HEIGHT GRATE



SECTION A-A

## GENERAL

Class SI Concrete shall be used throughout. This specification covers Slotted Drain used for the removal of water as shown on the plans. The Slotted Drain shall be Corrugated Pipe Culvert with Integral Slotted Drains. Before placing the concrete adjacent to the pipe, the slot shall be covered by either thin, flat metal sheeting or by a board notched to fit over the grate bars. This covering must fit closely in the slot to prevent entry of concrete into the pipe. Paving over the slotted drain will then be one continuous operation over the protected drain. The protection for the drain slot shall then be removed. The pipe shall drain into the side of the inlet. The opening where the slot is removed shall be covered to prevent concrete from entering the pipe. The Corrugated Steel Pipe used in the Slotted Drain shall meet the requirements of AASHTO M36/ASTM A760. The CMP shall be ALUMINIZED STEEL Type 2. The diameter shall be as shown on the plans. Steel grating shall meet the galvanizing requirements of AASHTO M111. This work will be paid for at the contract unit price per foot for SLOTTED DRAIN of the pipe diameter specified WITH VARIABLE SLOT, or SLOTTED DRAIN, of the pipe diameter specified, WITH 6" SLOT, and shall include concrete and grating for depth specified on plans. Use approved end cap to prevent concrete entry into the pipe during gutter construction on the upstream end of the pipe.

## CONNECTIONS

The Corrugated Steel Pipe shall have a minimum of two rerolled annular ends. The Slotted Drain bands shall be modified HUGGER Bands to secure the pipe and prevent infiltration of the backfill. When the Slotted Drain is banded together, the adjacent grates shall have a maximum 3" gap.

## GRATES

The grates shall be manufactured from ASTM A670, Grade 36 steel. The spacers and bearing bars (sides) shall be 3/16" material ±0.008". The spacers shall be on 6" centers and welded on both sides to each bearing bar (sides) with four (4) 1-1/4" long 3/16" fillet welds on each side of the bearing bar. The plate extender shall be 7 gage steel meeting ASTM A761. The engineer may call for tensile strength tests on the grate if the grate is not in compliance with the above spacer specifications. If tensile strength tests are called for, minimum results for an in-place spacer pulled perpendicular to the bearing bar shall be:  
T = 12,000 pounds for 2-1/2" grate  
T = 15,000 pounds for 6" grate

## GALVANIZING


The grate and plate extenders shall be galvanized in accordance with ASTM A123 except with a 2 oz. galvanized coating.

## GRATE ATTACHED TO CSP


The grate shall be fillet welded with a minimum weld 1" long to the CSP on each side of the grate at every other corrugation.

## TOLERANCES - FINISHED SLOTTED DRAIN - 20' LENGTHS


Vertical Bow = ± 3/8"  
Horizontal Bow = ± 5/8"  
Twist = ± 1/2"




TOP VIEW



SIDE VIEW



SECTION A-A  
STANDARD DETAIL



SECTION A-A  
DETAIL WITH MESH  
(TRAPEZOIDAL GALVANIZED GRATE SHOWN)


GAGE OF PIPE	DIAMETER OF PIPE					
	12"	15"	18"	24"	30"	36"
16	X	X	X	X	X	X
14	X	X	X	X	X	X
12	N.A.	N.A.	N.A.	N.A.	X	X

GRATE TYPE	"A"
VERT	2-1/2"
TRAP	2-1/2"
TRAP	6"



VERT = VERTICAL  
TRAP = TRAPEZOIDAL

## SLOTTED DRAIN NOTES


- GRATING IS AVAILABLE IN DEPTHS OF 2-1/2" AND 6".
- VERTICAL GRATING (STRAIGHT SIDES) WITH VERTICAL SPACERS IS ALSO AVAILABLE.
- FOR 6" VERTICAL & TRAPEZOIDAL REQUIREMENTS, THE SLOTTED DRAIN BAND MAY BE FURNISHED WITH THE 4" TECHCO BAND ANGLE.
- DIMENSIONS ARE SUBJECT TO MANUFACTURING TOLERANCES.
- DIMENSIONS FOR H<sub>1</sub> AND H<sub>2</sub> AS REQUIRED.
- H<sub>1</sub> AND H<sub>2</sub> MEASURED FROM TOP OF GRATE TO BOTTOM OF GRATE.




END VIEW




TYPICAL PIPE SECTION




GRATE WELDING DETAIL



SECTION B-B



DETAIL FOR CURB & GUTTER



DETAIL FOR CROSSOVERS,  
DRIVEWAYS, OR PARKING LOTS

ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 10-18-11
	PLOT DATE = 1/18/2017	DATE -	REVISED -



STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				


# DETAIL OF FLOOD GATE



## BILL OF MATERIALS

QUANTITY	UNIT	ITEM
	FT	2 x 4 TREATED LUMBER
	FT	GALVANIZED BARBED WIRE
	FT	SPECIAL STEEL CHANNEL SC 25, 2 1/2 x 2 1/2
	EACH	3/8 x 3 GALVANIZED STEEL BOLTS AND WASHERS
	EACH	3/8 x 2 GALVANIZED STEEL U-BOLTS
	EACH	GALVANIZED CABLE CLAMPS
	LBS	GALVANIZED FENCE STAPLES

**NOTE:**  
THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR




QUANTITIES FOR 2 DEADMEN  
0.3 CU. YD. CLASS SI CONCRETE  
36 LBS REINFORCEMENT BARS

## DETAIL OF PRECAST CONCRETE DEADMAN


## BILL OF MATERIALS

QUAN.	UNIT	ITEM
FT		3/4 DIA. GALVANIZED WIRE ROPE
EACH		3/4 DIA. x 15 GALVANIZED EYE BOLTS WITH NUTS AND WASHERS
EACH		3/4 DIA. GALVANIZED TURNBUCKLES
EACH		3/4 DIA. GALVANIZED CABLE CLAMPS
EACH		5x5x3/4 STEEL WASHER PLATES
EACH		PRECAST CONCRETE DEADMEN OR CAST-IN-PLACE CONCRETE DEADMEN
FT		12 CREOSOTED TIMBER PILE (INCLUDES FURNISHING AND DRIVING TIMBER PILE)



QUANTITIES FOR 2 DEADMEN  
0.7 CU. YD. CLASS SI CONCRETE

## DETAIL OF CAST-IN-PLACE CONCRETE DEADMAN



## DETAIL 'A'

EXPLODED VIEW OF FLOOD GATE TO CABLE

**NOTE:**  
PRECAST CONCRETE DEADMEN AND CAST-IN-PLACE CONCRETE DEADMEN SHALL BE CONSTRUCTED OF CLASS SI CONCRETE



ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - REVISED -	8-09-12	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 1:10000' / in.	CHECKED -	REVISED -			SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								

# 40' SINGLE LANE MEDIAN CROSSOVER


(POSTED SPEED LIMIT 55 MPH, WORK ZONE SPEED LIMIT 45 MPH)

**TYPICAL SECTION**



**SECTION A-A**

(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



**SECTION A-A**

(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

**GENERAL NOTES**

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(1340.88 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(1250.80 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(45.1 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(402.52 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.


The crossover is designed using a 45mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (Jointed) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (Jointed).

TABLE OF OFFSETS AND DROPS						
Distance feet from location station	0	60'	75'	100'	125'	143.73'
		ⓑ				ⓒ
Offsets feet from inside edge of pavement	20'	18'	15.32'	11.37'	8.06'	6.00'
	ⓓ					
Drop feet from inside edge of pavement	0.0'	0.0'	0.0'	0.0'	0.0'	0.0'



**TYPICAL PLAN**

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 8-27-13	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED - DATE -	REVISED - 12-07-10 REVISED -						CONTRACT NO.				FED. ROAD DIST. NO.
	PLOT DATE = 1/18/2017				SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.				

# 50' SINGLE LANE MEDIAN CROSSOVER


(POSTED SPEED LIMIT 55 MPH, WORK ZONE SPEED LIMIT 45 MPH)

## TYPICAL SECTION



### SECTION A-A

(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



### SECTION A-A

(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

## GENERAL NOTES

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(1634.94 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(1533.52 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(52.9 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(472.79 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.

The crossover is designed using a 45mph design speed.


The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (Jointed) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (Jointed).

TABLE OF OFFSETS AND DROPS

Distance feet from location station	0'	53'	75'	100'	125'	150.00'	161.73'
		ⓑ					ⓒ
Offsets feet from inside edge of pavement	25'	23'	18.57'	14.14'	10.37'	7.25'	6.00'
	ⓓ						
Drop feet from inside edge of pavement	0.5'	0.46'	0.37'	0.28'	0.021'	0.15'	0.12'



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - 8-27-13						SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO.
		CHECKED -	REVISED - 12-07-10		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								
		DATE -	REVISED -										


# 64' SINGLE LANE MEDIAN CROSSOVER

(POSTED SPEED LIMIT 55 MPH, WORK ZONE SPEED LIMIT 45 MPH)

## TYPICAL SECTION



**SECTION A-A**  
(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



**SECTION A-A**  
(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

**TABLE OF OFFSETS AND DROPS**

Distance feet from location station	0	46'	50'	75'	100'	125'	150'	175'	185.20'
Offsets feet from inside edge of pavement	32'	30'	29.02'	23.32'	18.28'	13.90'	10.17'	7.08'	6'
Drop feet from inside edge of pavement	0.64'	0.6'	0.58'	0.47'	0.37'	0.28'	0.20'	0.14'	0.12'

## GENERAL NOTES

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(2071.96 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(1956.64 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(62.5 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(558.24 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.


See District Standard 86.1 for details for the beveled pipe & guard.

The crossover is designed using a 45mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 8-27-13	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 12-07-10		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED -						FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

# 40' SINGLE LANE MEDIAN CROSSOVER


**TYPICAL SECTION (POSTED SPEED LIMIT 65 MPH OR HIGHER, WORK ZONE SPEED LIMIT 55 MPH)**

## GENERAL NOTES



### SECTION A-A

(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



### SECTION A-A

(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(1709.35 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(1596.03 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(57.1 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(509.64 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.


The crossover is designed using a 55mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).

Distance feet from location station	0	77'	100'	125'	150'	175'	183.23
Offsets feet from inside edge of pavement	20'	18'	14.79'	11.69'	8.98'	6.67'	6'
Drop feet from inside edge of pavement	0.4'	0.36'	0.3'	0.23'	0.18'	0.13'	0.12'



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.

TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 8-27-13		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED - 12-07-10						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# 50' SINGLE LANE MEDIAN CROSSOVER

**TYPICAL SECTION (POSTED SPEED LIMIT 65 MPH OR HIGHER, WORK ZONE SPEED LIMIT 55 MPH)**






TABLE OF OFFSETS AND DROPS									
Distance feet from location station	0'	68'	75'	100'	125'	150'	175'	200'	206.02'
Offsets feet from inside edge of pavement	25'	23'	21.84'	17.97'	14.50'	11.43'	8.76'	6.49'	6'
Drop feet from inside edge of pavement	0.5'	0.46'	0.44'	0.36'	0.29'	0.23'	0.175'	0.13'	0.12'



## SECTION A-A

(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



## SECTION A-A

(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

## GENERAL NOTES

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(2084.0 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(1956.55 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(67.1 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(598.67 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.


See District Standard 86.1 for details for the beveled pipe & guard.

The crossover is designed using a 55mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 8-27-13		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED - 12-07-10						FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			


# 64' SINGLE LANE MEDIAN CROSSOVER

**TYPICAL SECTION (POSTED SPEED LIMIT 65 MPH OR HIGHER, WORK ZONE SPEED LIMIT 55 MPH)**

## GENERAL NOTES



**SECTION A-A**  
(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



**SECTION A-A**  
(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(2651.79 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(2509.74 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(79.2 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(707.03 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.


The crossover is designed using a 55mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).

Distance feet from location station	0	60'	75'	100'	125'	150'	175'	200'	225'	236.83'
Offsets feet from inside edge of pavement	32'	30'	27.18'	22.80'	18.84'	15.27	12.11	9.35'	6.98	6'
Drop feet from inside edge of pavement	0.64'	0.6'	0.54'	0.456'	0.377'	0.31'	0.24'	0.187'	0.139'	0.12'



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.




TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED - DATE -	REVISED - 8-27-13 REVISED - 12-07-10		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017								FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

# 88' SINGLE LANE MEDIAN CROSSOVER

**TYPICAL SECTION (POSTED SPEED LIMIT 65 MPH OR HIGHER, WORK ZONE SPEED LIMIT 55 MPH)**

## GENERAL NOTES



① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(3704.06 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(3535.98 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(96.79 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(864.23 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.

The crossover is designed using a 55mph design speed.


The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).

**TABLE OF OFFSETS AND DROPS**

Distance feet from location station	0	50'	75'	100'	125'	150'	175'	200'	225'	250'	275'	283.50'
Offsets feet from inside edge of pavement	44'	42'	36.44'	31.30'	26.57'	22.25'	18.34'	14.83'	11.72'	9.01'	6.70'	6'
Drop feet from inside edge of pavement	0.88'	0.84'	0.73'	0.63'	0.53'	0.43'	0.37'	0.30'	0.23'	0.18'	0.13'	0.12'



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.

TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16
		DRAWN -	REVISED - 6-27-14
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 8-27-13
	PLOT DATE = 1/18/2017	DATE -	REVISED - 12-07-10

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**REGION 2 / DISTRICT 2 STANDARD**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# 40' TWO LANE MEDIAN CROSSOVER

(POSTED SPEED LIMIT 55 MPH, WORK ZONE SPEED LIMIT 45 MPH)

## TYPICAL SECTION





TABLE OF OFFSETS AND DROPS						
Distance feet from location station	0	76.95'	100'	125'	150'	168.69'
		ⓑ				ⓒ
Offsets feet from inside edge of pavement	20'	18'	14.22'	10.70'	7.79'	6.00'
	ⓓ					
Drop feet from inside edge of pavement	0.4'	0.36'	0.28'	0.21'	0.16'	0.12'

## GENERAL NOTES


- Construction of median crossover shall conform to the requirement of current Standard Specifications.
- Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.
- Pavement, subbase, & shoulder quantities are:
 

(1685.28 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(1572.43 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(57.28 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(511.45 Sq. Yds.)	HMA SHOULDERS 6"
- Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.
- See District Standard 61.2 or 68.1 for details for the slotted drain.
- See District Standard 86.1 for details for the beveled pipe & guard.
- The crossover is designed using a 45mph design speed.
- The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.
- The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106
- The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).



### SECTION A-A


(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



### SECTION A-A

(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving



## TYPICAL PLAN



- Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.
- Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.
- TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - 8-27-13										
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 4-04-11										
	PLOT DATE = 1/18/2017	DATE -	REVISED -										
					SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
									FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				


# 50' TWO LANE MEDIAN CROSSOVER

(POSTED SPEED LIMIT 55 MPH, WORK ZONE SPEED LIMIT 45 MPH)

**TYPICAL SECTION**



**SECTION A-A**  
(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

**SECTION A-A**  
(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

**GENERAL NOTES**

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(2029.23 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(1904.29 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(65.64 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(586.07 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.


The crossover is designed using a 45mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).

TABLE OF OFFSETS AND DROPS								
Distance feet from location station	0	69.72'	75'	100'	125'	150'	175'	188.01'
Offsets feet from inside edge of pavement	25'	23'	21.95'	17.35'	13.37'	9.99'	7.21'	6.00'
Drop feet from inside edge of pavement	0.5'	0.46'	0.44'	0.35'	0.27'	0.20'	0.14'	0.12'



**TYPICAL PLAN**

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - 8-27-13						SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO.
		CHECKED -	REVISED - 4-04-11		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								
		DATE -	REVISED -										


# 64' TWO LANE MEDIAN CROSSOVER

(POSTED SPEED LIMIT 55 MPH, WORK ZONE SPEED LIMIT 45 MPH)

**TYPICAL SECTION**



**SECTION A-A**  
(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

**SECTION A-A**  
(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

**GENERAL NOTES**

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(2534.76 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(2394.89 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(75.73 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(676.15 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.

The crossover is designed using a 45mph design speed.


The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).

**TABLE OF OFFSETS AND DROPS**

Distance feet from location station	0	62.41'	75'	100'	125'	150'	175'	200'	212.87'
Offsets feet from inside edge of pavement	32'	30'	27.14'	21.92'	17.33'	13.35'	9.97'	7.20'	6.00'
Drop feet from inside edge of pavement	0.64'	0.60'	0.54'	0.44'	0.35'	0.27'	0.20'	0.14'	0.12'



**TYPICAL PLAN**

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 1-05-16	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED - 8-27-13		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
		CHECKED -	REVISED - 4-04-11		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								
		DATE -	REVISED -										


# 40' TWO LANE MEDIAN CROSSOVER

**TYPICAL SECTION (POSTED SPEED LIMIT 65 MPH OR HIGHER, WORK ZONE SPEED LIMIT 55 MPH)**

## GENERAL NOTES



**SECTION A-A**  
(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

**SECTION A-A**  
(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(2142.56 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(2003.87 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(71.01 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(634.04 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.


The crossover is designed using a 55mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).

Distance feet from location station	0	100.33'	125'	150'	175'	200'	220.57'
Offsets feet from inside edge of pavement	20'	18'	14.88'	12.07'	9.60'	7.48'	6.00'
Drop feet from inside edge of pavement	0.40'	0.36'	0.30'	0.24'	0.19'	0.15'	0.12'



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 8-27-13		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED - 4-04-11		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								
<b>40' TWO LANE MEDIAN CROSSOVER (45 MPH WORK ZONE SPEED LIMIT) 82.1</b>													


# 50' TWO LANE MEDIAN CROSSOVER

**TYPICAL SECTION (POSTED SPEED LIMIT 65 MPH OR HIGHER, WORK ZONE SPEED LIMIT 55 MPH)**

## GENERAL NOTES



**SECTION A-A**  
(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

**SECTION A-A**  
(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(2593.23 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(2438.79 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(81.92 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(731.46 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.


The crossover is designed using a 55mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).

Distance feet from location station	0	90.88'	100'	125'	150'	175'	200'	225'	246'
		ⓑ							ⓒ
Offsets feet from inside edge of pavement	25'	23'	21.63'	18.10'	14.93'	12.11'	9.64'	7.52'	6.00'
Drop feet from inside edge of pavement	0.50'	0.46'	0.43'	0.36'	0.30'	0.24'	0.19'	0.15'	0.12'



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - REVISED -	1-05-16 6-27-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED -	8-27-13		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED -	4-04-11						FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
<b>50' TWO LANE MEDIAN CROSSOVER (55 MPH WORK ZONE SPEED LIMIT) 83.1</b>														


# 64' TWO LANE MEDIAN CROSSOVER

**TYPICAL SECTION (POSTED SPEED LIMIT 65 MPH OR HIGHER, WORK ZONE SPEED LIMIT 55 MPH)**

## GENERAL NOTES



**SECTION A-A**  
(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

**SECTION A-A**  
(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(3256.59 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(3082.80 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(95.09 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(848.99 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.


The crossover is designed using a 55mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (JOINTED) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (JOINTED).

Distance feet from location station	0	81.32'	100'	125'	150'	175'	200'	225'	250'	275'	278.80'
Offsets feet from inside edge of pavement	32'	30'	26.79'	22.80'	19.16'	15.88'	12.95'	10.37'	8.14'	6.26'	6.00'
Drop feet from inside edge of pavement	0.64'	0.60'	0.54'	0.46'	0.38'	0.32'	0.26'	0.21'	0.16'	0.13'	0.12'



## TYPICAL PLAN

Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.



TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED -	REVISED - 8-27-13		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017	DATE -	REVISED - 4-04-11		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								
<b>64' TWO LANE MEDIAN CROSSOVER (55 MPH WORK ZONE SPEED LIMIT) 84.1</b>													


# 88' TWO LANE MEDIAN CROSSOVER

**TYPICAL SECTION (POSTED SPEED LIMIT 65 MPH OR HIGHER, WORK ZONE SPEED LIMIT 55 MPH)**

## GENERAL NOTES



**SECTION A-A**  
(USE TO MAINTAIN MEDIAN DRAINAGE THROUGH THE CROSSOVER)



① Duct tape or wood blocks shall be used to cover slotted drain during construction of crossover paving

**SECTION A-A**  
(WHEN CROSSOVER IS AT MEDIAN HIGH POINT)

Construction of median crossover shall conform to the requirement of current Standard Specifications.

Slotted drain shall be constructed of 14 or 16 gauge corrugated metal roadway pipe modified to accommodate slotted drain as shown.

Pavement, subbase, & shoulder quantities are:

(4481.22 Sq. Yds.)	AGGREGATE SUBGRADE IMPROVEMENT, 12"
(4279.37 Sq. Yds.)	P.C.C. PAVEMENT 10" (JOINTED)
(114.14 Tons)	2" HMA SURFACE COURSE, MIX "C", N50
(1019.14 Sq. Yds.)	HMA SHOULDERS 6"

Elbows and Caps shall be considered included to the SLOTTED DRAIN 12" WITH 6" SLOT.

See District Standard 61.2 or 68.1 for details for the slotted drain.

See District Standard 86.1 for details for the beveled pipe & guard.


The crossover is designed using a 55mph design speed.

The end of the pipe guard shall be set where a minimum 1:4 front slope can be constructed from each side of pipe guard to the HMA shoulder.

The PCC Pavement 10" (Jointed) shall be constructed according to Section 420 of the Standard Specifications and Highway Standards 420001, 420101, & 420106

The PCC Pavement 10" (Jointed) shall be tied to adjacent existing concrete pavement and the concrete encasement for the slotted drain. The tie bars shall be No.6 bars 24" long @ 30" cts, and installed according to the applicable portions of Article 420.05(b) of the Standard Specifications. The cost of the bars to be included in the cost of the PCC Pavement 10" (Jointed).

Distance feet from location station	0	70.29'	75'	100'	125'	150'	175'	200'	225'	250'	275'	300'	325'	329.24'
Offsets feet from inside edge of pavement	44'	42'	41.00'	35.93'	31.23'	26.86'	22.86'	19.22'	15.94'	13.00'	10.42'	8.18'	6.29'	6.00'
Drop feet from inside edge of pavement	0.88'	0.84'	0.82'	0.72'	0.62'	0.54'	0.46'	0.38'	0.32'	0.26'	0.21'	0.16'	0.13'	0.12'



## TYPICAL PLAN


Unless otherwise specified, when the median crossover is to be removed, the Contractor shall be required to saw full-depth along the shoulder line 6' from edge of pavement). The 6' adjacent to the edge of pavement shall remain in place and be used as shoulders. The cost of Sawing shall be included in the Pavement Removal.

Longitudinal joints shall be sawed at a max 12' width. All joints shall be sealed.

TRAFFIC CONTROL STANDARD 701416 IS TO BE USED WITH THIS DETAIL

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 1-05-16 REVISED - 6-27-14	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:8000' / in.	CHECKED - DATE -	REVISED - 8-27-13 REVISED - 4-04-11		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	CONTRACT NO.			
	PLOT DATE = 1/18/2017								FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

# BEVELED PIPE & GUARD DETAIL FOR MEDIAN CROSSOVER



PLAN VIEW

12 PIPE REINFORCING SCHEDULE			
Mark Req'd	Bar Size	Length	No.
a	5	110	2
b	5	32	2
c	8	34	10

18 PIPE REINFORCING SCHEDULE			
Mark Req'd	Bar Size	Length	No.
a	5	162	2
b	5	38	2
c	8	40	18

**GENERAL NOTES:**


Details shown hereon are for the construction of beveled pipe and guard. Alternate designs, methods of construction or materials may be submitted to the Engineer for approval. All methods of construction and materials involved shall conform to current Standard Specifications.

Reinforcing steel used in construction of "Beveled Pipe and Guard" shall be deformed bars meeting the requirements of Article 1006.10 of the Standard Specifications. All steel bars shall be hot-dip galvanized in accordance with ASTM A 123 specifications.


Concrete used in construction of the beveled pipe and guard shall be Class "SI" Concrete.

The corrugated metal pipe shall be cut to fit the 1:8 foreslope. Slots shall be cut into the C.M.P. for placement of the 'b' and 'c' bars. After the foreslope has been placed, the 'b' and 'c' bars shall be fitted into the slots cut in the C.M.P. so they will be in proper position when the concrete collar is poured.

This work shall be paid for at the contract unit price per Each for "Beveled Pipe and Guard", as shown hereon and as directed by the Engineer.




SECTION A-A



SECTION B-B

TABLE OF DIMENSIONS				
PIPE SIZE	A	B	C	D
12	9' - 6"	36	6'	10'
18	13' - 10"	42	10' - 4"	14' - 10"


## TYPICAL SECTION THRU CENTERLINE OF MEDIAN CROSSOVER



ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED.


FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED -	REVISED - 5-27-09	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:10000' / 1"	DRAWN -	REVISED -					CONTRACT NO.				
PLOT DATE = 1/18/2017	CHECKED -	REVISED -	DATE -	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT				

# TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)



PLAN

\* With standard washers. After tightening, cut the anchor bolts flush with the nuts and damage the nuts to prevent them from loosening.



ELEVATION

## GENERAL NOTES

This work shall be done according to Section 631 of the Standard Specifications and this detail.

See Standard 630001 for details of guardrail not shown.

Thrie beam rail shall be bolted to block-out at all posts.

Posts located above pier foundation shall have plate attached to post and anchored to foundation.

All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).

All dimensions are in inches unless otherwise shown.

The Traffic barrier Terminal, Type 6B (Special) will be measured for payment, complete in place, in units of each.

This work shall be paid for at the contract unit price per each for TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL).






PLATE DETAIL

FILE NAME = District 2 Standard	USER NAME = ID07/District 2	DESIGNED -	REVISED - 10-18-11	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REGION 2 / DISTRICT 2 STANDARD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:10000' / in.	DRAWN -	REVISED -					CONTRACT NO.				
PLOT DATE = 1/18/2017	CHECKED -	DATE -	REVISED -	SCALE:      SHEET NO.      OF      SHEETS      STA.      TO STA.			FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT				


# TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)




SECTION A-A




WOOD BLOCKOUT DETAIL




THRIE BEAM END SHOE DETAIL




MODIFIED THICKNESS DETAIL  
WOOD BLOCKOUTS A, B, C, & D



WOOD BLOCKOUT D



WOOD BLOCKOUT C



WOOD BLOCKOUT A & B

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 10-18-11 REVISED -
	PLOT SCALE = 1:1000 1/4 in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -


STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD


SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

# DETAILS OF PLANTING AND BRACING TREES





TREES SMALLER THAN 4 1/2 IN DIAMETER




SMALL	A	B	C	D	E	F
TREE SIZE	DIAMETER OF BALL OR ROOT SYS.	DEPTH OF HOLE EXCAVATION	WIDTH OF HOLE EXCAVATION	THICKNESS OF MULCH COVER	DEPTH OF BALL OR ROOT SYS.	VOLUME OF MULCH COVER CU. YDS.
5'-6'	16	10	30	4	12	0.54
5'-6' BB	16	10	30	4	12	0.54
6'-7' BB	18	12	30	4	14	0.54
7'-8' BB	20	11	30	4	13	0.54
8'-10' BB	24	14	36	4	16	0.61
10'-12' BB	26	15	36	4	17	0.61

LARGE	A	B	C	D	E	F
TREE SIZE	DIAMETER OF BALL OR ROOT SYS.	DEPTH OF HOLE EXCAVATION	WIDTH OF HOLE EXCAVATION	THICKNESS OF MULCH COVER	DEPTH OF BALL OR ROOT SYS.	VOLUME OF MULCH COVER CU. YDS.
0-2	20	11	36	4	13	0.61
2-2 1/2 BB	24	14	48	4	16	0.78
2 1/2-3 BB	28	17	48	4	19	0.78
3-3 1/2 BB	32	17	60	4	19	0.96
3 1/2-4 BB	36	20	60	4	22	0.96
4-4 1/2 BB	40	22	72	4	24	1.16
4 1/2-5 BB	44	24	72	4	26	1.16
5-5 1/2 BB	48	27	84	4	29	1.38




PLANT HARDINESS ZONE MAP

U.S. DEPARTMENT OF AGRICULTURE  
AGRICULTURAL RESEARCH SERVICE  
PUBLICATION NO. 814



TREES OVER 4 1/2 IN DIAMETER



ALL DIMENSIONS ARE IN INCHES  
UNLESS OTHERWISE NOTED.

FILE NAME = District 2 Standard	USER NAME = IDOT/District 2	DESIGNED - DRAWN -	REVISED - 10-18-11 REVISED -
	PLOT SCALE = 1,0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/18/2017	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

REGION 2 / DISTRICT 2 STANDARD

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				