

SUMMARY OF QUANTITIES

URBAN
100% STATE

| CODE NUMBER | ITEM | UNIT | TOTAL QUANTITY | SFTY-2A STATE |
|-------------|--|--------|----------------|---------------|
| 50102400 | CONCRETE REMOVAL | CU YD | 77 | 77 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 78 | 78 |
| 50300300 | PROTECTIVE COAT | SQ YD | 111 | 111 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 15,040 | 15,040 |
| 50800515 | BAR SPLICERS | EACH | 74 | 74 |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 159 | 159 |
| 52000340 | NEOPRENE EXPANSION JOINT 4" | FOOT | 54 | 54 |
| 67000400 | ENGINEERS FIELD OFFICE, TYPE A | CAL MO | 6 | 6 |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 2,589 | 2,589 |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 988 | 988 |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 988 | 988 |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 36 | 36 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING -LINE 4" | FOOT | 1,728 | 1,728 |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING -LINE 6" | FOOT | 140 | 140 |
| * 78100300 | REPLACEMENT REFLECTOR | EACH | 50 | 50 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 682 | 682 |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 102 | 102 |
| X0322933 | SILICONE JOINT SEALER, 2.5" | FOOT | 51 | 51 |
| X0320087 | POLYMER CONCRETE | CU FT | 5.3 | 5.3 |
| X0323076 | SILICONE JOINT SEALER, 1 3/4" | FOOT | 53 | 53 |
| X0323077 | SILICONE JOINT SEALER, 2 3/4" | FOOT | 51 | 51 |
| X0325305 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 447 | 447 |
| X0325775 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH | FOOT | 6,964 | 6,964 |
| X0325837 | WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH | FOOT | 394 | 394 |
| X0325842 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS | SQ FT | 73 | 73 |
| X0325737 | TEMPORARY TRAFFIC SIGNAL TIMING | EACH | 2 | 2 |
| Z0010605 | CLEANING DRAINAGE SYSTEM | L SUM | 1 | 1 |
| Z0030240 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2 | EACH | 2 | 2 |
| Z0030340 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2 | EACH | 2 | 2 |
| Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 | 1 |
| Z0073200 | TEMPORARY SHORING AND CRIBBING | EACH | 4 | 4 |

* DENOTES SPECIALTY ITEM

H:\Jobs\2009\20093023-02\CAD\Site\00\016\016-sht-500.dgn
11/2/2009 10:53 PM

| | | | | | | | | | | | |
|-------------|--------------------|-----------------|-----------|---|--|--------------------|---------------------|--------|--------------|---------------------------|--|
| FILE NAME = | USER NAME = .USER. | DESIGNED - RS | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | IL 50 (CICERO AVENUE) SUMMARY OF QUANTITIES | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | TOTAL SHEET NO. | |
| | | DRAWN - EF | REVISED - | | | 350 | 50-1 VB-1-BR | COOK | 33 | 3 | |
| | | CHECKED - | REVISED - | | | CONTRACT NO. 60H76 | | | | | |
| | | DATE - 10/23/09 | REVISED - | | | SCALE: | SHEET NO. OF SHEETS | STA. | TO STA. | ILLINOIS FED. AID PROJECT | |

Rev