

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY		SURVEILLANCE		BRIDGE	BRIDGE	BRIDGE	BRIDGE	TRAFFIC SIGNS	
					90% FED 10% STATE		90% FED 10% STATE		SN 016-1130 SN 016-1131 SN 016-1132 SN 016-1133	SN 022-0005 SN 022-0006	SN 022-0007 SN 022-0008	SN 016-0083 SN 016-0084 SN 016-1134 SN 016-1135		
					COOK	DUPAGE	COOK	DUPAGE	COOK	DUPAGE	DUPAGE	COOK		
					CONSTRUCTION TYPE CODE								COOK	DUPAGE
					1000-2A	1000-2A	Y032-1F	Y032-1F	X171-2A	X231-2A	X271-2A	X271-2A		
*	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	66,000	40,800	25,200								
*	72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	100									62	38
*	78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	6,600	4,080	2,520								
*	72000205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	749									423	326
*	78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	1,198	254	944								
*	72000305	SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	11,264									6,805	4,459
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	5,663	4,863	800								
*	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	10									6	4
*	78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	97,334	47,255	50,079								
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	252									198	54
*	78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	36,032	22,346	13,686								
*	78000105	WOOD SIGN SUPPORT, SPECIAL	FOOT	594									396	198
*	78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	5,353	3,304	2,049								
*	81200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	43									28	15
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	496	132	364								
*	X0326838	REMOVE SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	45									24	19
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	171	118	53								
*	X0326839	REMOVE SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	307									92	215
*	78100300	REPLACEMENT REFLECTOR	EACH	487	292	195								
*	X0326840	REMOVE SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	10,534									6,137	4,397
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4									
*	X0326841	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL)	EACH	36									26	10
*	78200450	MONODIRECTIONAL GUARD RAIL REFLECTORS	EACH	300	180	120								
*	X0326842	MILE POST MARKER ASSEMBLY (SPECIAL)	EACH	18									10	8
*	78200530	BARRIER WALL MARKERS, TYPE C	EACH	1,354	812	542								
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	49,285	29,963	19,322								
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	496	298	198								
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	100			50	50						
	X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	24,443					8,612	3,050	4,223	8,558		
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1349	891	458								
	X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	6									6	
	X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	1,455					94	394	389	578		
	X0325391	EXPANDED POLYSTYRENE FILL	CU YD	674						674				
	X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.6	0.4								
	X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	3				3						
	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	207,612	130,208	77,404								
	X0325840	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	20,396	13,483	6,913								
	X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	545	327	218								
	X0325876	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH	FOOT	112,594	63,363	49,231								
	X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	40,474	21,070	19,404								
	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	10	6	4								
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	0.6	0.4								
	X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	149	89	60								
*	X8730312	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 4/C, TWISTED, SHIELDED	FOOT	4,068			1313	2755						
*	X8850102	INDUCTION LOOP	FOOT	1,329			599	730						
	Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	5.0							5.0			
	Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	20,816					8,612		3,646	8,558		
	Z0006220	BRIDGE DECK HYDRO-SCARIFICATION 2 1/4"	SQ YD	3,628						3,050	578			
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.6	0.4								

*Specialty Items

FILE NAME =	DESIGNED - AJP	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...prpIn.ABC.C4.sog.83.dgn	DRAWN - TMB	REVISED -							290	2009-0998R	COOK/DUPAGE	309	5
USER NAME = tblank	CHECKED - JMM	REVISED -			SCALE: N.T.S. SHEET NO. 3 OF 3 SHEETS STA. TO STA.				CONTRACT NO. 60157				
PLOT DATE = 11/16/2009	DATE - 10/16/09	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								