F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3578	15VB-1-R-1	COOK	243	3
STA.		TO STA.		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 62388

SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QTY.	80% FEDERAL 20% STATE (ACM) ROADWAY	80% FEDERAL 20% STATE (ACBRF) BRIDGE	80% FEDERAL 20% STATE (ACM) RETAINING WALL	80% FEDERAL 20% STATE (ACM) TRAFFIC SIG. INTERCON.	80% FED 15% STATE 5% OAK LAWN SW HWY @ RIDGELAND	100% OAK LAWN LIGHTING	100% CHICAGO RIDGE LIGHTING	100% CHICAGO RIDGE EMERGENCY PRE-EMPTION	100% CHICAGO RIDGE PED. PUSH BUTTONS	100% CHICAGO RIDGE BRIDGE SW BARRIER
					J000-2A	X371-2A	Y007	Y031-1F	YO31-1F	YO30-1E	YO30-1E	Y031-3D	Y031-1F	SFTY-2A
*	20101100	TREE TRUNK PROTECTION	EACH	10	10									
*	25200200	SUPPLEMENTAL WATERING	UNIT	114	114									
	28000510	INLET FILTERS	EACH	20	20									
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1								
	50202901	COFFERDAM (LOCATION-1)	EACH	1		1								
	50202902	COFFERDAM (LOCATION-2)	EACH	1		1								
	50500505	STUD SHEAR CONNECTORS	EACH	26,212		26,160	52							
	50800515	BAR SPLICERS	EACH	3,985		3,985								
	51204650	PILE SHOES	EACH	276		276								
	51500100	NAME PLATES	EACH	1		1								
	52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	72		72								
	52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	46		46								
	56400100	FIRE HYDRANTS TO BE MOVED	EACH	2	2									
	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	2		1							
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2	2									
	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1									
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	6									
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2									
	60255500	MANHOLES TO BE ADJUSTED	EACH	5	5									
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1									
	60260100	INLETS TO BE ADJUSTED	EACH	1	1									
	60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1									
	60500050	REMOVING CATCH BASINS	EACH	7	7									
	60500060	REMOVING INLETS	EACH	4	4									
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2									
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	2	2									
	67000600	ENGINEER'S FIELD LABORATORY	CAL MO	20	20									
	67100100	MOBILIZATION	L SUM	1	0.4	0.5	0.1							
	70101800	TRAFFIC CONTROL AND PROTECTION,(SPECIAL)	L SUM	1	1.0									
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	515	515									
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	80	80									
1	M66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2,190	2,190									
	66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1									
	66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3									

* SPECIALTY ITEMS

1 Rev. 12-29-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAU 3578 (SOUTHWEST HIGHWAY)
OVER B&O RAILROAD AND STONY CREEK
SUMMARY OF QUANTITIES

SCALE: DRAWN BY: DES
DATE: 5-08-2009 CHECKED BY: JJC

PATRICK ENGINEERING INC.
LISLE, ILLINOIS

tkoeppen(Rdwy_Lisle) 6/26/2009 8:55:40 AM PDF(Grey_Large).plt Q:\IDOT\9556_A0\Drawings\RDWY\shts\RDS_02_soq.dgn