

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3578	15VB-1-R-1	COOK	243	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62388				

ACM    ACBRF    ←    ACM    →

SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	80% FEDERAL 20% STATE				80% FED 15% STATE	100% OAK	100% CHICAGO RIDGE									
				ROADWAY	BRIDGE	RETAINING WALL	TRAFFIC SIG. INTERCON.	5% OAK LAWN SW HWY @ RIDGELAND	LAWN LIGHTING	LIGHTING	EMERGENCY PRE-EMPTION	PED. PUSH BUTTONS	BRIDGE SW BARRIER						
				J000-2A	X371-2A	Y007	Y031-1F	Y031-1F	Y030-1E	Y030-1E	Y031-3D	Y031-1F	SFTY-2A						
M5210024	ANCHOR BOLTS, M36	EACH	196		196														
M5500030	STORM SEWERS, CLASS A, TYPE 1 300MM	METER	97	97															
M5510025	STORM SEWER REMOVAL 300MM	METER	135	135															
M5610950	ADJUSTING WATER MAIN 350MM	METER	45							45									
M5870300	CONCRETE SEALER	SQ M	99		99														
M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	122		109	13													
M6010610	PIPE UNDERDRAINS 150MM	METER	439	439															
M6011100	PIPE UNDERDRAINS FOR STRUCTURES 100MM	METER	75		64	11													
M6020185	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 24 FRAME AND GRATE	EACH	10	10															
M6060400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.15	METER	18	18															
M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	658	644										14					
M6063600	CONCRETE MEDIAN SURFACE, 100 MM	SQ M	82	82															
M6066000	CORRUGATED MEDIAN	SQ M	34	34															
* M6300101	STEEL PLATE BEAM GUARDRAIL, TYPE A, <sup>1.83M</sup> POSTS	METER	20	20															
M6320030	GUARDRAIL REMOVAL	METER	98	98															
M6380605	TEMPORARY MODULAR GLARE SCREEN	METER	520	520															
M6640110	CHAIN LINK FENCE, 1.5 METER	METER	222	222															
* M7030210	TEMPORARY PAVEMENT MARKING- LETTERS AND SYMBOLS	SQ M	14	14															
* M7030220	TEMPORARY PAVEMENT MARKING- LINE 100MM	METER	2,307	2,307															
* M7030240	TEMPORARY PAVEMENT MARKING- LINE 150MM	METER	82	82															
* M7030260	TEMPORARY PAVEMENT MARKING- LINE 300MM	METER	9	9															
* M7030280	TEMPORARY PAVEMENT MARKING- LINE 600MM	METER	25	25															
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	1,845	1,845															
M7040100	TEMPORARY CONCRETE BARRIER	METER	994	994															
M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	499	499															
* M7200200	SIGN PANEL - TYPE 2	SQ M	15					15											
* M7800115	THERMOPLASTIC PAVEMENT MARKING- LINE 150MM	METER	115																
* M7800600	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	7	7															
* M7802010	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 100MM	METER	3,931	3,931															
* M7800605	EPOXY PAVEMENT MARKING - LINE 100 MM	METER	4,590	4,590															
* M7802015	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 150MM	METER	901	786															
* M7800615	EPOXY PAVEMENT MARKING - LINE 150 MM	METER	36	36															
* M7802030	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 300MM	METER	39	39															
* M7800625	EPOXY PAVEMENT MARKING - LINE 300 MM	METER	27	27															
* M7802060	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 600MM	METER	84	84															
* M7800640	EPOXY PAVEMENT MARKING - LINE 600 MM	METER	15	15															

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAU 3578 (SOUTHWEST HIGHWAY)  
OVER B&O RAILROAD AND STONY CREEK  
SUMMARY OF QUANTITIES

SCALE:  
DATE: 6/17/09

DRAWN BY: DES  
CHECKED BY: JJC

Rev.

tkoeppen(Rdwy\_Lisle) 6/26/2009 10:32:32 AM PDF(Grey\_Large).plt C:\DOT\9556\_A0\Drawings\RDWY\shts\Rd\5\_02\_soc.dgn

