

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326		McHENRY	502	8
STA. 9+35.22		TO STA. 142+08.53		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• (105X & 106) WRS-2				

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		SIDEWALK	BOX CULVERT	KREUTZER	MAIN	TRAFFIC SIGNALS				LIGHTING	WATER MAIN & SAN. SEWER
				KANE COUNTY	McHENRY COUNTY					ALGONQUIN	REED	EVP	INTERCONNECT		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE					50% STATE 50% LOCAL	50% STATE 50% LOCAL	100% LOCAL	80% FEDERAL 20% STATE		
# 83100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	J000-2A	J000-2A	SFTY-1B	X028-2A	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-5D	Y031-1F	Y030-1E	Y060
# 83200310	GUARDRAIL REMOVAL	FOOT	1,817												
# 86400305	CHAIN LINK FENCE, 6'	FOOT	57												
# 86400535	CHAIN LINK FENCE, 6' ATTACHED TO STRUCTURE	FOOT	70												
# 87000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	24												
# 87100100	MOBILIZATION	L SUM	1												
# 89800105	UNDERGROUND STORAGE TANK REMOVAL	EACH	1												
# 89900200	NON-SPECIAL WASTE DISPOSAL	CU YD	470												
# 89900400	SPECIAL WASTE GROUND WATER DISPOSAL	GALLON	345												
# 89900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1												
# 89900530	SOIL DISPOSAL ANALYSIS	EACH	3												
# 89901000	BACKFILL PLUGS	CU YD	120												
# 70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1												
# 70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	555												
# 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	980	218	768										
# 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	71,104	9,433	61,671										
# 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,128	546	2,582										
# 70300280	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	327	113	214										
# 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	620	67	553										
# 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	26,666		26,666										
# 70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,740		2,740										
# 70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,220		1,220										
# 70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	50		50										
# 72000100	SIGN PANEL - TYPE 1	SQ FT	832	23	809			73	132	73	27				
# 72000100	METAL POST - TYPE A	FOOT	619	42	577				104						
# 72000200	METAL POST - TYPE B	FOOT	252		252										
# 78008200	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	SQ FT	2,710	297	2,413										
# 78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	18,499	2,226	16,273										
# 78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	21,582	1,228	20,354										
# 78008240	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	FOOT	200	280											
# 78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	2,577	626	1,951										
# 78008270	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24"	FOOT	1,356	84	1,272										
# 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,142	124	1,018										
# 78100100	GUARDRAIL MARKERS, TYPE A	EACH	36	3	33										
# 78300100	PAVEMENT MARKING REMOVAL	SQ FT	9,457	69	9,388										
# 80400100	ELECTRIC SERVICE INSTALLATION	EACH	3												
# 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1												
# 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	12,156					546	637	1,051	653		8884	385	
# 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	384					116	65	85	118				
# 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	171					44	68	59					
# 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	236					75	74	87					
# 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	40					10	10	10	10				
# 81017510	CONDUIT IN TRENCH, 1" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	580												580
# 81017515	CONDUIT IN TRENCH, 1 1/4" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	1,120												1,120
# 81018500	CONDUIT, PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	3,292					325	482	274	148		1,113	910	
# 18201000	TERMINAL MARKER - DIRECT APPLIED	EACH	72	2	70										

SPECIALTY ITEM

PLOT DATE = Friday, August 07, 2009
 FILE NAME = S:\11-ROAD\01-11-084-012.sum.of.quant.dgn
 PLOT SCALE = 1:1
 USER NAME = 3698



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 47
SUMMARY OF QUANTITIES

SCALE: VERT. NO SCAL.
 HORIZ. DATE: 8/5/2009

DRAWN BY: E.D.
 CHECKED BY: A.A.C.

Rev. 12-28-09