

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	*	McHENRY	502	5
STA. 9+35.22		TO STA.142+08.53		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* (105X & 106) WRS-2				

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		SIDEWALK	BOX CULVERT	KREUTZER	MAIN	TRAFFIC SIGNALS				INTERCONNECT	LIGHTING	WATER MAIN & SAN SEWER			
				KANE COUNTY	McHENRY COUNTY					ALGONQUIN	REED	EVP	100% LOCAL				80% FEDERAL	100% LOCAL	100% LOCAL
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE					50% STATE 50% LOCAL	50% STATE 50% LOCAL	50% STATE 25% LOCAL 25% COUNTY	50% STATE 50% LOCAL				100% LOCAL	80% FEDERAL 20% STATE	100% LOCAL
42001300	PROTECTIVE COAT	SQ YD	152,422		13,198														
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	288		288														
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	216,102		32,370	104,332													
42400800	DETECTABLE WARNINGS	SQ FT	252		252														
44000100	PAVEMENT REMOVAL	SQ YD	81,941	11,880	70,272														
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	5,038		5,038														
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	368		368														
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	15,812	380	15,492														
44000300	CURB REMOVAL	FOOT	2,287		2,287														
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	23,459	1,582	21,877														
44000600	SIDEWALK REMOVAL	SQ FT	21,444		21,444														
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	27		27														
44002805	ISLAND REMOVAL	SQ FT	3,424	1,844	1,580														
44003100	MEDIAN REMOVAL	SQ FT	4,787		4,787														
44004250	PAVED SHOULDER REMOVAL	SQ YD	4,002	703	3,299														
44213200	SAW CUTS	FOOT	94		94														
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	20	20															
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	859	112	727														
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,943	1,313	1,630														
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1				1												
50105220	PIPE CULVERT REMOVAL	FOOT	1,834	81	1,753														
50200100	STRUCTURE EXCAVATION	CU YD	937		937														
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	651				651												
50300225	CONCRETE STRUCTURES	CU YD	337		293.5											43.5			
50300300	PROTECTIVE COAT	SQ YD	106		106														
50800105	REINFORCEMENT BARS	POUND	97,450				97,450												
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	24,580		22,750		610									1230			
50800305	WELDED WIRE FABRIC 6X6	SQ YD	304		2											302			
50800515	BAR SPLICERS	EACH	148				148												
51500100	NAME PLATES	EACH	1				1												
54003000	CONCRETE BOX CULVERTS	CU YD	415				415												
54213857	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8	2	6														
54213860	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1		1														
54213863	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1														
54213869	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4		4														
54213887	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2		2														
54214509	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24"	EACH	2		2														
54214725	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	1		1														
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	4		4														
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	2		2														
54248130	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 24"	EACH	2		2														
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	1		1														
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	3023	64	2959														
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	225		225														

McHenry Co. 100% HUNTLEY

SPECIALTY ITEM

PLOT DATE = Friday, August 07, 2009
 FILE NAME = S:\11-CADD\01-111-004-012-sum-of-quant.dgn
 PLOT SCALE = 1:1
 USER NAME = 3699



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 47
SUMMARY OF QUANTITIES

SCALE: VERT. NO SCALE
 HORIZ. NO SCALE
 DATE: 8/5/2009

DRAWN BY: E.D.
 CHECKED BY: A.A.C.

Rev.