

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	*	McHENRY	502	12
STA. 9+35.22		TO STA.142+08.53		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* (105X & 106) WRS-2

McHenry County

100% HUNTLEY

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		SIDEWALK	BOX CULVERT	TRAFFIC SIGNALS				LIGHTING	WATER MAIN & SAN. SEWER				
				80% FEDERAL	80% FEDERAL			50% STATE	80% FEDERAL	50% STATE	50% STATE			100% LOCAL	80% FEDERAL	100% LOCAL	100% LOCAL
				20% STATE	20% STATE			50% LOCAL	20% STATE	50% LOCAL	50% LOCAL			100% LOCAL	20% STATE	100% LOCAL	100% LOCAL
X0326723	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LETTERS AND SYMBOLS	SQ FT	473		473												
X0326724	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 4"	FOOT	2,864		2,864												
X0326725	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 6"	FOOT	3,699		3,699												
X0326726	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 12"	FOOT	403		403												
X0326727	WET REFLECTIVE PREFORMED PLASTIC PAVEMENT MARKINGS-LINE 24"	FOOT	121		121												
X0326732	HOT-MIX ASPHALT SURFACE REMOVAL FOR RECESSED PAVEMENT MARKINGS, 0.1 INCH DEPTH	SQ FT	2,467		2,467												
X0326730	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	175					50	50	25	50						
X0326728	WET PAVEMENT MARKING TAPE, TYPE III-LETTERS AND SYMBOLS	SQ FT	4,170	338	3,832												
X0326729	WET PAVEMENT MARKING TAPE, TYPE III-4 INCH	FOOT	200,413	32,470	167,943												
X0326730	WET PAVEMENT MARKING TAPE, TYPE III-6 INCH	FOOT	16,714	1,686	15,028												
X0326731	WET PAVEMENT MARKING TAPE, TYPE III-12 INCH	FOOT	2,642	619	2,023												
X0326733	SANITARY PVC SDR 26, 6"	FOOT	681									881					
X0326734	SANITARY PVC SDR 26, 8"	FOOT	1,916									1916					
X0326735	SANITARY PVC SDR 26, 10"	FOOT	270									270					
X0326736	SANITARY PVC SDR 26, 12"	FOOT	480									480					
X0326737	SANITARY PVC SDR 26 (WATER MAIN QUALITY), 8"	FOOT	204									204					
X0326400	MANHOLES, DROP TYPE, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1									1					
X0326738	CLEAN SANITARY MANHOLE	EACH	2									2					
X0326740	LINE MANHOLE	FOOT	34									34					
X0326739	CLEAN SANITARY SEWER	FOOT	101									101					
X006247	SANITARY SEWER REMOVAL	FOOT	3,171									3171					
X0326741	REPLACE FRAMES AND ADJUSTMENTS	EACH	2									2					
X0326744	PLUG PIPE PENETRATION	EACH	1									1					
X0326745	SANITARY SEWER LIFT STATION	L SUM	1									1					
X0326746	SANITARY SEWER LIFT STATION ABANDONMENT	L SUM	1									1					
X0326747	SANITARY FORCE MAIN, 6"	FOOT	925		630							295					
X0326748	CLEAN-OUT MANHOLE	EACH	1		1							1					
X0061100	AIR RELEASE VALVE	EACH	1									1					
X0326750	STEEL CASING PIPE, BORE AND JACK, 18"	FOOT	70		70												
X0067450	STEEL CASINGS 15"	FOOT	67									67					
X0326755	VALVE VAULT, 5' DIAMETER, WITH 12" VALVE	EACH	13									13					
X0326754	VALVE VAULT, 5' DIAMETER, WITH 10" VALVE	EACH	7		2							5					
X0326753	VALVE VAULT, 4' DIAMETER, WITH 8" VALVE	EACH	7									7					
X0326752	VALVE VAULT, 4' DIAMETER, WITH 6" VALVE	EACH	9									9					
X0326751	VALVE VAULT 4" VALVE	EACH	1									1					
X0326750	WATER MAIN REMOVAL	FOOT	7,196		370							6826					
X0326500	VALVE VAULTS TO BE REMOVED	EACH	10									10					
X0326500	FIRE HYDRANTS TO BE REMOVED	EACH	14									14					
X0326756	LIGHT POLE, COMPLETE IN PLACE, PE 1	EACH	78									78					
X0326757	LIGHT POLE, COMPLETE IN PLACE, TYPE 2	EACH	8									8					
X0326758	UNIT DUCT, 600V, 4/C #6, 2/C #8, 1/C #8 NEUTRAL & 1/C #8 GROUND (XLP TYPE-USE) 1/2" DIAMETER HDPE, IN TRENCH	FOOT	14,940									14940					
X4420540	CLASS B PATCHES, TYPE IV, 8 1/4 INCH	SQ YD	27		27												
X0076600	TRAINERS	HR	2,000	2,000													

© Y080
SPECIALTY ITEM

REVISIONS	
NAME	DATE



ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 48
SUMMARY OF QUANTITIES

VERT. NO SCALE
HORIZ.
DATE: 8/5/2009
DRAWN BY: E.D.
CHECKED BY: A.A.C.

PLOT DATE = Monday, August 10, 2009
FILE NAME = s:\11-coad\01-ahs\094-012_sum_of_quant.dgn
USER NAME = j3930