F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2662	08-00041-00-RS	DuPAGE	25	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 63098

SPECIALTY ITEMS	SPECIAL PROVISION	ITEM Code Number	Description	Unit	TOTAL QUANTITY CODE1000
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	575
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7
		25000500	PHOPHORUS FERTILIZER NUTRIENT	POUND	7
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7
		25200100	SODDING	SQ YD	575
		25200200	SUPPLEMENTAL WATERING	UNIT	10
		28000510	INLET FILTERS	EACH	70
		40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40
		40600300	AGGREGATE (PRIME COAT)	TON	200
		40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	25
		40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4264
		40600895	CONSTRUCTING TEST STRIP	EACH	1
	SP	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	216
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4975
		42001300	PROTECTIVE COAT	SQ YD	288
		42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	15
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	200
		42400800	DETECTABLE WARNINGS	SQ FT	100
		44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	50751
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	75
		44000600	SIDEWALK REMOVAL	SQ FT	200
		44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	765
	SP	44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	100
	SP	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	200
	SP	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	300
	SP	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	400
		44213200	SAW CUTS	FOOT	265
		60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4
		60257900	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
		60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
		60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	12
		60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2
		60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20
	SP	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1
		67100100	MOBILIZATION	L SUM	1
	SP	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1
	SP	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
	SP	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
	SP	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4
		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4250
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1417
		72000100	SIGN PANEL-TYPE 1	SQ FT	28
		72900200	METAL POST-TYPE B	FOOT	56
•		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1097
•		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3420
•		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3818
•		78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	225
•		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	753
•		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	395
•		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	166
•		88600100	DETECTOR LOOP, TYPE 1	FOOT	1788
		XX002267	MEDIAN REMOVAL AND REPLACEMENT	SQ FT	138
	SP	X4021000	TEMPORARY ACCESS(PRIVATE ENTRANCE)	EACH	11
	SP	Z0066500	STABILIZED DRIVEWAYS, 7"	SQ YD	60
	SP	Z0076600	TRAINEES	HOURS	500 **

** CODE Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. 2662
JORIE BOULEVARD

SUMMARY OF QUANTITIES

SCALE: N/A
DRAWN BY: SMP
DATE: 2/06/09
CHECKED BY: JDM