

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1617	09-00077-00-RS	COOK	9	2
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS		

GENERAL NOTES:

- THIS PROJECT WILL BE CONSTRUCTED IN ACCORDANCE WITH THE ILLINOIS DEPARTMENT OF TRANSPORTATION "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, ADOPTED JANUARY 1, 2007", THE LATEST EDITION OF THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS", THE "MANUAL OF TEST PROCEDURES OF MATERIALS" IN EFFECT ON THE DATE OF INVITATION OF BIDS, AND THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET INCLUDED IN THE CONTRACT'S SPECIFICATIONS, WHICH APPLY TO AND GOVERN THE CONSTRUCTION OF MFT 09-00077-00-RS.
- THE TERM "VILLAGE" USED HEREIN IN REFERENCE TO NOTIFICATION(S) BY OR PERMIT(S)/PERMISSION(S) TO BE OBTAINED BY THE CONTRACTOR SHALL MEAN THE MUNICIPAL OFFICIAL DULY DESIGNATED BY THE VILLAGE BOARD FOR THE PURPOSE. THE CONTRACTOR SHALL CONTACT THE VILLAGE MANAGER'S OFFICE AT (708) 335-9600 TO GET THE NAME(S) AND CONTACT INFORMATION OF SUCH DESIGNATED OFFICIALS/STAFF.
- A MINIMUM OF TWO (2) WORKING DAYS BEFORE STARTING EXCAVATION, THE CONTRACTOR SHALL CONTACT JULIE (1-800-892-0123) TO HAVE THE LOCATION OF EXISTING UNDERGROUND UTILITIES STAKED OR OTHERWISE MARKED AT THE SITE.
- IF AND WHEN EXISTING DRAINAGE FACILITIES ARE DISTURBED BY PROPOSED CONSTRUCTION, THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY OUTLETS AND CONNECTIONS FOR ALL PRIVATE AND PUBLIC DRAINS, SEWERS OR CATCH BASINS, AND PROVIDE ADEQUATE FACILITIES TO TAKE IN ALL STORM WATER INCLUDING PUMPING AND A TEMPORARY OUTLET, IF NECESSARY. THIS WORK SHALL NOT BE PAID FOR DIRECTLY, BUT WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT.
- ALL UTILITIES AND THE ASSOCIATED DATA SHOWN ON THE PLANS ARE FROM THE AVAILABLE RECORDS AND REPRESENT THE BEST AVAILABLE INFORMATION. HOWEVER, THEIR ACCURACY OR COMPLETENESS IS NOT GUARANTEED. IT SHALL REMAIN THE CONTRACTOR'S RESPONSIBILITY TO CONTACT JULIE (1-800-892-0123) AND VARIOUS UTILITY FIRMS AND/OR ORGANIZATIONS HAVING FACILITIES AT THE SITE TO DETERMINE THEIR ACTUAL LOCATIONS, AND OTHER DETAILS, AND DETERMINE WHETHER THEY ARE IN CONFLICT WITH THE PROPOSED WORK. THE CONTRACTOR SHALL BRING ALL SUCH CONFLICTS TO THE ENGINEER'S ATTENTION AND SHALL NOT PROCEED WITH THE PORTION OF THE WORK IN CONFLICT UNTIL THE RESOLUTION OF THE CONFLICT(S) AND THE AUTHORIZATION TO PROCEED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UNDERGROUND UTILITIES WITHIN THE PROJECT LIMITS, WHETHER OR NOT SUCH UTILITIES ARE SHOWN ON THE PLANS. ANY UTILITY DAMAGED DURING CONSTRUCTION, SHALL BE REPAIRED OR REPLACED TO THE SATISFACTION OF THE RESPECTIVE UTILITY, BY THE CONTRACTOR WITHOUT ANY ADDITIONAL COMPENSATION.
- THE CONTRACTOR SHALL MAKE EVERY POSSIBLE EFFORT TO PREVENT CONSTRUCTION DEBRIS FROM ENTERING EXISTING MANHOLES, CATCH BASINS, INLETS OR DRAINAGE DITCHES. ANY SUCH DEBRIS, DETERMINED BY THE VILLAGE TO BE PRESENT IN SUCH STRUCTURES DUE TO THE CONTRACTOR'S OPERATIONS SHALL BE PROMPTLY REMOVED AND DISPOSED OFF BY THE CONTRACTOR TO THE VILLAGE'S SATISFACTION AT NO ADDITIONAL COMPENSATION.
- ALL REMOVAL OF CURB AND GUTTER, SIDEWALK, DRIVEWAYS AND PAVEMENT ETC. SHALL BE BY SAWCUTTING TO ENSURE A CLEAN REMOVAL WITHOUT DAMAGING OR GAUGING THE PORTION(S) TO REMAIN. ALL SUCH DAMAGE OR GAUGING SHALL BE REPAIRED BY THE CONTRACTOR TO THE VILLAGE'S SATISFACTION WITHOUT ANY ADDITIONAL COMPESATION. THE SAWCUTTING SHALL NOT BE COMPENSATED FOR SEPARATELY BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE REMOVAL OF THE ITEM INVOLVED.
- THE CONTRACTOR SHALL MAINTAIN AT ALL TIMES ADEQUATE ACCESS TO ALL PROPERTIES ADJACENT TO THE PROPOSED IMPROVEMENT. THE COST OF THIS WORK SHALL NOT BE COMPENSATED FOR SEPARATELY BUT SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS REMOVAL ITEMS.
- THE CONTRACTOR SHALL PROVIDE ADEQUATE PROVISIONS FOR PEDESTRIAN TRAFFIC THROUGH THE CONSTRUCTION AREA AT ALL TIMES AND SEEK THE VILLAGE'S PERMISSION FOR ANY UNAVOIDABLE OBSTRUCTION(S) TO SUCH TRAFFIC.
- LOCAL ACCESS ON ALL SECONDARY STREETS MUST BE MAINTAINED AT ALL TIMES BY THE CONTRACTOR WHEN CONSTRUCTION IS NOT TAKING PLACE AT SUCH LOCATION. ALL TRAFFIC OBSTRUCTIONS TO SUCH STREETS SHALL BE REMOVED ON WEEKENDS, HOLIDAYS AND OVERNIGHT, UNLESS SPECIFICALLY AND EXPLICITLY PERMITTED BY THE VILLAGE.

- REMOVAL AND STABILIZATION OF UNSTABLE MATERIAL DURING BASE REPAIR: THIS WORK, IF REQUIRED, SHALL BE DONE IN ACCORDANCE WITH THE SPECIAL PROVISION TITLED POROUS GRANULAR EMBANKMENT, SUBGRADE INCLUDED IN THE CONTRACT, SUBJECT TO THE FOLLOWING: "POROUS GRANULAR EMBANKMENT, SUBGRADE" (PGES) HAS BEEN PROVIDED FOR THE USE AT THE LOCATIONS INDICATED FOR SOILS THAT TEND TO BE UNSTABLE. THE ACTUAL NEED FOR REMOVAL AND REPLACEMENT WITH PGES WILL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE GEOTECHNICAL ENGINEER. ALL POTENTIALLY UNSTABLE SOILS SHOULD BE TESTED WITH STATIC CONE PENETROMETER AND TREATED IN ACCORDANCE WITH ARTICLE 301.03 AND THE UNDERCUT GUIDELINES IN THE IDOT SUBGRADE STABILITY MANUAL. IF UNSTABLE MATERIAL IS NOT ENCOUNTERED AT THE SITE, THEN THE QUANTITY OF THIS ITEM WILL BE DEDUCTED FROM THE CONTRACT AND NO COMPENSATION FOR THIS ITEM WILL BE DUE TO THE CONTRACTOR.

IDOT STANDARDS

STANDARD NO.	NAME OF STANDARD
424001-05	CURB RAMPS FOR SIDEWALKS
442201-03	CLASS C & D PATCHES
602011-01	CATCH BASIN TYPE C
602701-02	MANHOLE STEPS
604001-03	FRAME AND LIDS TYPE 1
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701301-03	LANE CLOSURE 2L, 2W SHORT TIME OPERATION
701501-05	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701801-04	URBAN LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS

DISTRICT 1 DETAILS

CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT, BD-24, DISTRICT ONE
 BUTT JOINT AND HMA TAPER DETAILS, BD-32, DISTRICT ONE
 DISTRICT ONE, TYPICAL PAVEMENT MARKINGS, TC-13

REVISIONS	
NAME	DATE

GENERAL NOTES

HAZEL CREST, IL

SCALE: VERT. NONE
 HORIZ. NONE
 DATE 10/15/09

DRAWN BY BS
 CHECKED BY NC

CIVIL / STRUCTURAL ENGINEERS



GLOBETROTTERS INTERNATIONAL,
 300 SOUTH WACKER DRIVE, SUITE 200
 CHICAGO, IL. 60606