

GENERAL NOTES

1. ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE DETAILS IN THE PLANS, THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS, AND THE LATEST EDITION OF THE FOLLOWING STATE OF ILLINOIS SPECIFICATIONS: "THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" (REFERRED TO AS THE "STANDARD SPECIFICATIONS"), THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS", THE "STANDARD SPECIFICATIONS FOR TRAFFIC CONTROL ITEMS", THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS", THE "MANUAL OF TEST PROCEDURES FOR MATERIALS" AND THE "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS".
2. THE LOCATIONS OF PUBLIC OR PRIVATE UTILITIES SHOWN ON THE PLANS ARE APPROXIMATE AND THE COUNTY DOES NOT GUARANTEE THEIR ACCURACY. THE CONTRACTOR SHALL HAVE THE RESPECTIVE UTILITY COMPANIES FIELD LOCATE ALL THEIR FACILITIES PRIOR TO BEGINNING CONSTRUCTION. THE CONTRACTOR SHALL ALSO VERIFY THE DEPTHS OF THE EXISTING UTILITIES IF NECESSARY. ANY RELOCATION OR LOWERING OF UTILITIES SHALL BE COORDINATED BY THE CONTRACTOR.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND OR SURFACE UTILITIES, INCLUDING SPRINKLER SYSTEMS, EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY OR SPRINKLER SYSTEM THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE ENGINEER OR COUNTY.
4. THE CONTRACTOR SHALL NOTIFY THE WILL COUNTY DEPARTMENT OF HIGHWAYS AND THE ENGINEER AT LEAST TWO (2) WORKING DAYS IN ADVANCE OF BEGINNING WORK.
5. THE CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE WITH THE VILLAGE TO OBTAIN VILLAGE UTILITY LOCATIONS AND SHALL COORDINATE ALL CONSTRUCTION OPERATIONS NEAR THOSE FACILITIES WITH THE ENGINEER.
6. MATERIALS RESULTING FROM THE REMOVAL OF PAVEMENT, DRIVEWAYS, CURB AND GUTTER, HOT-MIX ASPHALT SURFACES, ETC. SHALL BE REMOVED AT THE END OF EACH DAY TO AN APPROVED SITE. IN THE JUDGMENT OF THE COUNTY, SHOULD IT BE NECESSARY TO REMOVE SUCH MATERIALS, THE COUNTY WILL HAVE THE MATERIAL REMOVED AND THE CONTRACTOR WILL BE BILLED (CHARGED) ACCORDINGLY.
7. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL SECTION OR SUBSECTION MONUMENTS OR PROPERTY OR REFERENCE MARKERS UNTIL THE OWNERS, HIS AGENT OR AN AUTHORIZED SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS.

8. EXISTING PAVEMENT, DRIVEWAY PAVEMENT, CURB AND GUTTER AND SIDEWALK TO REMAIN IN PLACE SHALL BE SAW CUT FULL DEPTH TO PROVIDE A NEAT VERTICAL FACE BETWEEN THE PROPOSED AND EXISTING AND SHALL BE INCLUDED IN THE PRICE OF THE APPROPRIATE REMOVAL PAY ITEM.

9. IN AREAS WHERE THE EXISTING DRIVEWAY, SIDEWALK, OR CURB AND GUTTER IS TO BE REMOVED AND REPLACED, THE REMOVAL AND DISPOSAL OF ANY ADDITIONAL MATERIAL REQUIRED TO ESTABLISH THE PROPOSED DRIVEWAY, SIDEWALK, OR CURB AND GUTTER SUBGRADE ELEVATION SHALL BE INCLUDED IN THE PAY ITEMS, SIDEWALK REMOVAL (SPECIAL) OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT.

10. CURB AND GUTTER SHALL BE DEPRESSED AT DRIVEWAYS AND SIDEWALK RAMPS IN ACCORDANCE WITH THE IDOT HIGHWAY STANDARDS. SIDEWALK RAMPS FOR ACCESS FOR THE DISABLED SHALL BE PROVIDED AT THE PROPOSED CROSSWALKS IN ACCORDANCE WITH THE IDOT HIGHWAY STANDARDS OR AS DETERMINED BY THE ENGINEER.

11. THE FINISHED HOT-MIX ASPHALT SURFACE SHALL BE CONSTRUCTED 0.25 INCH ABOVE THE GUTTER FLAG.

12. THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED. ONE (1) WEIGHTED SANDBAG SHALL BE PLACED ACROSS EACH BOTTOM RAIL.

13. A 1/2 INCH THICK EXPANSION JOINT SHALL BE PROVIDED AT THE JUNCTION OF THE SIDEWALK. THIS WORK WILL BE INCLUDED IN THE COST OF PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL.

14. DETECTABLE WARNINGS SHALL CONSIST OF A CAST IN PLACE PRODUCT AND CONFORM TO SECTION 424 OF THE STANDARD SPECIFICATIONS. DYED CONCRETE WILL NOT BE ALLOWED.

15. ALL POSTS, RAILROAD TIES, AND DECORATIVE TIMBER IN CONFLICT WITH THE PROPOSED IMPROVEMENTS SHALL BE REMOVED AND RELOCATED AS DETERMINED BY THE ENGINEER AT THE TIME OF CONSTRUCTION AND SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED REMOVAL PAY ITEMS. EVERY EFFORT SHALL BE MADE BY THE CONTRACTOR WHEN REMOVING THESE ITEMS TO PRESERVE THEM FROM HARM. ITEMS NOT RELOCATED SHALL BE PROPERLY DISPOSED OF BY THE CONTRACTOR.

16. PRIOR TO CONSTRUCTION OF ANY PROPOSED UTILITIES, THE CONTRACTOR SHALL EXCAVATE AND LOCATE THE EXISTING UTILITIES TO VERIFY THEIR LOCATION, SIZE, AND DEPTH TO INSURE THAT GRADE CONFLICTS WILL NOT OCCUR. THE COST OF THIS EXPLORATION SHALL BE INCLUDED IN THE COST OF THE PROPOSED UTILITY CONSTRUCTION.

17. THE DETAIL FOR COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT SHOWN IN THE PLANS SHALL BE MODIFIED TO INCLUDE THE FOLLOWING. THE WORK SHALL INCLUDE SAW-CUTTING AND REMOVING THE EXISTING PAVEMENT A MINIMUM OF 6-INCHES MEASURED FROM THE EXISTING EDGE OF PAVEMENT, AND FILLING THE 6" GAP WITH CLASS SI CONCRETE TO AN ELEVATION 1 3/4" BELOW THE PROPOSED CURB AND GUTTER FLAG. IF THE CONCRETE IS POURED HIGHER THAN 1 3/4" FROM THE GUTTER FLAG FOR STREETS TO BE RESURFACED, THE CONTRACTOR WILL BE REQUIRED TO GRIND ADDITIONAL CONCRETE TO THE REQUIRED 1 3/4" DEPTH. THE AREA BEHIND THE PROPOSED CURB AND GUTTER SHALL BE RESTORED WITH NATIVE SOD IN ACCORDANCE WITH SECTION 10B1.03 RATHER THAN SALT TOLERANT SOD.

18. ANY DAMAGE TO PAVEMENT, SIDEWALK, CURB AND GUTTER, OR ANY OTHER PORTION OF THE ROADWAY NOT SPECIFICALLY INDICATED TO BE REMOVED AND REPLACED SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL CHARGE.

19. THE CONTRACTOR SHALL PROVIDED WARRANTIES OR GUARENTEES PROVIDING FOR SATISFACTORY IN-SERVICE OPERATION OF THE MECHANICAL AND ELECTRICAL EQUIREMENT AND RELATED COMPONENTS AS PER IDOT STANDARDS.

20. THE CONTRACTOR SHALL MAKE SPECIAL NOTE OF THE REQUIREMENTS FOR GROUNDING. GROUNDING CONNECTIONS AT THE FOUNDATION SHALL BE EXOTHERMICALLY WELDED, AS SPECIFIED, AND SHALL BE INSPECTED AND APPROVED BY THE ENGINEER PRIOR TO BACKFILLING.

21. THE CONTRACTOR SHALL MAKE SPECIAL NOTE OF THE REQUIREMENTS FOR BURIED WARNING TAPE, SPECIFIED AS PART OF "TRENCH AND BACKFILL FOR ELECTRICAL WORK." THE INSTALLATION OF THE TAPE SHALL BE INSPECTED AND APPROVED BY THE ENGINEER PRIOR TO BACKFILLING.

22. NO POLES SHALL BE ERECTED UNTIL THE RESPECTIVE FOUNDATIONS HAVE CURED, AS APPROVED BY THE ENGINEER.

23. THE CONTRACTOR SHALL MAKE SPECIAL NOTE OF THE REQUIREMENTS FOR WIRE MARKERS AND SHALL TAG ALL WIRE MARKERS AND SHALL TAG ALL WIRING ACCORDINGLY.

24. MAINTENANCE OF TRAFFIC ITEMS INCLUDED IN THE PLAN IS INTENDED TO BE SUPPLEMENTARY. ITEMS NOT VISUALLY SHOWN SHALL NOT BE CONSIDERED UNNECESSARY. ALL APPLICABLE STANRDARDS, AS SUPPLEMENTED AND/OR ALTERED BY NOTES, SPECIFICATIONS, AND SPECIAL PROVISIONS SHALL BE FOLLOWED IN CONJUCTION WITH THE INFORMATION PRESENTED IN THE PLAN.

25. AREAS OF THE SIDEWALK REMOVAL SHOWN IN THE PLANS THAT ARE NOT REPLACED WITH NEW PCC SIDEWALK SHALL BE RESTORED WITH TOPSOIL AND NATIVE SOD. THIS SHALL BE INCLUDED IN THE COST OF SIDEWALK REMOVAL (SPECIAL).

26. A CHANGEABLE MESSAGE SIGN SHALL BE PLACED ON ALL LEGS OF THE INTERSECTION, A MINIMUM 72 HOURS PRIOR TO WORK AND REMAIN THROUGHOUT THE CONSTRUCTION WORK.

NOTE:

ITEMS SHOWN IN BOX INCLUDE WORK AND/OR MODIFICATIONS THAT ARE INCIDENTAL, OR OTHERWISE INDICATED

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC. PROJECT NO. 071621-GENNOTES
 LICENSE NO. 184-0012 - EXPIRES 4/30/2011
 10/15/2009 8:55:20 AM \\corbawood.com\projects\mkenns\willco\071621-GenNotes.dgn



DESIGNED - NJP	REVISED - PER COUNTY 8-20-09
DRAWN - BCD	REVISED - PER IDOT 09-16-09
CHECKED - RWL	REVISED -
DATE - 06-25-09	FILE - 071621-GenNotes.shx

**WILL COUNTY DEPARTMENT OF HIGHWAYS
LARAWAY ROAD AT WOLF ROAD**

GENERAL NOTES

SCALE: STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	07-00138-26-TL	WILL	19	3
C-91-405-08		CONTRACT NO. 63329		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				