

**SUMMARY OF QUANTITIES**

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 1000-1A	SIGNALS Y031-1F	SIDEWALK Y044
28000305	TEMPORARY DITCH CHECKS	FOOT	10	10		
28000400	PERIMETER EROSION BARRIER	FOOT	95	95		
28000510	INLET FILTER	EACH	2	2		
x 35101600	AGGREGATE BASE COURSE, TYPE B 4"	SO YD	133	133		
x 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2	2		
x 42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SO FT	949	949		
x 42400800	DETECTABLE WARNINGS	SO FT	80	80		
x 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	94	94		
x 44004700	SIDEWALK REMOVAL (SPECIAL)	SO FT	444	444		
67100100	MOBILIZATION	L SUM	1	1		
x 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
x 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
x 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
x 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16		
72000100	SIGN PANEL, TYPE 1	SO FT	64.5	36	28.5	
x 72400100	REMOVE SIGN PANEL ASSEMBLY, TYPE A	EACH	5	5		
72900100	METAL POST, TYPE A	FOOT	100	100		
** 78000400	THERMOPLASTIC PAVEMENT MARKING, LINE 6"	FOOT	608	608		
** 78000600	THERMOPLASTIC PAVEMENT MARKING, LINE 12"	FOOT	169	169		
** 78000650	THERMOPLASTIC PAVEMENT MARKING, LINE 24"	FOOT	140	140		
x ** 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	584		584	
** 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	28.5		28.5	
** 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	8		8	
** 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	10		10	
** 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	71		71	
** 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	87		87	
** 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	336		336	
** 81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	28		28	
** 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4		4	
** 81400710	HEAVY DUTY HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5		5	
** 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2		2	
** 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	934		934	
** 85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1	
** 86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1		1	
** 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	1316		1316	
** 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1904		1904	
** 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	921		921	
** 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	1760		1760	
** 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1884		1884	
** 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6, 2C	FOOT	95		95	
** 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	3		3	

\*\* DENOTES SPECIALTY ITEMS  
x DENOTES ITEMS REFERENCED IN A SPECIAL PROVISION

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.  
 ALL RIGHTS RESERVED. PROJECT NO. 07-00138-26-TL  
 LICENSE NO. 018-00029 - EXPIRES 4/30/2011  
 \\C:\p\boxwood.com\p\0\elect\Makemo\WILL\071621-1\rvy.ctb Ref: CADP-SURVEY\DRAWINGS\DCNS\071621-soq.dwg  
 10/19/2009 9:06:45 AM



DESIGNED - NJP	REVISED - PER COUNTY 8-20-09
DRAWN - BCD	REVISED - PER IDOT 09-16-09
CHECKED - RWL	REVISED -
DATE - 06-25-09	FILE - 071621-soq.shx

**WILL COUNTY DEPARTMENT OF HIGHWAYS  
 LARAWAY ROAD AT WOLF ROAD**

**SUMMARY OF QUANTITIES**

SCALE: \_\_\_\_\_ STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.U. RTE. 320	SECTION 07-00138-26-TL	COUNTY WILL	TOTAL SHEETS 19	SHEET NO. 4
C-91-405-08		CONTRACT NO. 63329		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				