THERMOPLASTIC PM - LINE 6" (WHITE) - 100 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 3' C-C) - 42 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 3' C-C) - 24 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 14 LF
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 866 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 15 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 75 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 3' C-C) - 30 LF
BANK LANE
THERMOPLASTIC PM - LINE 6" (WHITE) - 85 LF
PARALLEL PARKING PM THERMOPLASTIC PM - LINE 4" (WHITE) 326 LF
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 694 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 45° EQUALLY SPACED)
THERMOPLASTIC PM - LINE 6" (WHITE) - 24 LF
MATCH LINE STA. 19+00 - SEE BELOW LEFT
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 890 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 70 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 17 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 3' C-C) - 42 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 62 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 10 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 70 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 3' C-C) - 60 LF
WALKER AVENUE
WASHINGTON AVENUE
WEBSTER AVENUE
CLAY AVENUE
SHERIDAN ROAD
THERMOPLASTIC PM - LINE 6" (WHITE) - 60 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 100 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 20 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 3' C-C) - 42 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 21 LF
PARALLEL PARKING PM THERMOPLASTIC PM - LINE 4" (WHITE) 366 LF
PARALLEL PARKING PM THERMOPLASTIC PM - LINE 4" (WHITE) 331 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 18 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 124 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 45° EQUALLY SPACED) (TYP)
THERMOPLASTIC PM - LINE 6" (WHITE, SKIP-DASH, 2' LINE, 6' SKIP)
THERMOPLASTIC PM - LETTERS AND SYMBOLS 36.4 SQ FT
THERMOPLASTIC PM - LINE 4" (WHITE) - 74 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 100 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 134 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 3' C-C) - 36 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 15 LF
TWO-WAY LEFT TURN MEDIAN
OUTSIDE: THERMOPLASTIC PM - LINE 4" (YELLOW) 1030 LF
INSIDE: THERMOPLASTIC PM - LINE 4" (YELLOW, SKIP-DASH, 10' LINE, 30' SKIP) - 412 LF
(LINES 5 1/2" C-C)
22 RAISED REF PVMT MAPKERS , 40' C-C (2-WAY AMBER)
MEDIAN CHANNELIZATION LINES
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 360 LF
THERMOPLASTIC PM - LINE 12" (YELLOW, 45° DIAGONAL - EQUALLY SPACED)
10 RAISED REF PVMT MAPKERS 40' C-C (2-WAY AMBER)
THERMOPLASTIC PM - LINE 6" (WHITE) - 50 LF
THERMOPLASTIC PM - LETTERS AND SYMBOLS - 36.4 SQ FT
MATCH LINE STA. 19+00 - SEE ABOVE RIGHT
MATCH LINE STA. 31+00 - SEE BELOW LEFT
55' LT TAPER
100' LT STORAGE
100' LT TAPER
50' LT STORAGE
THERMOPLASTIC PM - LINE 6" (WHITE) - 100 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 21 LF
MEDIAN CHANNELIZATION LINES
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 90 LF
THERMOPLASTIC PM - LINE 12" (YELLOW, 45° DIAGONAL - EQUALLY SPACED)
7 RAISED REF PVMT MAPKERS 40' C-C (2-WAY AMBER)
THERMOPLASTIC PM - LINE 6" (WHITE) - 86 LF
THERMOPLASTIC PM - LINE 12" (WHITE, 3' C-C) - 36 LF
THERMOPLASTIC PM - LINE 6" (WHITE) - 96 LF
MEDIAN CHANNELIZATION LINES
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 450 LF
THERMOPLASTIC PM - LINE 12" (YELLOW, 45° DIAGONAL - EQUALLY SPACED)
17 RAISED REF PVMT MAPKERS 40' C-C (9 2-WAY AMBER, 8 1-WAY AMBER)
SHERIDAN ROAD
121' LT TAPER
100' LT STORAGE
MATCH LINE STA. 31+00 - SEE ABOVE RIGHT
THERMOPLASTIC PM - LINE 6" (WHITE) - 25 LF
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 54 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 21 LF
THERMOPLASTIC PM - LETTERS AND SYMBOLS 36.4 SQ FT
THERMOPLASTIC PM - LINE 6" (WHITE) - 100 LF
4 RAISED REF PVMT MARKERS, 40' C-C
(1-WAY CRYSTAL)
100' LT STORAGE
113' LT TAPER
MEDIAN CHANNELIZATION LINES
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 1260 LF
THERMOPLASTIC PM - LINE 12" (YELLOW, 45° DIAGONAL - EQUALLY SPACED)
14 RAISED REF PVMT MAPKERS 40' C-C (6 2-WAY AMBER, 8 1-WAY AMBER)
MATCH LINE STA. 43+00 - SEE SHEET NO. 14
THERMOPLASTIC PM - LINE 6" (WHITE) - 197 LF
THERMOPLASTIC PM - LINE 24" (WHITE) - 38 LF
THERMOPLASTIC PM - LINE 4" (DOUBLE YELLOW, 11" C-C) - 3760 LF
1ST STREET
THERMOPLASTIC PM - LINE 6" (WHITE) - 100 LF
4 RAISED REF PVMT MARKERS, 40' C-C
(1-WAY CRYSTAL)
THERMOPLASTIC PM - LINE 6" (WHITE, SKIP-DASH, 2' LINE, 6' SKIP) - 30 LF
SHERIDAN ROAD

COPYRIGHT © 2009, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. - 184-001085 - EXPIRES 4/30/2010
...\plot\dgn\PDF22x34.plt
PLOTTED: 10/6/2009 3:42:08 PM
BY: KAR
I:\HWD\C\090831-Sheridan LAP\CADD-SURVEY\DRAWINGS\DGNS\Sheets\090831-pml.sht

BAXTER & WOODMAN Consulting Engineers

DESIGNED	SLN	REVISED	IDOT REVIEW 10/05/09
DRAWN	KAR	REVISED	-
CHECKED	RWL	REVISED	-
DATE	08-20-09	FILE	090831-pml.sht

CITY OF HIGHWOOD, ILLINOIS
SHERIDAN ROAD ARRA (LAPP)
RESURFACING

PAVEMENT MARKING PLAN – SHERIDAN ROAD

SCALE: 1" = 40' | STA. 7+00 | TO STA. 43+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2744	09-00053-00-RS	LAKE	25	13
FED. ROAD DIST. NO. 1	C-91-891-09	CONTRACT NO. 63338		
ILLINOIS	FED. AID PROJECT ARA-9003(457)			