

**GENERAL NOTES**

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR WILL CALL "J.U.L.I.E." AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR WILL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE VILLAGE OF GLEN ELLYN.

IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS WILL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.

ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

THE CONTRACTOR WILL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR WILL RECORD ALL EXISTING PAVEMENT MARKING LINES IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED.

ALL PAVEMENT MARKINGS WILL BE PLACED THROUGHOUT THE IMPROVEMENT ACCORDING TO THE DISTRICT 1 STANDARD DETAIL.

RAISED REFLECTIVE PAVEMENT MARKERS WILL BE PLACED THROUGHOUT THE IMPROVEMENT ACCORDING TO THE DISTRICT 1 STANDARD DETAIL.

**SUMMARY OF QUANTITIES**

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	PARK QUANTITY	LAMBERT QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3159	2466	693
40600300	AGGREGATE (PRIME COAT)	TON	127	99	28
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	10	8	2
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	378	300	78
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3538	2762	776
42400800	DETECTABLE WARNINGS	SQ FT	352	328	24
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	31585	24658	6927
X 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	250	350
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	60	30	30
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	145	75	70
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	250	150	100
X 60266800	VALVE BOXES TO BE REPLACED	EACH	2	2	0
X 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	35	35	0
67100100	MOBILIZATION	L SUM	1	0.5	0.5
<del>70102620</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701501</del>	<del>L SUM</del>	<del>1</del>	<del>0.5</del>	<del>0.5</del>
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5	0.5
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5	0.5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3300	2764	536
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	374	250	124
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13490	9865	3625
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2683	1330	1353
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	746	475	271
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	433	270	163
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	431	345	86
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	420	340	80
X * 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1400	700	700
X <del>44004600</del>	<del>SIDEWALK REMOVAL AND REPLACEMENT</del>	<del>SQ FT</del>	<del>1100</del>	<del>1025</del>	<del>75</del>
X XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	27	27	0
X XD322256	TEMPORARY INFORMATION SIGNING	SQ FT	100	50	50
X X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1770	1382	388

\* SPECIALTY ITEM  
X SPECIAL PROVISION

FILE NAME =	USER NAME =	DESIGNED - SPF	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES AND SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - FJS	REVISED -			2580	09-00073-00-RS	DuPAGE	16	2
		CHECKED - JMS	REVISED -			CONTRACT NO. 63346		FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT
		DATE - 10/19/09	REVISED - 10/28/09			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.		