

Summary of Quantities

1000

CONTRACT NO. 63347

CODE NO	ITEM	UNIT	TOTAL QUANTITY
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	50
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4573
40600300	AGGREGATE (PRIME COAT)	TON	69
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	592
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2241
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2700
42400800	DETECTABLE WARNINGS	SQ FT	300
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	22865
44000600	SIDEWALK REMOVAL	SQ FT	2700
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1305
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	25
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	50
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	350
60255500	MANHOLES TO BE ADJUSTED	EACH	5
60260100	INLETS TO BE ADJUSTED	EACH	7
60262700	INLETS TO BE RECONSTRUCTED	EACH	3
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL-MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1500
70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	250
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	2729
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	120
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	600
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1000
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2500
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	537
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	120
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1275
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1280
XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	550

\* DENOTES SPECIALTY ITEM(S)

VILLAGE OF WOODRIDGE PUBLIC WORKS  
1 Plaza Drive, Woodridge IL 60517 (630) 719-4753

JANES AVENUE  
REHABILITATION PROJECT

SUMMARY OF QUANTITIES

DRAWN BY: AF

CHECKED BY: SM