

CONTRACT NO. 63347

PAVEMENT QUANTITIES SCHEDULE

STA.	SIDE	LOCATION	PAVEMENT WIDTH (FT)	PAVEMENT LENGTH (FT)	PAVEMENT AREA (SQ. FT.)	PAVEMENT AREA (SQ. YD.)	40600100 BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	40600300 AGGREGATE (PRIME COAT) (TON)	40603340 HMA SURFACE COURSE, MIX "D", N70 (TON)	44000160 HMA SURFACE REMOVAL, 2 3/4" (SQ. YD.)	X4067107 POLYMERIZED LEVEL BINDER (TON)
127+68.5 TO 133+00		MAINLINE	38	531.5	20197	2244	448.8	6.7	219.9	2244	125.7
133+00 TO 138+00		MAINLINE	34	500	17000	1889	377.8	5.7	185.1	1889	105.8
138+00 TO 148+00		MAINLINE	33	1000	33000	3667	733.3	11.0	359.3	3667	205.3
148+00 TO 153+00		MAINLINE	33.5	500	16750	1861	372.2	5.6	182.4	1861	104.2
153+00 TO 158+00		MAINLINE	34.5	500	17250	1917	383.3	5.8	187.8	1917	107.3
158+00 TO 168+00		MAINLINE	34.8	1000	34800	3867	773.3	11.6	378.9	3867	216.5
168+00 TO 173+00		MAINLINE	35	500	17500	1944	388.9	5.8	190.6	1944	108.9
173+00 TO 178+00		MAINLINE	49	500	24500	2722	544.4	8.2	266.8	2722	152.4
178+00 TO 179+97		MAINLINE	75	205	15375	1708	341.7	5.1	167.4	1708	95.7
135+75	RT	SOUTH APARTMENT ENT.	BEGIN REMOVAL 10' FROM MAINLINE		720	80	16.0	0.2	7.8	80	4.5
142+75	RT	NORTH APARTMENT ENT.	BEGIN REMOVAL 10' FROM MAINLINE		700	78	15.6	0.2	7.6	78	4.4
146+00	LT	WILLOW WOOD WAY	BEGIN REMOVAL 12' FROM MAINLINE		492	55	10.9	0.2	5.4	55	3.1
152+50	RT	BIRCHWOOD PKWY.	BEGIN REMOVAL 22' FROM MAINLINE		990	110	22.0	0.3	10.8	110	6.2
155+80	LT	EVERGREEN LANE	BEGIN REMOVAL 22' FROM MAINLINE		836	93	18.6	0.3	9.1	93	5.2
159+20	RT	JANES COURT	BEGIN REMOVAL 22' FROM MAINLINE		814	90	18.1	0.3	8.9	90	5.1
165+50	RT	CRABTREE AVENUE	BEGIN REMOVAL 25' FROM MAINLINE		1225	136	27.2	0.4	13.3	136	7.6
167+00	LT	CRABTREE AVENUE	BEGIN REMOVAL 22' FROM MAINLINE		1078	120	24.0	0.4	11.7	120	6.7
169+15	RT	DALEWOOD PARKWAY	BEGIN REMOVAL 23' FROM MAINLINE		920	102	20.4	0.3	10.0	102	5.7
172+50	RT	CHARMINGFARE DRIVE	BEGIN REMOVAL 23' FROM MAINLINE		851	95	18.9	0.3	9.3	95	5.3
176+00	RT	JEWEL ENTRANCE	BEGIN REMOVAL 10' FROM MAINLINE		370	41	8.2	0.1	4.0	41	2.3
176+00	LT	SHOPING CENTER ENT.	BEGIN REMOVAL 13' FROM MAINLINE		416	46	9.2	0.1	4.5	46	2.6
							4573	69	2241	22865	1280
							GALLON	TON	TON	SY	TON

RESURFACING LIMITS (BUTT JOINT SCHEDULE)

STA.	SIDE	LOCATION	BUTT JOINT	PAVEMENT BUTT JOINT LENGTH (FT)	PAVEMENT BUTT JOINT WIDTH (FT)	40600982 HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ. YD.)
127+68.5		83RD STREET		54	10	60
135+75	RT	SOUTH APARTMENT ENT.	BEGIN REMOVAL 10' FROM MAINLINE	44	10	49
142+75	RT	NORTH APARTMENT ENT.	BEGIN REMOVAL 10' FROM MAINLINE	44	10	49
146+00	LT	WILLOW WOOD WAY	BEGIN REMOVAL 12' FROM MAINLINE	28	10	31
152+50	RT	BIRCHWOOD PKWY.	BEGIN REMOVAL 22' FROM MAINLINE	35	10	39
155+80	LT	EVERGREEN LANE	BEGIN REMOVAL 22' FROM MAINLINE	25	10	28
159+20	RT	JANES COURT	BEGIN REMOVAL 22' FROM MAINLINE	25	10	28
165+50	RT	CRABTREE AVENUE	BEGIN REMOVAL 25' FROM MAINLINE	25	10	28
167+00	LT	CRABTREE AVENUE	BEGIN REMOVAL 22' FROM MAINLINE	25	10	28
169+15	RT	DALEWOOD PARKWAY	BEGIN REMOVAL 23' FROM MAINLINE	25	10	28
172+50	RT	CHARMINGFARE DRIVE	BEGIN REMOVAL 23' FROM MAINLINE	25	10	28
176+00	RT	JEWEL ENTRANCE	BEGIN REMOVAL 10' FROM MAINLINE	33	10	37
176+00	LT	SHOPPING CENTER ENT.	BEGIN REMOVAL 13' FROM MAINLINE	25	10	28
179+97		75TH STREET		120	10	133
						592
						SY

NOTE:
ALL QUANTITIES SHOWN IN THE SCHEDULES ARE APPROXIMATE. THE ENGINEER WILL LOCATE ALL IMPROVEMENTS IN THE FIELD PRIOR TO CONSTRUCTION. PAYMENT SHALL BE BASED ON ACTUAL FIELD MEASUREMENTS.

VILLAGE OF WOODRIDGE PUBLIC WORKS
1 Plaza Drive, Woodridge IL 60517 (630) 719-4753

**JANES AVENUE
REHABILITATION PROJECT
RESURFACING SCHEDULE**

DRAWN BY: AF CHECKED BY: SM