

CONTRACT NO: 63372

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 100% FED 0% VILLAGE 1000-2A	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	200	200	
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	200	200	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	600	600	
25200200	SUPPLEMENTAL WATERING	UNIT	15	15	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15	
40600300	AGGREGATE (PRIME COAT)	TON	75	75	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	34	34	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,306	1,306	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	163	163	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,092	2,092	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	42	42	
42400800	DETECTABLE WARNINGS	SQ FT	136	136	
44000162	HOT-MIX ASHALT SURFACE REMOVAL, 3 1/4"	SQ YD	17,661	17,661	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	67	67	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,351	1,351	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	25	25	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	80	80	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	135	135	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	160	160	
50300300	PROTECTIVE COAT	SQ YD	565	565	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 100% FED 0% VILLAGE 1000-2A	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	20	20	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	11	11	
67100100	MOBILIZATION	L SUM	1	1	
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,650	1,650	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	590	590	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9,916	9,916	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,978	1,978	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,454	1,454	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	131	131	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,350	1,350	
72000100	SIGN PANEL - TYPE 1	SQ FT	33	33	
72900200	METAL POST - TYPE B	FOOT	56	56	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	590	590	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,916	9,916	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,978	1,978	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,454	1,454	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	131	131	
44004600	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	647	647	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10	
Z0066700	STABILIZED DRIVEWAYS 10"	SQ YD	25	25	

LEGEND
* -DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. ROUTE 2697
GILBERT AVENUE

SUMMARY OF QUANTITIES

SCALE: N/A
DATE: 10/01/09

DRAWN BY: BCD
CHECKED BY: BDH



JAMES J. BENES & ASSOCIATES, INC.
950 Warrenville Road, Suite 101, Lisle, Illinois 60532
Tel. (630) 719-7570 - Fax (630) 719-7589