

# SCHEDULE OF QUANTITIES

50100300	REMOVAL OF EXISTING STRUCTURES NO. 1				
	LOCATION		<u>EACH</u>	<u>REMARKS</u>	
	STA 897 + 77.46		1	CHELSEA ROAD - EX. SN 043-1041 (5' x 4' Box Culvert)	
		TOTAL	1		

63200310	GUARDRAIL REMOVAL					<u>FOOT</u>	<u>REMARKS</u>
	LOCATION						
	STA 895 + 80.99	TO		STA 898 + 70.10	RT	290	CHELSEA ROAD
	STA 896 + 96.71	TO		STA 899 + 73.10	LT	277	CHELSEA ROAD
	STA 967 + 90.56	TO		STA 970 + 42.22	RT	252	MEYER ROAD
	STA 968 + 15.33	TO		STA 970 + 67.56	LT	253	MEYER ROAD
			TOTAL			1072	

50100400	REMOVAL OF EXISTING STRUCTURES NO. 2				
	LOCATION		<u>EACH</u>	<u>REMARKS</u>	
	STA 969 + 28.62		1	MEYER ROAD - EX. SN 043 - 1039 (4' x 5' Box Culvert)	
		TOTAL	1		

63500105	DELINEATORS					<u>EACH</u>	<u>REMARKS</u>
	LOCATION						
	STA 897 + 77.46	LT				1	CHELSEA ROAD
	STA 897 + 77.46	RT				1	CHELSEA ROAD
	STA 969 + 28.62	LT				1	MEYER ROAD
	STA 969 + 28.62	RT				1	MEYER ROAD
			TOTAL			4	

51205200	TEMPORARY SHEET PILING				
	LOCATION		<u>SQ. FT.</u>	<u>REMARKS</u>	
	CHELSEA ROAD	LT	290.1	LOOKING WEST	
	CHELSEA ROAD	RT	278.4	LOOKING WEST	
		TOTAL	569		

66411900	TEMPORARY FENCE					<u>FOOT</u>	<u>REMARKS</u>
	LOCATION						
	STA 896 + 50	TO		STA 897 + 50	RT	150	CHELSEA ROAD
	STA 968 + 00	TO		STA 970 + 00	RT	206	MEYER ROAD
			TOTAL			356	

51500100	NAME PLATES				
	LOCATION		<u>EACH</u>	<u>REMARKS</u>	
	STA 897 + 77.46		1	CHELSEA ROAD - NEW SN 043-1060	
	STA 969 + 28.62		1	MEYER ROAD - NEW SN 043-1059	
		TOTAL	2		

54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"				
	LOCATION		<u>FOOT</u>	<u>REMARKS</u>	
	STA 896 + 74.95	LT	48	CHELSEA ROAD	
	STA 967 + 65.95	LT	54	MEYER ROAD	
		TOTAL	102		

66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS					<u>EACH</u>	<u>REMARKS</u>
	LOCATION			<u>OFFSET (FT.)</u>			
	STA 894 + 76.86			50' RT		1	CHELSEA ROAD
	STA 896 + 00.00			50' RT		1	CHELSEA ROAD
	STA 896 + 50.00			65' RT		1	CHELSEA ROAD
	STA 897 + 50.00			65' RT		1	CHELSEA ROAD
	STA 897 + 75.00			54.95' LT		1	CHELSEA ROAD
	STA 898 + 00.00			55' RT		1	CHELSEA ROAD
	STA 898 + 00.00			75' LT		1	CHELSEA ROAD
	STA 899 + 00.00			75' LT		1	CHELSEA ROAD
	STA 899 + 25.00			54.90' LT		1	CHELSEA ROAD
	STA 899 + 59.28			55' RT		1	CHELSEA ROAD
			TOTAL			10	

54200475	PIPE CULVERTS, TYPE 1 RCCP 60"				
	LOCATION		<u>FOOT</u>	<u>REMARKS</u>	
	STA 969 + 28.62		82	MEYER ROAD	
		TOTAL	82		

66700305	PERMANENT SURVEY MARKERS, TYPE II					<u>EACH</u>	<u>REMARKS</u>
	LOCATION						
	STA 895 + 00	TO		STA 900 + 50		2	CHELSEA ROAD
	STA 966 + 50	TO		STA 972 + 25.07		2	MEYER ROAD
			TOTAL			4	

54207615	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ARCH, EQUIVALENT				
	LOCATION		<u>ROUND-SIZE</u>	<u>REMARKS</u>	
	STA 897 + 77.46	LT	60	CHELSEA ROAD	
	STA 897 + 77.46	RT	60	CHELSEA ROAD	
		TOTAL	120		

54213450	END SECTIONS 15"				
	LOCATION		<u>EACH</u>	<u>REMARKS</u>	
	STA 896 + 74.95		2	CHELSEA ROAD	
	STA 967 + 65.95		2	MEYER ROAD	
		TOTAL	4		

70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS					<u>EACH</u>	<u>REMARKS</u>
	LOCATION						
	CHELSEA ROAD					1	
			TOTAL			1	

54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"				
	LOCATION		<u>EACH</u>	<u>REMARKS</u>	
	STA 969 + 28.62	LT	1	MEYER ROAD	
	STA 969 + 28.62	RT	1	MEYER ROAD	
		TOTAL	2		

70106700	TEMPORARY RUMBLE STRIP					<u>EACH</u>	<u>REMARKS</u>
	LOCATION						
	CHELSEA ROAD - NORTH					3	
	CHELSEA ROAD - SOUTH					3	
			TOTAL			6	