

# IL 75 SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% Federal	I000	I000	RURAL
			TOTAL QUANTITY	RURAL	URBAN	101-1085 101-1084
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	25	25	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8656	6968	1688	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	962	774	188	
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	156907	119927	36980	
• 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	140	140		
• 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	148	124	24	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	360	290	70	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	18	18		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	9	9		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	18	18		
• A2005114	TREE, JUGLANS NIGRA (BLACK WALNUT), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10		
• A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10		
• A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10		
• A2007114	TREE, QUERCUS RUBRA (RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10		
• B2001114	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10		
X0301794	INLET, STAND PIPE	EACH	1			1
X0324380	REMOVE AND REPLACE LID	EACH	2		2	
X5402110	PRECAST CONCRETE BOX CULVERT 11' x 7'	FOOT	132			132
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	41	41		
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1		1	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5	
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	1	1		
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	127	85	42	
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CUYD	21	14	7	
Z0029001	GRATED CULVERT EXTENSION, NO. 1	EACH	8			8
Z0040315	PILOT CAR	DAY	4	3	1	

• Specialty Items