

GENERAL NOTES

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall seed all disturbed areas within the project limits. Seeding Class 4 shall be used. This work will be included in the contract unit price per Ton for Stone Riprap.

Mulch Method II shall be applied over all seeded areas. This shall be included in the cost of the Stone Riprap.

Culvert & bridge flows must be maintained throughout the project. Normal flow shall be allowed to pass at the rate it enters the jobsite. High flows shall be allowed to pass without causing damage to upstream properties.

FILE NAME =	USER NAME = lnrkdj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	General Notes	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D:\BRYCADD plans\Winnebago County\1010035 & 0036\1010035 & 0036.dgn	DRAWN -	REVISED -	738			(5B-1M)	Winnebago	5	3	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 64F58							
PLOT DATE = Thu Oct 01 11:09:56 2009	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		