

SUMMARY OF QUANTITIES				80% FED. 20% STATE X070-2A
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	TOTAL QUANTITY	SN 050-150
20101000	TEMPORARY FENCE	FOOT	398	398
20200100	EARTH EXCAVATION	CU YD	677	677
20400800	FURNISHED EXCAVATION	CU YD	615	615
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	144	144
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	187	187
* 25000110	SEEDING, CLASS 1A	ACRE	1.0	1.0
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90
25100630	EROSION CONTROL BLANKET	SQ YD	4840	4840
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100
28000305	TEMPORARY DITCH CHECKS	FOOT	50	50
28000400	PERIMETER EROSION BARRIER	FOOT	751	751
28000500	INLET AND PIPE PROTECTION	EACH	3	3
28100107	STONE RIPRAP, CLASS A4	SQ YD	1347	1347
28200200	FILTER FABRIC	SQ YD	1347	1347
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1631	1631
35501400	HOT-MIX ASPHALT BASE COURSE, VARIABLE DEPTH	TON	728	728
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	135	135
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	346	346
40600300	AGGREGATE (PRIME COAT)	TON	9	9
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	0.9	0.9
40600525	LEVELING BINDER (HAND METHOD), N50	TON	1.4	1.4
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	120	120
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	587	587
40600990	TEMPORARY RAMP	SQ YD	19	19
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	354	354
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	14	14
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	779	779
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1

SUMMARY OF QUANTITIES				80% FED. 20% STATE X070-2A
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	TOTAL QUANTITY	SN 050-150
50102400	CONCRETE REMOVAL	CU YD	11.4	11.4
50105200	REMOVE EXISTING CULVERTS	EACH	2	2
50200100	STRUCTURE EXCAVATION	CU YD	144	144
50300225	CONCRETE STRUCTURES	CU YD	46.2	46.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	359.0	359.0
50300260	BRIDGE DECK GROOVING	SQ YD	906	906
50300300	PROTECTIVE COAT	SQ YD	1144	1144
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1
50500505	STUD SHEAR CONNECTORS	EACH	4284	4284
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	94,670	94,670
50800515	BAR SPLICERS	EACH	915	915
51500100	NAME PLATES	EACH	1	1
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12	12
52100520	ANCHOR BOLTS, 1"	EACH	36	36
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24	24
54200217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	4	4
54200241	PIPE CULVERTS, CLASS D, TYPE 1 36"	FOOT	300	300
54215571	METAL END SECTIONS 36"	EACH	2	2
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	84	84
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	140	140
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1
61100605	MISCELLANEOUS CONCRETE	CU YD	7.0	7.0
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 ^{FOOT} POSTS	FOOT	163	163
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	475	475
63301000	REMOVE AND RE ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	250	250
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8
67100100	MOBILIZATION	L SUM	1	1

*SPECIALTY ITEM