

SUMMARY OF QUANTITIES

80% FED.
20% STATE
X070-2A

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	TOTAL QUANTITY	SN 050-150
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	678	678
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3813	3813
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48	48
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1099	1099
70400100	TEMPORARY CONCRETE BARRIER	FOOT	713	713
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	662	662
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2436	2436
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	305	305
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	6	6
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	481	481
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	15	15
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	98	98
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	49	49
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	128	128
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2

* SPECIALTY ITEMS