## PAVEMENT

| STA. TO STA. | LENGTH | HOT-MIX ASPHALT BASE COURSE, 8" | HOT-MIX ASPHALT BASE COURSE, VARIABLE DEPTH | BITUMINOUS MATERIALS (PRIME COAT) | AGGREGATE (PRIME COAT) | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | LEVELING BINDER (HAND METHOD), N50 | 3/4" LEVELING BINDER (MACHINE METHOD), N50 | HOT-MIX ASPHALT SURFACE REMOVAL--BUTT JOINT | TEMPORARY RAMP | 1 1/2" HOT-MIX ASPHALT SURFACE COURSE MIX. "C", N50 | HOT-MIX ASPHALT SURFACE REMOVAL--1 1/2" |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | FT | SQ YD | TON | GALLON | TON | TON | TON | TON | SQ YD | SQ YD | TON | SQ YD |
| PRIOR TO STAGE I - CONSTRUCT WIDENING NORTH SIDE OF ROADWAY | | | | | | | | | | | | |
| WEST SIDE OF BRIDGE | | 412.34 | | | | | | | | | | |
| EAST SIDE OF BRIDGE | | 505.76 | | | | | | | | | | |
| SUB-TOTAL | | 918.10 | | | | | | | | | | |
| STAGE I - CONSTRUCT EASTBOUND PAVEMENT | | | | | | | | | | | | |
| 317+05.00 TO 319+00.00 | 195.00 | | | | | | | | | | | |
| 319+00.00 TO 319+60.00 | 60.00 | 60.33 | | | | | | | | | | |
| 319+60.00 TO 320+60.86 | 100.86 | 120.20 | | | | 0.08 | 0.13 | 11.0 | | | | |
| 320+60.86 TO 322+01.10 | 140.24 | 190.80 | 196.8 | | | 0.11 | 0.18 | 15.2 | | 6.7 | | |
| BRIDGE AND BRIDGE APPROACHES OMISSION | | | | | | | | | | | | |
| 322+01.10 TO 324+40.98 | 239.88 | | | | | | | | | | | |
| 324+40.98 TO 325+76.26 | 135.28 | 168.21 | 171.8 | | | 0.10 | 0.17 | 14.4 | | 6.7 | | |
| 325+76.26 TO 327+88.20 | 211.94 | 127.95 | | | | 0.13 | 0.22 | 18.1 | | | | |
| 327+88.20 TO 328+48.20 | 60.00 | 45.08 | | | | | | | | | | |
| 328+48.20 TO 329+23.00 | 74.80 | | | | | | | | | | | |
| SUB-TOTALS | | 712.56 | 368.60 | | | 0.42 | 0.70 | 58.66 | | 13.4 | | |
| STAGE II - CONSTRUCT WESTBOUND PAVEMENT | | | | | | | | | | | | |
| 317+05.00 TO 319+00.00 | 195.00 | | | | | | | | | | | |
| 319+00.00 TO 319+60.00 | 60.00 | | | | | | | | | | | |
| 319+60.00 TO 320+60.86 | 100.86 | | | | | 0.07 | 0.12 | 10.4 | | | | |
| 320+60.86 TO 322+01.10 | 140.24 | | 193.2 | | | 0.11 | 0.18 | 15.2 | | | | |
| BRIDGE AND BRIDGE APPROACHES OMISSION | | | | | | | | | | | | |
| 322+01.10 TO 324+40.98 | 239.88 | | | | | | | | | | | |
| 324+40.98 TO 325+76.26 | 135.28 | | 165.9 | | | 0.10 | 0.17 | 14.0 | | | | |
| 325+76.26 TO 327+88.20 | 211.94 | | | | | 0.16 | 0.26 | 22.2 | | | | |
| 327+88.20 TO 328+48.20 | 60.00 | | | | | | | | | | | |
| 328+48.20 TO 329+23.00 | 74.80 | | | | | | | | | | | |
| SUB-TOTALS | | 0.00 | 359.10 | 0.00 | 0.00 | 0.44 | 0.73 | 61.72 | 0.00 | | 0.00 | 0.00 |
| STAGE III - SURFACE COURSE - EASTBOUND & WESTBOUND | | | | | | | | | | | | |
| 317+05.00 TO 319+00.00 | 195.00 | | | 45.07 | 1.13 | | | | | 14.4 | 47.5 | 563.33 |
| 319+00.00 TO 319+60.00 | 60.00 | | | 23.47 | 0.59 | | | 2.82 | 293.33 | | 24.7 | |
| 319+60.00 TO 320+60.86 | 100.86 | | | 40.45 | 1.01 | | | | | | 42.6 | |
| 320+60.86 TO 322+01.10 | 140.24 | | | 57.51 | 1.44 | | | | | | 60.5 | |
| BRIDGE AND BRIDGE APPROACHES OMISSION | | | | | | | | | | | | |
| 322+01.10 TO 324+40.98 | 239.88 | | | | | | | | | | | |
| 324+40.98 TO 325+76.26 | 135.28 | | | 53.71 | 1.34 | | | | | | 56.6 | |
| 325+76.26 TO 327+88.20 | 211.94 | | | 76.13 | 1.90 | | | | | | 80.2 | |
| 327+88.20 TO 328+48.20 | 60.00 | | | 22.27 | 0.56 | | | 2.82 | 293.33 | | 23.5 | |
| 328+48.20 TO 329+23.00 | 74.80 | | | 17.29 | 0.43 | | | | | 14.4 | 18.2 | 216.09 |
| SUB-TOTALS | | 0 | 0 | 335.90 | 8.40 | | | | 586.67 | | 353.84 | 779.42 |
| TOTALS | | 1630.66 | 727.70 | 335.90 | 8.40 | 0.86 | 1.43 | 120.37 | 586.67 | 13.40 | 353.84 | 779.42 |

| | | | |
|---|---|---|---|
| FILE NAME = c:\pw_work\pwidot\schwankerg\dms73146\d312345-sht-SCHEDULE.DGN | USER NAME = schwankerg | DESIGNED - | REVISED - |
| | | DRAWN - | REVISED - |
| | PLOT SCALE = 50.0000 ' / IN. | CHECKED - | REVISED - |
| | PLOT DATE = Oct 16, 2009 - 02:36:12 PM | DATE - | REVISED - |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**PAVEMENT SCHEDULE**

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 41 | 15 BR-2 | LIVINGSTON | 64 | 6 |

CONTRACT NO. 66691

ILLINOIS FED. AID PROJECT