

TEMPORARY PAINT PAVEMENT MARKING				
U.S. 17 STATION LOCATIONS			4" LINE	24" LINE
			WHITE FOOT	WHITE FOOT
STAGE I				
317+05				12
329+23				12
INSIDE LINE				
317+05	TO	328+63.20	1159	
OUTSIDE LINE				
318+80	TO	327+63	883	
STAGE II				
317+05				12
329+23				12
INSIDE LINE				
318+25	TO	328+63.20	1039	
OUTSIDE LINE				
319+30	TO	326+62	732	
TOTALS			3,813	48

PAVEMENT MARKING					
U.S. 17 STATION LOCATIONS			LIN FT	4" LINE	6" LINE
				WHITE FOOT	YELLOW FOOT
317+05	TO	329+23	1218	2436	304.5
TOTALS			1218	2,436	304.5

RAISED REFLECTIVE PAVEMENT MARKERS				
STA.	TO	STA.	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)
			EACH	EACH
317+05.00	TO	322+01.10	6	
322+01.10	TO	324+40.98		3
324+40.98	TO	329+23.00	6	
TOTALS			12	3

SHORT-TERM PAVEMENT MARKING & WORK ZONE PAVEMENT MARKING REMOVAL						
U.S. 17 STATION LOCATIONS		SHORT-TERM		PAVEMENT MARKING REMOVAL SQ FT	WORK ZONE PAVEMENT MARKING REMOVAL	
		CENTER LINE YELLOW FOOT	EDGE DASH WHITE FOOT		4" LINE WHITE SQ FT	24" LINE WHITE SQ FT
STAGE I						
317+05				481		
329+23						24
INSIDE LINE						
317+05	TO	328+63.20			480	
OUTSIDE LINE						
318+80	TO	327+63				
STAGE II						
317+05						
329+23						24
INSIDE LINE						
318+25	TO	328+63.20			345	
OUTSIDE LINE						
319+30	TO	326+62				
STAGE III						
317+05	TO	329+23	366	312	226	
(3 APPLICATIONS)						
TOTALS			366	312	481	1051