

**DRAINAGE SCHEDULE**

LOCATION	SIDE	CULVERT TO BE CLEANED	CLEANING EXISTING INLETS	GRADING & SHAPING DITCHES	INLETS TO BE ADJUSTED (SPECIAL)	INLET BOXES TO BE ADJUSTED (SPECIAL)	PIPE CULVERT REMOVAL	CONCRETE HEADWALL REMOVAL	REMOVE INLET BOX	END SECTION TO BE REMOVED	INLET BOX STANDARD 542506	INLET BOX STANDARD 542536	PIPE CULV TYPE 1 RCCP, 24"	PIPE CULV TYPE 1 RCCP, 36"	PIPE CULV CLASS D TY 1, 15"
		EACH	EACH	FOOT	EACH	EACH	FOOT	EACH	EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT
STA. 918+00	NB	1	1												
	MEDIAN				1										
STA. 939+50	MEDIAN				1										
STA. 941+50	NB			50											
	MEDIAN					1									
STA. 952+00	NB		1												
	MEDIAN				1										
STA. 961+70	SB	1													
STA. 976+00	NB							1			1		3		
	MEDIAN				1										
STA. 986+00	NB							1			1				
RAMP BD STA. 19+00	RT							1			1		3		
	LT							1			1		2.5		
STA. 994±00	MEDIAN								1						
STA. 995+00	SOUTH			50											
STA. 996+50	SB	1													
STA. 997±40	MEDIAN						8								8
STA. 999+00	NB			50											
RAMP CB STA. 14+50	RT		1												
STA. 1013+00	MEDIAN				1										
	MEDIAN				1										
	NB & SB			100											
STA. 1021+00	SB							1				1		2	
STA. 1026+00	SB	1		50											
STA. 1047+00		1													
STA. 1050+00	SB	1													
STA. 1056+00	NB									1					
STA. 1065+00	NB									1					
	MEDIAN				1										
STA. 1076+00	NB									1					
	SB									1					
STA. 1079+32		1													
	SB							1							
STA. 1080+86	NB	1													
STA. 1091+00	NB		1												
	MEDIAN		1												
STA. 1099+00	NB		1												
STA. 1111+00	NB	1	1												
	MEDIAN		1												
STA. 1132+00	NB		1												
STA. 1142+00	NB		1												
STA. 1152+00	NB		1												
<b>TOTALS</b>		<b>9</b>	<b>11</b>	<b>300</b>	<b>7</b>	<b>1</b>	<b>8</b>	<b>2</b>	<b>5</b>	<b>5</b>	<b>4</b>	<b>1</b>	<b>8.5</b>	<b>2</b>	<b>8</b>

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\pwork\duncanbd\dms30392\ep05105-shd-detail.dgn	5105-shd-detail.dgn	DRAWN -	REVISED -						57	(38-1,2)RS-2 & I	IROQUOIS	263	13
PLT SCALE = 50,0000' / IN.	CHECKED -	REVISED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT CONTRACT NO. 66981				
PLOT DATE = Oct 21, 2009 - 09:43:16 AM	DATE -	REVISED -	REVISED -										