

GENERAL NOTES

SEEDING SHALL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET, OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED WILL BE DETERMINED BY THE ENGINEER.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE PARCEL FOR BUILDING NO. 1 (3TJ0013) HAS BEEN IDENTIFIED AS A SITE CONTAINING CONTAMINATED SOIL (MOSTLY IN NORTH CORNER OF PARCEL). NO EARTH/EMBANKMENT MATERIAL MAY BE REMOVED OFFSITE. THE EARTH SOIL MAY BE MOVED AS LONG AS IT STAYS ON SITE. IF CONSTRUCTION OPERATIONS REQUIRE THAT EARTH MATERIAL TO BE REMOVED OFFSITE THE DISTRICT 3 ENVIRONMENTAL UNIT SHALL BE CONTACTED AT 815-434-8569 PRIOR TO ANY EARTH REMOVAL OPERATIONS. ANY OFFSITE EARTH REMOVAL OPERATIONS WILL ALSO REQUIRE OBTAINING AN ENVIRONMENTAL FIRM TO MONITOR THE OFFSITE REMOVAL AT THE EXPENSE OF THE CONTRACTOR.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

SUMMARY OF QUANTITIES				100% FEDERAL
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		
		UNIT	Y004	
			UNIT	TOTAL QUANTITY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	290	
* 25000200	SEEDING, CLASS 2	ACRE	0.06	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6	
* 25100115	MULCH, METHOD 2	ACRE	0.06	
67100100	MOBILIZATION	L SUM	1	
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	

\*SPECIALTY ITEMS

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE

PREPARED BY: *Paul Powell*  
DISTRICT STUDIES & PLANS ENGINEER

DATE: 8.17.09

EXAMINED BY: *Antoine J. ...*  
DISTRICT CONSTRUCTION ENGINEER

*John J. Phillips*  
DISTRICT MATERIALS ENGINEER

*Bruce A. Hatcher*  
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -
ca:\pwork\1279\1279\JUNCANBD\66157225\6386988sh-t-detailed.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
& GENERAL NOTES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1279	(P6)DM	LASALLE	3	2
CONTRACT NO. 66988				