

CODE NO.	PAY ITEM	UNIT	TOTAL	ROADWAY FAP 685 80% FEDERAL 20% STATE		STRUCTURE FAP 685 80% FEDERAL 20% STATE
				FULTON	MCDONOUGH	MCDONOUGH
				CONSTRUCTION TYPE CODE		
				I000-2A	I000-2A	X081-2A
20100500	TREE REMOVAL, ACRES	ACRE	1.3	0.4	0.9	
20200100	EARTH EXCAVATION	CU YD	14378	7419	6959	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	2304	1219	1085	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	72		72	
20300100	CHANNEL EXCAVATION	CU YD	3146			3146
20700220	POROUS GRANULAR EMBANKMENT	CU YD	17		17	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	169			169
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	103		103	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	15897	6196	9701	
* 25000210	SEEDING, CLASS 2A	ACRE	3.5	1.3	2.2	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	315	117	198	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	315	117	198	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	315	117	198	
* 25100115	MULCH, METHOD 2	ACRE	3.5	1.3	2.2	
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	5870	2155	3715	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	700	260	440	
28000305	TEMPORARY DITCH CHECKS	FOOT	336	56	280	
28000400	PERIMETER EROSION BARRIER	FOOT	6481	1377	5104	
28000500	INLET AND PIPE PROTECTION	EACH	2	1	1	
28100107	STONE RIPRAP, CLASS A4	SQ YD	515		515	
28100125	STONE RIPRAP, CLASS B3	SQ YD	159	64	95	
28100811	STONE DUMPED RIPRAP, CLASS A6	TON	1570			1570
28200200	FILTER FABRIC	SQ YD	2065		515	1550
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1086	484	602	
35501400	HOT-MIX ASPHALT BASE COURSE, VARIABLE DEPTH	TON	223	6	217	
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	974	555	419	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	18		18	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	9.4	2	7.4	
40600300	AGGREGATE (PRIME COAT)	TON	31	7	24	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160	75	85	
40600990	TEMPORARY RAMP	SQ YD	625	16	609	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	692	160	532	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	146	95	51	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	43		43	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	39.5		39.5	
44000100	PAVEMENT REMOVAL	SQ YD	208		208	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	7151	1304	5847	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	61		61	
44002720	GUTTER REMOVAL (SPECIAL)	FOOT	2379	1200	1179	
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SQ YD	80	80		

*SPECIALTY ITEM

EFK Moen, LLC
Civil Engineering Design

FILE NAME =	USER NAME = crespole	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
\$FILES\$		DRAWN - JD	REVISED -			685	37BR-1	MCDONOUGH/ FULTON	138	3	
	PLOT SCALE = 2.0091' / IN.	CHECKED - SD	REVISED -			CONTRACT NO. 68352					
	PLOT DATE = 10/19/2009	DATE - 10/15/09	REVISED -			SCALE: N.T.S.	SHEET NO. 1 OF 3 SHEETS	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			