

CODE NO.	PAY ITEM	UNIT	TOTAL	ROADWAY FAP 685 80% FEDERAL 20% STATE		STRUCTURE FAP 685 80% FEDERAL 20% STATE
				FULTON	MCDONOUGH	MCDONOUGH
				CONSTRUCTION TYPE CODE		
				I000-2A	I000-2A	X081-2A
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	206	32	174	
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	64		64	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	217		217	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2284	1200	1084	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	494	28.4	465.6	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2294	510	1784	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	165	45	120	
50200100	STRUCTURE EXCAVATION	CU YD	244			244
50300225	CONCRETE STRUCTURES	CU YD	69.2			69.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	258.1			258.1
50300260	BRIDGE DECK GROOVING	SQ YD	518			518
50300280	CONCRETE ENCASEMENT	CU YD	5.6			5.6
50300300	PROTECTIVE COAT	SQ YD	662			662
50401105	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 54 IN.	FOOT	558.5			558.5
50800105	REINFORCEMENT BARS	POUND	4014		4014	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	62,950			62,950
50800515	BAR SPLICERS	EACH	566			566
51201600	FURNISHING STEEL PILES HP 12X53	FOOT	945			945
51202305	DRIVING PILES	FOOT	945			945
51203600	TEST PILE STEEL HP 12X53	EACH	2			2
51500100	NAME PLATES	EACH	1			1
54002020	EXPANSION BOLTS 3/4 INCH	EACH	52		52	
54003000	CONCRETE BOX CULVERTS	CU YD	31.3		31.3	
54201273	PIPE CULVERTS, TYPE 2 RCCP 18"	FOOT	34		34	
54201297	PIPE CULVERTS, TYPE 2 RCCP 42"	FOOT	44		44	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2		2	
54248510	CONCRETE COLLAR	CU YD	4		4	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	79	30	49	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	107			107
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	1	2	
60107600	PIPE UNDERDRAINS 4"	FOOT	2293	1157	1136	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	148			148
60219550	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 37 GRATE	EACH	2	1	1	
60600095	CLASS S1 CONCRETE (OUTLET)	CU YD	42.3	14.7	27.6	
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	2041	1007	1034	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1525		1525	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3		3	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	4	1	3	

\*SPECIALTY ITEM

**EFK Moen, LLC**  
Civil Engineering Design

FILE NAME =	USER NAME = crespole	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - JD	REVISED -			685	37BR-1	MCDONOUGH/FULTON	138	4	
	PLOT SCALE = 2.0091' / IN.	CHECKED - SD	REVISED -			SCALE: N.T.S. SHEET NO. 2 OF 3 SHEETS					
	PLOT DATE = 10/19/2009	DATE - 10/15/09	REVISED -			CONTRACT NO. 68352					
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT											