

CODE NO.	PAY ITEM	UNIT	TOTAL	ROADWAY FAP 685 80% FEDERAL 20% STATE		STRUCTURE FAP 685 80% FEDERAL 20% STATE
				FULTON	MCDONOUGH	MCDONOUGH
				CONSTRUCTION TYPE CODE		
				1000-2A	1000-2A	X081-2A
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	3		3	
63200310	GUARDRAIL REMOVAL	FOOT	2449		2449	
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	43.75		43.75	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	34	9	25	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	11	5	6	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1		
66700605	PERMANENT SURVEY TIES	EACH	8	8		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	2	6	
67100100	MOBILIZATION	L SUM	1		1	
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1		1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1		1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1		1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1		1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1		1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	120	24	96	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	3	3	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	0.5	0.5	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	976	211	765	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26270	5476	20794	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5871	1367	4504	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	387.5	50	337.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	362.5	50	312.5	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	9764	2139	7625	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	70		70	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	2	6	
78300100	PAVEMENT MARKING REMOVAL	SO FT	3255	554	2701	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	4	8	
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	563	18	545	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SO FT	1200			1200
X0712400	TEMPORARY PAVEMENT	SO YD	51		51	
X0919000	TEMPORARY PAVEMENT REMOVAL	SO YD	51		51	
† X2503100	MOWING	UNIT	64	13	51	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	343	77	266	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22			22
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1	
* Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1		1	
Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1	
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1	
Z0054500	ROCK FILL	TON	137		137	
⊙ Z0076600	TRAINEES	HOUR	5,000	2,500	2,500	

† NON-PARTICIPATING 100% STATE  
 \* SPECIALTY ITEM  
 ⊙ YOBO

EFK·Moen, LLC  
 Civil Engineering Design

FILE NAME =	USER NAME = jd	DESIGNED -	REVISED -
Z:\08096_Show_Creek\dgn\Design\Final\Plotsheets\05-D468352-sht-S003.dgn		DRAWN - JD	REVISED -
		CHECKED - SD	REVISED -
		DATE - 10/15/09	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 SCALE: N.T.S. SHEET NO. 3 OF 3 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	37BR-1	MCDONOUGH/FULTON	138	5
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		CONTRACT NO. 68352		