

LOCATION OF WORK:

FAS 1517
 BRIDGE
 SN 074-0086
 STA. 288+40.38
 TO
 STA. 290+04.38
 STA. 290+40.38 TO 296+45.15
 FED 80%
 STATE 20%
 I000-2A
 X171-2A

CONSTRUCTION TYPE CODE:

| CODE NO | ITEM | UNIT | TOTAL QUANTITY | QUANTITY | QUANTITY |
|----------|--|-------|----------------|----------|-----------|
| 50104650 | SLOPE WALL REMOVAL | SQ YD | 542.0 | | 542.0 |
| 50105200 | REMOVE EXISTING CULVERTS | EACH | 2.0 | 2.0 | |
| 50157300 | PROTECTIVE SHIELD | SQ YD | 230.0 | | 230.0 |
| 50200100 | STRUCTURE EXCAVATION | CU YD | 250.0 | | 250.0 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 258.2 | | 258.2 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 319.4 | | 319.4 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 697.0 | | 697.0 |
| 50300280 | CONCRETE ENCASEMENT | CU YD | 4.2 | | 4.2 |
| 50300300 | PROTECTIVE COAT | SQ YD | 967.0 | | 967.0 |
| 50500105 | FURNISHING AND ERECTING STRUCTURAL STEEL | L SUM | 1.0 | | 1.0 |
| 50500505 | STUD SHEAR CONNECTORS | EACH | 3,654.0 | | 3,654.0 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 109,850.0 | | 109,850.0 |
| 50800515 | BAR SPLICERS | EACH | 64.0 | | 64.0 |
| 51100100 | SLOPE WALL 4 INCH | SQ YD | 482.0 | | 482.0 |
| 51201600 | FURNISHING STEEL PILES HP12X53 | FOOT | 2,348.0 | | 2,348.0 |
| 51202305 | DRIVING PILES | FOOT | 2,348.0 | | 2,348.0 |
| 51203600 | TEST PILE STEEL HP12X53 | EACH | 2.0 | | 2.0 |
| 51500100 | NAME PLATES | EACH | 1.0 | | 1.0 |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 12.0 | | 12.0 |
| 52100520 | ANCHOR BOLTS, 1" | EACH | 24.0 | | 24.0 |

* SPECIALTY ITEM

(CONTINUED NEXT SHEET)

| | | | | | | | | | | | | |
|---|----------------------|----------------|-----------|---|------------------------------|-------------------------|-------|-------------|---|--------|--------------|-----------|
| FILE NAME = | USER NAME = shorerjm | DESIGNED - JMS | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| c:\pwwork\PWIDOT\SHERERJM\dms86674\050388-sht-500.dgn | DRAWN - JMS | CHECKED - JMS | REVISED - | | 1517 | 12VBR-1 | PIATT | 168 | 8 | | | |
| PLOT SCALE = 100.0000' / IN. | DATE - 050609 | REVISOR - | REVISOR - | | CONTRACT NO. 70388 | | | | | | | |
| PLOT DATE = 10/16/2009 | | | | | SCALE: N/A | SHEET NO. 3 OF 5 SHEETS | STA. | TO STA. | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | |