

44000100 PAVEMENT REMOVAL

STATION	TO	STATION	LENGTH	WIDTH	SQ YD
276+00.00		287+98.87	1198.9	26.0	3463.4
290+41.22		303+00.00	1258.8	26.0	3636.5
TOTAL =					7099.9
USE =					7100.0

44000700 APPROACH SLAB REMOVAL

STATION	TO	STATION	LENGTH	WIDTH	SQ YD
287+98.87		288+10.87	12.0	32.0	42.7
290+29.26		290+41.22	12.0	32.0	42.7
TOTAL =					85.4
USE =					86.0

44000155 HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"

STATION	TO	STATION	LENGTH	WIDTH	SQ YD
273+00.00		276+00.00	300.0	26.0	866.7
303+00.00		304+00.00	100.0	26.0	288.9
TOTAL =					1155.6
USE =					1156.0

44004250 PAVED SHOULDER REMOVAL

STATION	TO	STATION	LENGTH	WIDTH	SQ YD
297+04.80		297+36.53	31.7	3.0	10.6
297+91.68		299+93.19	201.5	13.0	291.1
299+93.19		300+38.89	45.7	3.0	15.2
300+90.70		301+74.41	83.7	3.0	27.9
TOTAL =					344.8
USE =					345.0

44000196 HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL

STATION	TO	STATION	LENGTH	WIDTH	SQ YD
299+19.61		300+15.24	95.6	VAR.	192.9
TOTAL =					192.9
USE =					193.0

50104000 BRIDGE RAIL REMOVAL

	STATION	TO	STATION	LENGTH
LT	288+08.70		LT 290+27.10	219.1
RT	288+12.90		RT 290+31.20	219.1
TOTAL =				438.2
USE =				438.0

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -
ct:\pw\work\PIWIDOT\SHERERJM\dms86674\0570388-shr-rem.dgn		DRAWN - JMS	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/13/2009	DATE - 051909	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF REMOVAL

SCALE: 1" = 20' SHEET NO. 1 OF 8 SHEETS STA. N/A TO STA. N/A

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1517	12VBR-1	PIATT	168	51
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70388	