

SUMMARY OF QUANTITIES

FAP 697 (IL 9)
 VERMILION COUNTY
 STATION 1304+13.46
 TO
 STATION 1305+18.54
 RURAL 2-LANE
 80% FEDERAL
 20% STATE
Y007

LOCATION OF WORK:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY
X542A447	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42", TEMPORARY	FOOT	23.0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	186.0
20400800	FURNISHED EXCAVATION	CU YD	45.0
20700220	POROUS GRANULAR EMBANKMENT	CU YD	124.0
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	200.0
* 25000210	SEEDING, CLASS 2A	ACRE	0.4
* 25000350	SEEDING, CLASS 7	ACRE	0.4
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	35.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	35.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	35.0
* 25100115	MULCH, METHOD 2	ACRE	0.4
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	39.0
28000305	TEMPORARY DITCH CHECKS	FOOT	143.0
28000400	PERIMETER EROSION BARRIER	FOOT	1,100.0
28000500	INLET AND PIPE PROTECTION	EACH	1.0
28100201	STONE RIPRAP, CLASS A1	TON	158.0
28200200	FILTER FABRIC	SQ YD	175.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	77.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	14.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	160.0
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	121.0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	267.0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1.0
50200100	STRUCTURE EXCAVATION	CU YD	319.0
51500100	NAME PLATES	EACH	1.0
54001000	BOX CULVERT END SECTIONS	EACH	2.0

*SPECIALTY ITEM

FILE NAME = c:\ph_work\FWIDOT\BUCKLESJJ\d0132042\05	USER NAME = bucklesjj 70594-sh.t-S00.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 697	SECTION 46BR	COUNTY Vermilion	TOTAL SHEETS 31	SHEET NO. 4
PLOT SCALE = 48,0000' / IN.		CHECKED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 70594		
PLOT DATE = 10/21/2009		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								