

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			90% FED./10% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	334	334	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19903	19903	
40600300	AGGREGATE (PRIME COAT)	TON	398	398	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2085	2085	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	473	473	
40600990	TEMPORARY RAMP	SQ YD	180	180	
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	667	667	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	12744	12744	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	12	12	
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	1618	1618	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	520	520	
44004250	PAVED SHOULDER REMOVAL	SQ YD	2613	2613	
44200549	CLASS A PATCHES, TYPE I, 10 INCH	SQ YD	72	72	
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	268	268	
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	507	507	
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	496	496	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	93	93	
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	102	102	
44213000	PATCHING REINFORCEMENT	SQ YD	1343	1343	
44213200	SAW CUTS	FOOT	5637	5637	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2654	2654	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	12360	12360	
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	3919	3919	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	169	169	
60100072	SHOULDER REMOVAL AND REPLACEMENT 5"	FOOT	82485	82485	
60107600	PIPE UNDERDRAINS 4"	FOOT	80119	80119	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	2366	2366	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	2625	2625	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6	
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	10	10	
63200310	GUARDRAIL REMOVAL	FOOT	3300	3300	
63500205	REMOVING AND REPLACING DELINEATORS	EACH	156	156	
64200105	SHOULDER RUMBLE STRIP	FOOT	83794	83794	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	

SUMMARY OF QUANTITIES			90% FED./10% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	18	18	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8034	8034	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	88158	88158	
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	88942	88942	
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	11044	11044	
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	1430	1430	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1143	1143	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	54	54	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	10	10	
* 81012400	CONDUIT IN TRENCH, 1 1/4" DIA., PVC	FOOT	80	80	
* 81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	52	52	
* 81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	94	94	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	3	3	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	148	148	
* 87900205	DRILL EXISTING HEAVY DUTY HANDHOLE	EACH	4	4	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	308	308	
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1	1	
* X0300780	PIEZO ELECTRIC SENSOR CABLE IN CONDUIT	FOOT	410	410	
* X0301242	PIEZO AXLE SENSOR, CLASS II	FOOT	78	78	
* X0301741	AERIAL SPEED CHECK MARKING	FOOT	48	48	
X0322729	MATERIAL TRANSFER DEVICE	TON	24821	24821	
* X0323014	ELECTRIC CABLE IN CONDUIT, CONOGA-30003	FOOT	672	672	
X0323583	SPEED INDICATOR SIGN	CAL DA	100	100	
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	168	168	
X4063500	PRELIMINARY TEST STRIP	EACH	1	1	
X4066580	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	12716	12716	
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	540	540	
X440A200	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING)	SQ YD	1680	1680	
X4420132	CLASS D PATCHES (SPECIAL)	SQ YD	427	427	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	42	42	
Z0075300	TIE BARS	EACH	439	439	

*Specialty Items