

**REMOVING AND REPLACING DELINEATORS**

MAINLINE NORTHBOUND	56 EACH
MAINLINE SOUTHBOUND	56 EACH
RAMP "A"	9 EACH
RAMP "B"	11 EACH
RAMP "C"	11 EACH
RAMP "D"	13 EACH
<b>TOTAL</b>	<b>156 EACH</b>

**GUARDRAIL REMOVAL**

NB RT STA 5443+15 TO 5446+40	325 FOOT
SB LT STA 5446+25 TO 5449+50	325 FOOT
NB RT STA 5496+15 TO 5499+40	325 FOOT
SB LT STA 5499+15 TO 5502+40	325 FOOT
NB LT STA 5526+48 TO 5529+98	350 FOOT
NB RT STA 5526+73 TO 5529+98	325 FOOT
SB RT STA 5530+79 TO 5534+29	350 FOOT
SB LT STA 5530+75 TO 5534+00	325 FOOT
NB RT STA 5579+40 TO 5582+65	325 FOOT
SB LT STA 5583+30 TO 5586+55	325 FOOT
<b>TOTAL</b>	<b>3300 FOOT</b>

**GUARDRAIL SCHEDULE**

DESCRIPTION	STATION TO STATION	DIRECTION	SIDE	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 6B	GUARDRAIL MARKER, TYPE A	TERMINAL MARKER, DIRECT APPLIED
				FOOT	EACH	EACH	EACH	EACH	EACH
OVERPASS HB-2	5443+00 TO 5443+50	NB	RT		1			4	1
	5443+50 TO 5445+87	NB	RT	237.5				1	
	5445+87 TO 5446+30	NB	RT			1		1	
	5446+30 TO 5446+80	SB	LT			1		1	
OVERPASS HB-3	5446+80 TO 5449+18	SB	LT	237.5				4	
	5449+18 TO 5449+68	SB	LT		1				1
	5496+00 TO 5496+50	NB	RT		1				1
	5496+50 TO 5498+87	NB	RT	237.5				4	
OVERPASS HB-4	5498+87 TO 5499+30	NB	RT			1		1	
	5499+24 TO 5499+67	SB	LT			1		1	
	5499+67 TO 5502+05	SB	LT	237.5				4	
	5502+05 TO 5502+55	SB	LT		1				1
GREEN CREEK BRIDGES	5579+27 TO 5579+77	NB	RT		1				1
	5579+77 TO 5582+14	NB	RT	237.5				4	
	5582+14 TO 5582+57	NB	RT			1		1	
	5583+42 TO 5583+85	SB	LT			1		1	
TOTALS				2625	10	6	4	54	10

**PAVEMENT MARKING SCHEDULE**

STATION TO STATION	LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	PERFORMED PLASTIC PAVEMENT MARKING TYPE B - INLAID LINE 4" (WHITE)	PERFORMED PLASTIC PAVEMENT MARKING TYPE B - INLAID LINE 4" (YELLOW)	PERFORMED PLASTIC PAVEMENT MARKING TYPE B - INLAID LINE 6" (WHITE)	PERFORMED PLASTIC PAVEMENT MARKING TYPE B - INLAID LINE 8" (WHITE)	RAISED REFLECTIVE PAVEMENT MARKER (CRYSTAL)
				FOOT	FOOT	FOOT	FOOT	FOOT
<b>NORTHBOUND</b>								
STA 539900 TO STA 544545	4645	840	9290	4645	4645	1161		117
STA 544545 TO STA 544730	185	37	370	185	185	46		6
STA 544730 TO STA 549845	5115	925	10230	5115	5115	1279		129
STA 549845 TO STA 550025	180	36	360	180	180	45		6
STA 550025 TO STA 550615	590	110	1180		590	148	285	16
STA 550615 TO STA 552135	1520	278	3040	1520	1520	380		39
STA 552135 TO STA 552860	725	135	1450		725	181		19
STA 552860 TO STA 553274	414	79	828					
STA 553274 TO STA 558180	4906	887	9812	4906	4906	1227		124
STA 558180 TO STA 558375	195	39	390	195	195	49		6
STA 558375 TO STA 561882	3507	635	7014	3507	3507	877		89
<b>SOUTHBOUND</b>								
STA 539900 TO STA 544540	4640	839	9280	4640	4640	1160		117
STA 544540 TO STA 544725	185	37	370	185	185	46		6
STA 544725 TO STA 549830	5105	923	10210	5105	5105	1276		129
STA 549830 TO STA 550010	180	36	360	180	180	45		6
STA 550010 TO STA 550971	961	177	1923	962	961	240		25
STA 550971 TO STA 552813	1842	336	3683	1842	1842	461		47
STA 552813 TO STA 553226	413	78	826					
STA 553226 TO STA 553955	729	135	1458		729	182		19
STA 553955 TO STA 555709	1754	320	3508	1754	1754	439		45
STA 555709 TO STA 556372	663	123	1326		663	166	350	18
STA 556372 TO STA 557613	1241	227	2482	1241	1241	310		32
STA 557613 TO STA 557529								
STA 557529 TO STA 558225	696	129	1392	696	696	174		18
STA 558225 TO STA 558420	195	39	390	195	195	49		6
STA 558420 TO STA 561913	3493	633	6986	3493	3493	873		88
RAMP "A"				840	270		285	16
RAMP "B"				950	170	160	80	
RAMP "C"				1025	260	70	80	
RAMP "D"				1150	480		350	20
<b>TOTALS</b>	<b>44079</b>	<b>8034</b>	<b>88158</b>	<b>44510</b>	<b>44432</b>	<b>11044</b>	<b>1430</b>	<b>1143</b>