

BUILDING REMOVAL SCHEDULE	
BUILDING NUMBER	REMOVAL (SQ FT)
1	4431.5
2	2951.6
3	5921.0
4	5949.3
5	454.5
6	10542.6
TOTAL	30251

PAVEMENT SCHEDULE		
LOCATION	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", NTO, 1 1/2" (TON)	BITUMINOUS MATERIALS (PRIME COAT) (TON)
SIDDLE PARCEL	610	2.3
TOTALS	610	2.3

EARTHWORK SCHEDULE			
MATERIAL	FILL (CU YD)	FILL (TON)	FABRIC (SQ YD)
FURNISHED EXCAVATION, SPECIAL	10349		
AGGREGATE SURFACE COURSE, TYPE A		9396	
GEOTEXTILE FABRIC, SPECIAL			14753
TOTALS	10349	9396	14753

POWER POLE REMOVAL SCHEDULE			
LOCATION	SIDE	POWER POLE (EACH)	POWER POLE W/GUY WIRE (EACH)
10+94.50	LT		1
11+43.59	LT	1	
11+87.06	LT	1	
12+15.25	LT		1
12+66.25	LT		1
12+95.08	LT	1	
13+01.37	LT	1	
13+19.86	RT	1	
13+51.47	RT	1	
13+63.63	LT	1	
13+88.80	LT	1	
14+83.07	LT	1	
15+42.50	RT	1	
16+53.11	RT	1	
17+54.61	RT	1	
18+76.27	RT	1	
19+12.02	LT	1	
19+83.62	LT	1	
20+22.86	RT	1	
20+57.16	RT	1	
TOTALS		17	3

••POWER POLE REMOVALS ARE PROVIDED FOR INFORMATION ONLY AND ARE TO BE REMOVED BY THE UTILITY COMPANY AND NOT THE CONTRACTOR.

FENCE REMOVAL SCHEDULE		
LOCATION		CHAIN LINK FENCE REMOVAL (SPECIAL) (FT)
10+35.64 - 195.94' LT TO 20+98.48 - 42.65' RT		1130
11+45.39 - 71.94' LT TO 11+86.36 - 88.05' LT		73
11+71.42 - 147.39' RT TO 12+20.24 - 188.06' LT		463
14+33.17 - 157.17' LT TO 15+75.06 - 193.15' RT		378
TOTAL		2044

FENCE SCHEDULE		
LOCATION		CHAIN LINK FENCE (SPECIAL) (FT)
10+35.64 - 195.94' LT TO 20+98.48 - 42.65' RT		1184
TOTAL		1184

STEEL SIGN REMOVAL SCHEDULE		
LOCATION	SIDE	SIGN REMOVAL (EACH)
11+61.40	94.0' RT	1
TOTAL		1

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			998	82-II	ST. CLAIR	13	5	
		CHECKED -	REVISED -			CONTRACT NO. 76C46					
		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	