EXISTING KANSAS CITY SOUTHERN RAILROAD

EXISTING CSX RAILROAD

ST. CLAIR AVENUE

BEGIN FENCE REMOVAL

END FENCE REMOVAL

EXISTING FENCING ALONG WEST PROPERTY LINE TO REMAIN

EXISTING FENCING ALONG WEST PROPERTY LINE TO BE REMOVED

EXISTING FENCING ALONG NORTH PROPERTY LINE TO BE REMOVED

EXISTING FENCING ALONG SOUTH PROPERTY LINE TO REMAIN

EXISTING FENCING ALONG NORTH PROPERTY LINE TO BE REMOVED

EXISTING INTERIOR FENCING TO BE REMOVED (TYP.)

EXISTING FENCING ALONG SOUTH PROPERTY LINE TO REMAIN

EXISTING GATE TO REMAIN

CONCRETE BROKEN & COVERED

OLD & BROKEN CONCRETE

CONCRETE FLOOR

AGGREGATE FLOOR

BIT. FLOOR

CONC. FLOOR EL. 421.7

CONC. LOADING DOCK

C AGGREGATE FLOOR

BIT. FLOOR ELEV. 421.5

ABANDONED RR.

OLD SIGN

BILLBOARD

TUNNEL

15+00

10+00

20+00

N

NOTES

1. NO EXCAVATION SHALL BE MADE ON THIS PARCEL.

2. CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL POLES, ANCHORS, GATES, BARBED WIRE, AND ANY OTHER APPURTENANCES OF THE EXISTING 8-FOOT FENCE WITH BARBED WIRE THAT IS TO BE REMOVED. ALL DISPOSAL, EQUIPMENT AND LABOR, IN PERFORMING THE REQUIRED OPERATIONS FOR THE REMOVAL OF THE FENCE SHALL BE INCLUDED IN THE UNIT PRICE. ONCE THE FENCE IS REMOVED IT SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND WILL BE HIS RESPONSIBILITY TO REMOVE IT FROM THE PREMISES.

3. ALL POLES, ANCHORS, AND SUPPORTS SHALL BE CUT FLUSH WITH THE EXISTING GROUND. NO EXCAVATION SHALL BE MADE TO REMOVE THE POSTS ON THIS PARCEL.

4. SEQUENCING OF EXISTING FENCE REMOVAL AND CONSTRUCTION OF THE PROPOSED FENCE WILL BE DETERMINED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING THE SITE SECURE AT ALL TIMES DURING CONSTRUCTION.

50' 0 50' 100'

SCALE: 1" = 50'

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = $DATE$	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FENCE REMOVAL PLAN

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
998	82-11	ST. CLAIR	13	8
		CONTRACT NO. 76C46		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT