

SCHEDULE OF QUANTITIES

44300200 - STRIP REFLECTIVE CRACK CONTROL TREATMENT

| STA | STA | SIDE | FOOT |
|--------|--------|------|------|
| 903+89 | 911+89 | LT | 721 |
| 903+89 | 910+95 | RT | 824 |
| 911+75 | 918+86 | RT | 710 |
| 911+90 | 912+34 | LT | 135 |
| 912+30 | 917+69 | LT | 562 |
| 917+98 | 921+76 | LT | 402 |
| 922+08 | 925+58 | LT | 362 |
| 922+71 | 925+53 | RT | 305 |
| TOTAL | | | 4021 |

60255500 - MANHOLES TO BE ADJUSTED

| STA | OFF | SIDE | EACH |
|-----------|-----|------|------|
| 911+80 | 15 | RT | 1 |
| 912+22 | 29 | LT | 1 |
| 917+88 | 3 | LT | 1 |
| 917+92 | 17 | LT | 1 |
| 918+03 | 2 | RT | 1 |
| 918+06 | 5 | RT | 1 |
| 921+85 | 2 | LT | 1 |
| 922+11 | 2 | LT | 1 |
| 921+66 | 1 | LT | 1 |
| SUB-TOTAL | | | 9 |

TO ACCOUNT FOR ITEM 60255800 CONTINGENCY, SAY 7 TOTAL

60255800 - MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID

FOR CONTINGENCY, USE 20% OF TOTAL MANHOLES, SAY 2 TOTAL

60260200 - INLETS TO BE ADJUSTED (SPECIAL)

| STA | OFF | SIDE | EACH |
|--------|-----|------|------|
| 905+00 | 0 | RT | 1 |
| 905+00 | 24 | RT | 1 |
| 909+00 | 0 | RT | 1 |
| 909+00 | 24 | RT | 1 |
| 911+05 | 26 | RT | 1 |
| 911+50 | 1 | LT | 1 |
| 911+66 | 24 | RT | 1 |
| 911+81 | 21 | LT | 1 |
| 912+59 | 17 | LT | 1 |
| 913+78 | 10 | LT | 1 |
| 914+00 | 24 | RT | 1 |
| 914+80 | 3 | LT | 1 |
| 917+40 | 0 | RT | 1 |
| 918+04 | 24 | RT | 1 |
| 918+19 | 0 | RT | 1 |
| 919+00 | 0 | RT | 1 |
| 920+00 | 0 | RT | 1 |
| 921+00 | 0 | RT | 1 |
| 922+35 | 0 | RT | 1 |
| 922+35 | 0 | RT | 1 |
| 917+70 | 18 | LT | 1 |
| 917+96 | 18 | LT | 1 |
| 923+52 | 71 | RT | 1 |
| 923+23 | 71 | RT | 1 |
| 922+89 | 53 | RT | 1 |
| 922+69 | 71 | RT | 1 |
| 922+69 | 75 | RT | 1 |
| TOTAL | | | 27 |

60265700 - VALVE VAULTS TO BE ADJUSTED

| STA | OFF | SIDE | EACH |
|-----------|-----|------|------|
| 911+96 | 25 | LT | 1 |
| 912+45 | 5 | LT | 1 |
| 913+62 | 3 | LT | 1 |
| SUB-TOTAL | | | 3 |

TO ACCOUNT FOR ITEM 60265900 CONTINGENCY, SAY 2 TOTAL

60265900 - VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID

FOR CONTINGENCY, USE 1/3 OF TOTAL VALVE VAULTS, SAY 1 TOTAL

60610100 - COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.18 (MODIFIED)

| STA | STA | SIDE | FOOT |
|--------|--------|------|------|
| 911+65 | 911+84 | LT | 28 |
| 911+90 | 912+33 | LT | 135 |
| 912+28 | 912+69 | LT | 54 |
| 912+86 | 913+98 | RT | 112 |
| 917+50 | 917+69 | LT | 30 |
| 920+34 | 920+78 | LT | 44 |
| 923+12 | 923+22 | RT | 31 |
| TOTAL | | | 434 |

70106800 - CHANGEABLE MESSAGE SIGN

| SIGNS | MONTHS/EACH | CAL MO |
|-------|-------------|--------|
| 3 | 1.5 | 4.5 |
| TOTAL | | 4.5 |

70300100 - SHORT-TERM PAVEMENT MARKING

| SKIP DASH | STA | FOOT |
|-----------|--------|------|
| 909+01 | 921+73 | 232 |
| 922+29 | 925+72 | 64 |
| 922+34 | 925+72 | 64 |
| SUB-TOTAL | | 360 |

| TURN LANE | STA | FOOT |
|-----------|--------|------|
| 912+91 | 913+89 | 40 |
| 922+76 | 923+86 | 24 |
| SUB-TOTAL | | 64 |

TOTAL 424

70300210 - TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS

| STA | ITEM | SQ FT |
|--------|----------|-------|
| 912+83 | LT ARROW | 15.6 |
| 913+27 | ONLY | 20.8 |
| 913+70 | LT ARROW | 15.6 |
| 923+04 | RT ARROW | 15.6 |
| 923+35 | ONLY | 20.8 |
| 923+66 | RT ARROW | 15.6 |
| TOTAL | | 104 |

70300220 - TEMPORARY PAVEMENT MARKING - LINE 4"

| EDGE LINE | STA | FOOT |
|-----------|--------|------|
| 899+00 | 909+01 | 1014 |
| 899+00 | 900+11 | 111 |
| 903+55 | 911+32 | 790 |
| 903+55 | 911+43 | 788 |
| 911+64 | 918+15 | 650 |
| SUB-TOTAL | | 3353 |

| SKIP DASH | STA | FOOT |
|-----------|--------|------|
| 909+01 | 921+73 | 320 |
| 922+29 | 925+72 | 90 |
| 922+34 | 925+72 | 90 |
| SUB-TOTAL | | 500 |

TOTAL 3853

70300240 - TEMPORARY PAVEMENT MARKING - LINE 6"

| CROSSWALK LINES | INTERSECTION | FOOT |
|-----------------|--------------|------|
| JACKSON | JACKSON | 48 |
| JACKSON | JACKSON | 45 |
| TOTAL | | 93 |

70300250 - TEMPORARY PAVEMENT MARKING - LINE 8"

| TURN LANE | STA | FOOT |
|-----------|--------|------|
| 900+11 | 902+05 | 193 |
| 900+31 | 901+28 | 100 |
| 911+90 | 913+89 | 200 |
| 911+99 | 912+03 | 97 |
| 912+03 | 912+91 | 180 |
| 918+15 | 921+67 | 351 |
| 918+15 | 921+67 | 351 |
| 922+76 | 923+86 | 110 |
| TOTAL | | 1582 |

70300260 - TEMPORARY PAVEMENT MARKING - LINE 12"

| DIAGONALS | STA | FOOT |
|-----------|--------|------|
| 903+55 | 909+01 | 44 |
| 918+90 | 921+67 | 128 |
| TOTAL | | 172 |

70300280 - TEMPORARY PAVEMENT MARKING - LINE 24"

| STOP BAR | INTERSECTION | APPROACH | FOOT |
|----------|--------------|----------|------|
| RURAL | WB | WB | 13 |
| Y BLVD | NB | NB | 14 |
| TOTAL | | | 27 |

78000100 - THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

| STA | ITEM | SQ FT |
|--------|----------|-------|
| 912+83 | LT ARROW | 15.6 |
| 913+27 | ONLY | 20.8 |
| 913+70 | LT ARROW | 15.6 |
| 923+04 | RT ARROW | 15.6 |
| 923+35 | ONLY | 20.8 |
| 923+66 | RT ARROW | 15.6 |
| TOTAL | | 104 |

78000200 - THERMOPLASTIC PAVEMENT MARKING - LINE 4"

| EDGE LINE | STA | FOOT |
|-----------|--------|------|
| 899+00 | 909+01 | 1014 |
| 899+00 | 900+11 | 111 |
| 903+55 | 911+32 | 790 |
| 903+55 | 911+43 | 788 |
| 911+64 | 918+15 | 650 |
| SUB-TOTAL | | 3353 |

| SKIP DASH | STA | FOOT |
|-----------|--------|------|
| 909+01 | 921+73 | 320 |
| 922+29 | 925+72 | 90 |
| 922+34 | 925+72 | 90 |
| SUB-TOTAL | | 500 |

TOTAL 3853

78000400 - THERMOPLASTIC PAVEMENT MARKING - LINE 6"

| CROSSWALK LINES | INTERSECTION | FOOT |
|-----------------|--------------|------|
| JACKSON | JACKSON | 48 |
| JACKSON | JACKSON | 45 |
| TOTAL | | 93 |

70301000 - WORK ZONE PAVEMENT MARKING REMOVAL

| SKIP DASH - SHORT TERM | STA | STA | SQ FT |
|------------------------|--------|-----|-------|
| 909+01 | 921+73 | | 232 |
| 922+29 | 925+72 | | 64 |
| 922+34 | 925+72 | | 64 |
| SUB-TOTAL | | | 360 |

| TURN LANES - SHORT TERM | STA | STA | SQ FT |
|-------------------------|--------|-----|-------|
| 912+91 | 913+89 | | 40 |
| 922+76 | 923+86 | | 24 |
| SUB-TOTAL | | | 64 |

| LETTERS AND SYMBOLS - TEMPORARY | STA | ITEM | TOTAL |
|---------------------------------|----------|------|-------|
| 912+83 | LT ARROW | | 15.6 |
| 913+27 | ONLY | | 20.8 |
| 913+70 | LT ARROW | | 15.6 |
| 923+04 | RT ARROW | | 15.6 |
| 923+35 | ONLY | | 20.8 |
| 923+66 | RT ARROW | | 15.6 |
| SUB-TOTAL | | | 104 |

| EDGE LINE - TEMPORARY | STA | STA | SQ FT |
|-----------------------|--------|-----|-------|
| 899+00 | 909+01 | | 338 |
| 899+00 | 900+11 | | 37 |
| 903+55 | 911+32 | | 263 |
| 903+55 | 911+43 | | 263 |
| 911+64 | 918+15 | | 217 |
| SUB-TOTAL | | | 1118 |

| SKIP DASH - TEMPORARY | STA | STA | SQ FT |
|-----------------------|--------|-----|-------|
| 909+01 | 921+73 | | 107 |
| 922+29 | 925+72 | | 30 |
| 922+34 | 925+72 | | 30 |
| SUB-TOTAL | | | 167 |

| CROSSWALKS - TEMPORARY | LOCATION | SQ FT |
|------------------------|----------|-------|
| JACKSON | JACKSON | 24 |
| JACKSON | JACKSON | 23 |
| SUB-TOTAL | | 47 |

| TURN LANES - TEMPORARY | STA | STA | SQ FT |
|------------------------|--------|-----|-------|
| 900+11 | 902+05 | | 129 |
| 900+31 | 901+28 | | 67 |
| 911+90 | 913+89 | | 133 |
| 911+99 | 912+03 | | 65 |
| 912+03 | 912+91 | | 120 |
| 918+15 | 921+67 | | 234 |
| 918+15 | 921+67 | | 234 |
| 922+76 | 923+86 | | 73 |
| SUB-TOTAL | | | 1055 |

| DIAGONALS - TEMPORARY | STA | STA | SQ FT |
|-----------------------|--------|-----|-------|
| 903+55 | 909+01 | | 44 |
| 918+90 | 921+67 | | 128 |
| SUB-TOTAL | | | 172 |

| STOP BARS - TEMPORARY | INTERSECTION | APPROACH | SQ FT |
|-----------------------|--------------|----------|-------|
| RURAL | WB | WB | 26 |
| Y BLVD | NB | NB | 28 |
| SUB-TOTAL | | | 54 |

| TOTAL | | | 3141 |
|-------|--|--|------|
|-------|--|--|------|

78000500 - THERMOPLASTIC PAVEMENT MARKING - LINE 8"

| TURN LANE LINES & ISLANDS | STA | STA | FOOT |
|---------------------------|--------|-----|------|
| 900+11 | 902+05 | | 193 |
| 900+31 | 901+28 | | 100 |
| 911+90 | 913+89 | | 200 |
| 911+99 | 912+03 | | 97 |
| 912+03 | 912+91 | | 180 |
| 922+76 | 923+86 | | 110 |
| TOTAL | | | 880 |

78000600 - THERMOPLASTIC PAVEMENT MARKING - LINE 12"

| DIAGONALS | STA | STA | FOOT |
|-----------|--------|-----|------|
| 903+55 | 909+01 | | 44 |
| TOTAL | | | 44 |

78000650 - THERMOPLASTIC PAVEMENT MARKING - LINE 24"

| STOP BAR | INTERSECTION | APPROACH | FOOT |
|----------|--------------|----------|------|
| RURAL | WB | WB | 13 |
| Y BLVD | NB | NB | 14 |
| TOTAL | | | 27 |

78005140 - EPOXY PAVEMENT MARKING - LINE 8"

| MEDIAN | STA | STA | FOOT |
|--------|--------|-----|------|
| 918+15 | 921+67 | | 351 |
| 918+15 | 921+67 | | 351 |
| TOTAL | | | 702 |

78005150 - EPOXY PAVEMENT MARKING - LINE 12"

| DIAGONALS | STA | STA | FOOT |
|-----------|--------|-----|------|
| 918+90 | 921+67 | | 128 |
| TOTAL | | | 128 |

X0321556 - SANITARY MANHOLES TO BE ADJUSTED

| STA | OFF | SIDE | EACH |
|--------|-----|------|------|
| 912+02 | 5 | RT | 1 |
| 917+83 | 17 | RT | 1 |
| 921+94 | 17 | RT | 1 |
| 922+60 | 16 | RT | 1 |
| 923+93 | 16 | RT | 1 |
| 924+46 | 16 | RT | 1 |
| TOTAL | | | 6 |

Z0010700 - COLD MILLING

| STA | STA | SQ YD |
|--------|--------|-------|
| 903+89 | 918+86 | 5140 |
| TOTAL | | 5140 |

Z0028415 - GEOTECHNICAL REINFORCEMENT

FOR CONTINGENCY, ASSUME 1/3 OF ALL PATCHES WILL REQUIRE THIS ITEM

| PATCH | SQ YD | |
|-------------------|-------|-----|
| TYPE II - 8 1/2" | 16 | |
| TYPE II - 10" | 22 | |
| TYPE III - 8 1/2" | 102 | |
| TYPE III - 10" | 59 | |
| TYPE IV - 8 1/2" | 616 | |
| TYPE IV - 10" | 148 | |
| TOTAL | | 962 |