

SUMMARY OF QUANTITIES

PAY ITEM	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE 1000	NON-PARTICIPATING 100% LOCAL FUNDING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	21	21	
* 20200410	EARTH EXCAVATION (SPECIAL)	CU YD	660	660	
▲ 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	200	200	
20800150	TRENCH BACKFILL	CU YD	281	281	
+ 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	48	48	
+ 25200100	SODDING	SQ YD	48	48	
28000500	INLET AND PIPE PROTECTION	EACH	10	10	
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	3,054	3,054	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	864	864	
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	2,728	2,728	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	544	544	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	595	595	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	260	260	
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	528	528	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	187	187	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	9,785	9,785	
42400800	DETECTABLE WARNINGS	SQ FT	78	78	
44000100	PAVEMENT REMOVAL	SQ YD	3,515	3,515	
* 50900810	PEDESTRIAN RAIL (SPECIAL)	FOOT	50	50	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	
* 60242400	INLETS, SPECIAL	EACH	8	8	
60255500	MANHOLES TO BE ADJUSTED	EACH	6	6	
60260100	INLETS TO BE ADJUSTED	EACH	1	1	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	14	14	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1,453	1,453	
67100100	MOBILIZATION	L SUM	1	1	
* 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,222	1,222	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	28	28	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	464	464	
72000100	SIGN PANEL - TYPE 1	SQ FT	54	54	
+ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,333	1,333	
+ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	714	714	
+ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	161	161	
+ 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	1,695	1,695	
+ 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	370	370	
+ 81028030	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT, 1"	FOOT	395	395	
+ 81028060	CONDUIT, BORED AND PULLED, COILABLE NON-METALLIC CONDUIT, 2"	FOOT	240	240	
+ 81200100	CONDUIT EMBEDDED IN STRUCTURE 1" DIA., GALVANIZED STEEL	FOOT	440	440	
+ 81200120	CONDUIT EMBEDDED IN STRUCTURE 2" DIA., GALVANIZED STEEL	FOOT	20	20	
*▲+ 81400115	HANDHOLE TO BE ADJUSTED	EACH	13	13	
+ 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1	1	
+ 81400730	HANDHOLE, COMPOSIT CONCRETE	EACH	4	4	
+ 81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	110	110	
+ 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	9,500	9,500	
+ 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	6,700	6,700	
+ 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	5,600	5,600	
+ 81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	500	500	
+ 81702180	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	110	110	
+ 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,065	2,065	
*+ 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1	1	
*+ 83600100	LIGHT POLE FOUNDATION	EACH	35	35	
+ 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	25	25	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	152	152	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	338	338	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	104	104	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	105	105	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	330	330	
+ A2007820	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5	
* X0322916	PROPOSED STORM SEWER CONNECTION TO EXISTING STORM SEWER	EACH	1	1	
+ B2000770	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2	
* X0444100	BENCHES	EACH	6	6	6
*+ X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1	1	
* XX000959	TRASH RECEPTACLES	EACH	3	3	3
* XX003059	DECORATIVE BRICK SIDEWALK	SQ FT	3,072	3,072	
*+ XX004145	DRINKING FOUNTAIN RELOCATED	EACH	1	1	
* XX005043	ORNAMENTAL SIGN POST	EACH	8	8	
* XX005283	BRICK PAVER CROSSWALK	SQ FT	2,026	2,026	
+ XX005856	MULCH-SHREDDED HARDWOOD BARK, 3" DEPTH	CU YD	2.7	2.7	
+ A200447	GINKGO BILOBA 'AUTUMN GOLD' (AUTUMN GOLD MAIDENHAIR TREE) 1 1/2	EACH	2	2	
*+ XX006901	TREE GRATE ASSEMBLY, COMPLETE	EACH	14	14	
*+ XX007393	DECORATIVE LIGHT TYPE A	EACH	35	35	
*▲+ Z0056800	SANITARY SEWER 6"	FOOT	200	200	

* SEE SPECIAL PROVISIONS + SPECIALTY ITEMS
 ▲ CONTINGENCY ITEMS


ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S. B. L. FALL 5489	*	LEE	35	3
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		
* Section 03-00160-00-PV			Contract #85503	

SUMMARY OF QUANTITIES

HENNEPIN AVE.

SECTION 03-00160-00-PV

CITY OF DIXON



GROUND BREAKING SOLUTIONS
engineers - surveyors - scientists

Date:
09/25/09

Job:
2090205

www.wendlergs.com ph: 815.288.2281