


ITEM NO.	DESCRIPTION	UNIT	QUANTITY
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW		
	INTERSECTION OF 2ND & HENNEPIN	FOOT	40
	BETWEEN 2ND ST. & 1ST. ON HENNEPIN	FOOT	582
	INTERSECTION OF 1ST & HENNEPIN	FOOT	64
	BETWEEN 1ST & RIVER ST. ON HENNEPIN	FOOT	570
	TOTAL		1256
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE		
	INTERSECTION OF 2ND ST. & 1ST. ON HENNEPIN	FOOT	34
	BETWEEN 1ST & RIVER ST. ON HENNEPIN	FOOT	43
	TOTAL		77
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6" WHITE		
	INTERSECTION OF 2ND & HENNEPIN	FOOT	356
	INTERSECTION OF 1ST & HENNEPIN	FOOT	304
	INTERSECTION OF ALLEY & HENNEPIN	FOOT	54
	TOTAL		714
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24" WHITE		
	INTERSECTION OF 2ND & HENNEPIN	FOOT	82
	INTERSECTION OF 1ST & HENNEPIN	FOOT	65
	INTERSECTION OF RIVER ST. & HENNEPIN	FOOT	14
	TOTAL		161
XX005043	ORNAMENTAL SIGN POST		
	LT. STA. 9+21	EACH	1
	RT. STA. 9+31	EACH	1
	LT. STA. 9+80	EACH	1
	RT. STA. 9+96	EACH	1
	LT. STA. 12+87	EACH	1
	RT. STA. 13+02	EACH	1
	LT. STA. 13+44	EACH	1
	RT. STA. 13+56	EACH	1
	TOTAL		8
72000100	SIGN PANEL - TYPE 1		
	LT. STA. 9+21 R1-1 STOP, R1-3	SQ. FT.	6.75
	RT. STA. 9+31 R1-1 STOP, R1-3	SQ. FT.	6.75
	LT. STA. 9+80 R1-1 STOP, R1-3	SQ. FT.	6.75
	RT. STA. 9+96 R1-1 STOP, R1-3	SQ. FT.	6.75
	LT. STA. 12+87 R1-1 STOP, R1-3	SQ. FT.	6.75
	RT. STA. 13+02 R1-1 STOP, R1-3	SQ. FT.	6.75
	LT. STA. 13+44 R1-1 STOP, R1-3	SQ. FT.	6.75
	RT. STA. 13+56 R1-1 STOP, R1-3	SQ. FT.	6.75
	TOTAL		54



- CONCRETE PAVERS
- PCC CONCRETE PAVEMENT
- HOT MIX ASPHALT

PAVEMENT & STRIPING PLAN

HENNEPIN AVE.
SECTION 03-00160-00-PV
CITY OF DIXON

GROUND BREAKING SOLUTIONS
engineers - surveyors - scientists

www.wendlers.com ph: 815.288.2261

Date:
09/25/09

Job:
2090205