



**GENERAL NOTES**

EXCAVATION FOR STRUCTURES SHALL NOT BE CLASSIFIED COMPENSATION FOR SUCH SHALL BE CONSIDERED AS INCLUDED IN THE CONTRACT UNIT PRICE FOR PRECAST/PRESTRESSED CONCRETE PLANK.  
 THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION ADOPTED BY THE DEPARTMENT OF PUBLIC WORKS AND BUILDINGS ON JANUARY 2, 1976 SHALL APPLY TO THIS WORK.  
 SEE SPECIAL PROVISIONS FOR THE ITEM PRECAST/PRESTRESSED CONCRETE PLANK.  
 ALL DIMENSIONS SHALL BE NOT-DIPPED UNLESS NOTED.

**PILE DATA**

TYPE	STEEL PIPE	HP 8X36
NUMBER REQUIRED	36	(19 Abut Piles) (17 Wing Piles)
ESTIMATED LENGTH		
MINIMUM CAPACITY		As Detailed

**WATERWAY INFORMATION**

DRAINAGE AREA	15.9	SQ MILES
EXISTING OPENING	202	SQ FT
REQUIRED OPENING	260	SQ FT
PROPOSED OPENING	260	SQ FT
DESIGN FREQUENCY	25	YEARS
DESIGN DISCHARGE	1441	C.F.S.

**NAME PLATE**

STATION 44+70.00  
 EGG BAG CREEK  
 BUILT 197  
 FAS RTE 1284 SEC 138-G  
 FAS PROJ. S-1284(106)  
 LOADING HS 20

**GENERAL PLAN  
 &  
 ELEVATION  
 EGG BAG CREEK  
 SECTION 138-G  
 LASALLE COUNTY  
 STATION 44+70.00**

**EXISTING STRUCTURE PLANS**

SHEET NO. 1  5 SHEETS	ROUTE NO. CH 29	SECTION 10-00649-00-BR	COUNTY LASALLE	TOTAL SHEETS 43	SHEET NO. 29
	S.N. 050-3593		CONTRACT NO. 87430		
	FED. ROAD DIST. NO. 7 ILLINOIS		FED. AID PROJECT BRS-0099(043)		