

LANDSCAPE SCHEDULE								
LOCATION	TREE REMOVAL (OVER 15 UNITS DIA) (20100210)	TREE AUTUMN BLAZE FREEMAN MAPLE (A2000116)	SEEDING CLASS 1A (25000110)	NITROGEN FERT. NUTRIENT (25000400)	PHOSPHOR. FERT. NUTRIENT (25000500)	POTASS. FERT. NUTRIENT (25000600)	MULCH METHOD 2 (25100115)	SODDING SALT TOLERANT (25200110)
	UNIT	EACH	ACRE	POUND	POUND	POUND	ACRE	SQ YD
WEST SIDE BUCHANAN STREET	34			1	1	1		63
EAST SIDE BUCHANAN STREET BTWN SIDEWALK & CURB				1	1	1		67
EAST SIDE BUCHANAN STREET EAST OF SIDEWALK		2	0.07	8	8	8	0.07	
<b>TOTALS</b>	34	2	0.07	10	10	10	0.07	130

AGG SURF CSE TYPE B SCHEDULE (40200800)	
LOCATION	TON
REPAIR OF EX AGGREGATE DRIVE AS DIRECTED BY THE ENGINEER	20
<b>TOTAL</b>	20

CONCRETE SCHEDULE				
LOCATION	CLASS C PATCHES TYPE IV 9 IN (44201347)	COMB. CONC CURB AND GUTTER, (SPECIAL) (60611600)	PCC SIDEWALK 5" (42400200)	CONCRETE COLLAR (54248510)
	SQ YD	FOOT	SQ FT	CU YD
OVER PR CULVERT	107			
WEST SIDE OF CULVERT		42		
EAST SIDE OF CULVERT		42	510	
EX 10" VCP NW CORNER				0.5
EX 10" VCP NE CORNER				0.5
EX 24" RCP				1.0
EX 21" RCP				0.9
EX 12" RCP				0.6
EX 8" RCP				0.5
EX 10" RCP				0.5
EX 6" RCP				0.5
PR 66" DIA				6.0
<b>TOTALS</b>	107	84	510	11

EARTHWORK SCHEDULE					
LOCATION	EARTH EXCAVATION (20200100)	INCIDENTAL EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT (NOT A PAY ITEM)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-)
	CU YD	CU YD	CU YD	CU YD	CU YD
PIPE CULVERT TRENCH		216	162		+162
RIPRAP	130		98		+98
EAST OF SIDEWALK				203	-203
<b>TOTALS</b>	130	216	260	203	-57

EXCAVATION USED AS EMBANKMENT = (EARTH EXCAVATION+INCIDENTAL EXCAVATION)\*0.75

USER: MWS, 09/08/09  
TIME: 11:05:53 AM  
FILE: 71934-506\_CVL.dgn  
SCALE: 0.0000 / IN